# Transmission Expansion Advisory Committee – PSE&G Supplemental Projects

February 6th, 2024


TEAC – PSE&G Supplemental 1/9/2024

# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



## PSE&G Transmission Zone M-3 Process Deans – E Windsor – New Freedom 500kV Communications



**Need Number:** PSEG-2023-0013 **Process Stage:** Solutions Meeting 2/6/2024

Previously Presented: Need Meeting 12/5/2023

#### Supplemental Project Driver:

- Equipment Material Condition, Performance and Risk
- Operational Flexibility and Efficiency

#### Specific Assumption Reference:

PSE&G 2023 Annual Assumptions

• Equipment Criticality, Consequence of Failure

#### **Problem Statement:**

Existing communications equipment is currently power line carrier (PLC) on Deans – E Windsor and E Windsor – New Freedom 500kV. PLC equipment is affected during severe weather.

PJM Relay Subcommittee issued recommendations effective 4/17/2014 concerning Directional Comparison Blocking (DCB). The tolerance for overtrips may be unacceptable when the stability of large generating units is adversely affected.

A protection scheme more secure than DCB is recommended in cases where stability concerns are present.

Model: 2023 Series 2028 Summer RTEP 50/50



## PSE&G Transmission Zone M-3 Process Deans – E Windsor – New Freedom 500kV Communications

#### Need Number: PSEG-2023-0013

Process Stage: Solutions Meeting 2/6/2024

#### **Proposed Solution:**


- Construct new fiber path between New Freedom E Windsor Deans
  - Replace 53 miles of static wire on 5038 (New Freedom E Windsor) and 15 miles of static wire on 5022 (E Windsor - Deans)
  - o Upgrade line relay equipment and remove Power Line Carrier (PLC) equipment
  - This project will replace Project s0473
- Will be coordinated with JCPL-2023-064
- Estimated Cost: \$39.2M


#### Transmission Line Ratings:

- East Windsor Deans 5022 500 kV Line:
  - Before Proposed Solution: 2644/2844/2946/3106 MVA (SN/SE/WN/WE)
  - After Proposed Solution: 2940/3733/3618/4424 MVA (SN/SE/WN/WE)
- East Windsor New Freedom 5038 500 kV Line:
  - Before Proposed Solution: 2644/2844/2917/3106 MVA (SN/SE/WN/WE)
  - After Proposed Solution: 2940/3386/3478/3827 MVA (SN/SE/WN/WE)

#### Alternative Considered:

- Continued operation and maintenance of existing PLC based protective relaying scheme which may result in reliability impacts and higher maintenance costs.
- Projected In-Service: 12/2025 (5022/Deans) & 6/2027 (5038/N Freedom)
- Project Status: Conceptual






Original Scope presented at the September 13<sup>th</sup>, 2012 TEAC



- Replace static wire at the following location
  New Freedom – East Windsor – Deans 500 kV (S0473).
- Static Wire Replacement is an ongoing program that entails replacing aged tower static wires with a new approach, installing static wire with Optical Guide Wire (OPGW). This provides strength, lightning protection and a potential communications path for high speed relaying.
- Estimated Project Cost: \$ 20 M
- Expected IS Date: 6/1/2014

## **PSE&G** Transmission Zone



# Questions?



# Appendix

## High level M-3 Meeting Schedule

#### Assumptions

Activity	Timing
Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
Stakeholder comments	10 days after Assumptions Meeting

Needs

### Solutions

Submission of Supplemental Projects & Local Plan

Activity	Timing
TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
Stakeholder comments	10 days after Needs Meeting
Activity	Timina

Activity	типинд
TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
Stakeholder comments	10 days after Solutions Meeting

Activity	Timing
Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
Post selected solution(s)	Following completion of DNH analysis
Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

# **Revision History**

1/26/2024 - V1 – Original version posted to pjm.com