

Network Impacts

Potential network impacts for the injection of 7 MW into the existing Kearny 230 kV system was evaluated for summer peak conditions in 2005. The G8 project is using the existing capacity injection rights of Kearny Unit #12.

Normal System

- No identified problems.

Multiple Facility Contingency (MAAC Criteria IIC)

- No identified problems.

Generator Deliverability

- No identified problems.

Short Circuit Analysis

- No identified problems.

System Reinforcements

No new system reinforcements are required.