

**#R98 Northeast**  
**Generator Interconnection**

**Network Impacts**

The R98 project was studied as a **14 MW Capacity injection into the Northeast 230-kV circuit**. R98 was evaluated for compliance with reliability criteria for summer peak conditions in 2011. Potential network impacts for both scenarios were as follows:

**Generator Deliverability (Single Contingency)**

No problems identified.

**Multiple Facility Contingencies**

No problems identified.

**Local System Network Impacts**

No problems identified.

**Short Circuit Analysis**

No problems identified.

**Stability Analysis**

Not required for this project.

**New Network Upgrade Requirements**

None required.

**Contribution to Previously Identified Upgrade Requirements**

None required.