

***Generation Interconnection
Feasibility Study Report
Web Version***

For

***PJM Generation Interconnection Request
Queue Position W1-043***

Hubar Road 2

Overview

Interconnection Customer (IC) has submitted an Attachment N to propose the interconnection of a 20 MW of PV solar generation in Franklin County, Pennsylvania for the purpose of selling up to 20 MW energy and 7.6 MW of Capacity into the PJM market via the Allegheny Power network. The Commercial Operation date for this project was requested to be July 1, 2011. The analysis was performed using a 2014 base year. By virtue of the developer's seeking QF status, this is a FERC jurisdictional interconnection.

PJM Feasibility Analysis Report

Network Impacts

Queue project W1-043 was studied as a(n) 20.0MW (7.6MW of which was Capacity) injection into APS's system at the LeMasters Junction 34.5kV substation. Project W1-043 was evaluated for compliance with reliability criteria for summer peak conditions in 2014. Potential network impacts were as follows:

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

No problems identified.

Multiple Facility Contingency

(Double Circuit Tower Line Contingencies only with full energy output. Stuck Breaker and Bus Fault contingencies will be applied during the Impact Study)

No problems identified.

Contribution to Previously Identified Overloads

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have % allocation of cost responsibility which will be calculated and reported for the Impact Study.)

No problems identified.

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. "Network Impacts", initially caused by the addition of this project generation)

None.

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None.

Short Circuit

Not required by the Transmission Service Provider (PJM)

Energy Portion of Interconnection Request

PJM also studied the delivery of the energy portion of the surrounding generation. Any potential problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which analyzes all overload conditions associated with the overloaded element(s) identified. As a result of the aggregate energy resources in the area, the following violations were identified.

No problems identified.

APS Feasibility Study Report

This portion of this Feasibility Study Report has been prepared for PJM queue project W1-043 by Allegheny Power.

Injection into the Lemasters Jct. 34.5 kV Switching Station Attachment Facilities and Related Network Upgrades

- No new facilities are necessary, assuming all facilities for the W1-042 project have been installed.

While the information in this report is reasonable for the scope of work defined, it should, however, be noted that the cost figures are conceptual in nature at this stage, as an engineering team has not been assigned to the project. Obviously, any change to the scope of work will require that the estimates be revisited. The costs are a best estimate, but the IC will be charged for actual costs. Any under-runs or over-runs will be reconciled at the conclusion of the project. The estimates in this report do not include tax gross-up.

The IC will interconnect with the Allegheny Power (AP) system utilizing facilities constructed for the interconnection of W1-042 by connecting to the W1-042 main 34.5kV bus. It is assumed that the IC's main step up transformer will conform to the AP standard with delta on the low side and grounded wye on the high side as illustrated in the AP Engineering Manual:

http://www.alleghenypower.com/PowerQuality/Attachments/e1936_00.pdf.

Short Circuit(APS)

No breakers were identified as being over their maximum interrupting rating.

AP reserves the right to review the electrical protection design and relay settings for IC facilities to ensure that the protective relaying equipment will be compatible with that installed at the new switching station. The relaying package will likely include both primary and backup protection. AP personnel must be present at the time of commissioning to inspect and witness proper function of the control scheme and related coordination. The estimated cost to perform this engineering review and field test effort is **\$5,000 in 2012 dollars**.

Note: The purchase and installation of protective relaying and associated equipment at the generation site is the responsibility of the IC and is not included in this scope of work.

It is assumed that a fiber optic interface will be used for the protection channel between the AP and IC stations. The IC will be required to install metering and telemetry equipment to provide revenue metering and real-time telemetry data to PJM. The requirements for this equipment are listed in Appendix 2, Section 8 of Attachment O to the PJM Tariff, as well as PJM Manuals 01 and 14D. Protective relaying and metering design and installation must comply with the AP applicable standards.

Overloads and Required Reinforcements

1. During several contingencies, the local area experiences a voltage collapse. Furthermore, the addition of generation causes a large voltage deviation in the local area.
 - **Reinforcement:** Install a 25 MVAR 34.5kV SVC at Lemasters Jct. SS
 - **Estimated Cost:** \$3,827,845 in 2012 dollars
 - **Estimated Project Duration:** 21 months after receipt of an executed Interconnection Agreement and Construction Agreement.

Please note: the cost of this reinforcement will be shared with W1-042 and W1-050 (option 1).

2. The LEMASTER-MERCERSB 34.5kV line loads to 174% of its emergency rating (19.1 MVA) for the loss of the LEMASTER-ST. THOM 34.5kV line. This project contributes approximately 4.73 MW to this thermal violation.
 - **Reinforcement:** Reconductor the LEMASTER-MERCERSB line (3.8 miles) with 954 AAC conductor. Upgrade the terminal equipment at Mercersburg SS.
 - **Estimated Cost:** \$1,105,327 in 2012 dollars

- **Estimated Project Duration:** 21 months after receipt of an executed Interconnection Agreement and Construction Agreement.

Other Supporting Facilities Charge

The Other Supporting Facilities Charge (OSFC) may include non-transmission facilities directly assigned and/or a general (rolled-in) facilities charge. The guidelines apply to all wholesale customers and all generators selling into or through the PJM market, regardless of capacity, not connected directly to the AP Transmission System.

The Other Supporting Facilities Charge for the W1-043 generator interconnection project has been estimated to be **\$10,800/month** in 2010 dollars. The estimate is based on an average (or rolled-in) rate for West Penn's sub-transmission system.

Please note, during the impact study AP will perform a study of the effect of harmonics from solar inverters on its system, as well as a "time-based study" to determine any loading effects on its system (i.e. a passing cloud causing a change in area generation resulting in a voltage deviation). These studies may require the use of an external consultant.