

Inter-regional Update

- 2025 summer and winter scenario build – on schedule
 - June preliminary builds - **complete**
 - July-August validation and final case posting - **complete**
 - October transfer analysis – **in progress**
 - December presentation & stakeholder input – **in progress**
- TC & EC recommendations
 - construct validated production cost simulation model for EI transmission studies. **License issues under consideration**
 - NERC MOD 32 activity – continue to monitor

- NCTPC
 - Preparation for 2016/17 operating year September 30 meeting
 - Draft coordinated operating plan discussed. Day ahead and Real time activities
 - Agreed to more closely coordinate power flow model interchange
- PJM/MISO JOA
 - Quick Hit upgrades
 - Tracking RTEP and MTEP upgrades addressing \$300M congestion
 - Michigan Interface study light load issues in progress
 - Merged power flows
 - Coordinating market efficiency assumptions

- **PJM/MISO JOA**

- **Process Timeline**

- Review transmission issues 4Q15
- Data exchange 1Q16
- Identify M2M issues, limiting elements and potential upgrades 2Q16
- Identify regional issues – 3Q16
- Project solicitations September 2016 – February 2017
- Joint model development November 2016 – March 2017


- Process drives metric discussions
 - File to eliminate \$20 million threshold in 2015
 - Consider MISO lower voltage threshold
 - Consider “quick hit” process/metric enhancements
 - Economic project process enhancements, such as
 - Streamline and simplify evaluations and approvals
 - Number/scope of analyses
 - Use of B/C screening
 - Consider congestion relief metrics

MISO MEP Coordination

Newtonville – Coleman 161 kV congestion

Southern IN Focus Area

■ MISO boundary
■ State boundaries



- **Coordination on MISO MEP to relieve Newtonville – Coleman 161 kV congestion**
 - MISO staff recommends Duff – Rockport – Coleman option
 - PJM found Duff – Rockport – Coleman option is more effective solution to Rockport operational issues
 - MISO board recommendation expected in December
 - To be included in RTEP power flows moving forward
 - AEP intends to include the project as a supplemental RTEP upgrade

- All PJM analyses are complete
- Studied Rockport – Coleman 345 kV DCTL
- Studied Rockport – Duff – Coleman 345 kV
- Analyses
 - Power flow, Stability, Short Circuit
- Results
 - No issues identified for Rockport – Duff – Coleman
 - Rockport - Coleman DCTL is unstable for specific area generation outputs and unity power factor at Rockport



Newtonville – Coleman 161 kV congestion

- Rockport – Coleman DCTL alternative studies complete
 - MISO identified \$200 k reliability upgrades
 - Replaces Rockport SPS with minimal voltage limited operating guide required
 - No PJM thermal or voltage reliability issues identified
 - Administrative complexity for MISO - shared responsibility for double circuit tower line – cost sharing and competitive bid process
- Duff - Rockport – Coleman alternative studies complete
 - MISO identified \$200 k reliability upgrades
 - Eliminates Rockport SPS – no operating guide required
 - No PJM thermal or voltage reliability issues identified
 - Less administrative complexity

Network Upgrade	Duff – Coleman 345kV	Rockport – Coleman Double Circuit 345kV	Duff – Rockport - Coleman 345 kV
Total Project Cost (\$M)	\$67.2	\$111.5	\$152.5
MISO Portion of Cost (\$M)	\$67.2	\$56.9	\$67.2
PJM Portion of Cost (\$M)	NA	\$54.6	\$85.3
MISO B/C ratio	15.6	19.1	16.1
Network Upgrade Costs from Reliability No Harm Test	\$200K	\$200K	\$200K