

4.10 Other Related Studies Performed

4.10.1 Interim Deliverability Studies

4.10.1.1 Applicability

PJM performs interim deliverability studies for two reasons:

1. Projects that request to come into service prior to the base case study year in which they are studied and
2. Projects that request to come into service prior to the construction of a required system reinforcement (~~FC~~contingent ~~F~~facilities). Contingent ~~facilities~~ Facilities are identified in the latest System Impact Study or in either (i) Specifications, sSection 3.d or (ii) Schedule F of the GIA or ISA. Contingent Facilities may be Nnetwork Upgrades, baseline upgrades, or Ssupplemental Project upgrades.

These studies are performed in order to determine whether a project is deliverable for all or a portion of ~~their~~ its output.

4.10.1.2 Schedule for Interim Deliverability Studies

Consistent with PJM's governing documents, Requests ~~requests~~ inclusive of project name, location, Project Identifier and requested study output megawatt for interim deliverability studies for a particular Delivery Yyear shall be made a minimum of ~~ten~~ eleven months prior to the start of that Delivery Yyear and will be publicly posted. PJM will only consider projects for interim deliverability analysis if a Project Developer initiates a request to be studied for a particular Delivery Yyear. PJM intends to provide interim deliverability results eight months prior to the start of the Delivery Yyear.

4.10.1.3 Analysis for Interim Deliverability Studies

The interim deliverability study evaluates the system availability differently depending on the reason for the interim study. Projects requesting to come into service prior to the base case study year in which they were originally studied are evaluated against all violations. Projects that request to come into service prior to the construction of a needed ~~system reinforcement~~ Contingent Facility are only evaluated against the violations in which system reinforcement mediates.

The interim deliverability study results are only valid for the RPM auction Delivery Yyear ~~on for~~ which they were studied. The Delivery Yyear is defined as June 1st of the first year to May 31st of the following year (e.g., the Delivery Yyear for the 2024/25 3rd Incremental Auction is considered to be from June 1st 2024 to May 31st 2025). The base case used for the interim study will be based off of an RTEP case of the Delivery Yyear under study. The Provisional Interconnection Service granted through the interim deliverability study process will be publicly posted.

The flowgate loading for the interim deliverability study performed follows the Generator Deliverability Procedure detailed in C.3 of Manual 14B.

A project is considered fully deliverable if the project only contributes to flowgates with a post study loading less than 100% or has a MW contribution less than 1% of the line rating to an overloaded flowgate. A project is considered not deliverable if the MW contribution is 1% or greater of the line rating of a previously overloaded flowgate.

For flowgates that are not overloaded prior to the interim deliverability study but are overloaded at the end of the interim deliverability study, deliverable MW's will be determined via a cluster study methodology and will be allocated proportionally based on the project's MW impact to the flowgate and distribution factor (DFAX).

At PJM's discretion, PJM may allow Provisional Interconnection Service for projects with Ceontingent Ffacilities to operate as energy-only resources for a particular Ddelivery Tyear. During such periods, PJM reserves the right to deny Provisional Interconnection Service for projects or to limit total injections for projects consistent with the results of the interim deliverability study (which may be less than the Maximum Facility Output).

The interim deliverability study shall include any additional studies necessary to evaluate a New Services Requests eligibility for Provisional Interconnection Service.

Note:

- Even if a project is found to be deliverable or granted Provisional Interconnection Service for a particular Ddelivery Yyear, interim deliverability must be requested for each additional Delivery yYear that the conditions apply. An energy-only resource is eligible for Provisional Interconnection Service but not awarded Capacity Interconnection Rights.
- Projects operating under Provisional Interconnection Service will be dispatched consistent with all applicable operating procedures including, but not limited to, those established in M-12 and M-14D.

4.10.1.4 Eligibility Requirements for Interim Deliverability Studies

Requests for interim deliverability studies for a particular Ddelivery Yyear shall be made a minimum of ~~ten~~eleven months prior to the start of that Ddelivery Yyear. Only projects with an executed GIA or ISA or have confirmation from their PJM Project Manager that they ~~will~~are expected to receive a GIA ~~by prior to~~ the 3rd Incremental Auction ~~date~~ may participate in the interim deliverability study for that Ddelivery Yyear. Requests received after the start of the interim deliverability study will not be considered. Refer to PJM Capacity Market Manual 18, Section 4.2.4, for eligibility requirements to participating in a PJM RPM auction.