Subregional RTEP Committee – Mid-Atlantic FirstEnergy Supplemental Projects

February 13, 2025

Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process





Need Number: JCPL-2024-033

Process Stage: Solution Meeting SRRTEP-MA - 02/13/2025

Previously Presented: Need Meeting 05/16/2024


Project Driver: Customer Service **Specific Assumption References:**

New customer connection requests will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and

"Transmission Planning Criteria" document.

Problem Statement:

New Customer Connection – A retail customer requested 34.5 kV service for load of approximately 3 MVA near Werner Substation. Requested in-service date is 10/01/2024







Need number(s): JCPL-2024-033

Process Stage: Solution Meeting SRRTEP-MA - 02/13/2025

Proposed Solution:

Raritan River - Werner 34.5 kV U99 Line Customer Connection: Tap the Raritan River - Werner 34.5 kV U99 Line Extend tap line ~200 ft to customer Add SCADA controlled switches Modify relay settings at Raritan River Substation and Werner Substation. Estimated Cost: \$0.7 M


Transmission Cost Estimate: \$0.7 M

Alternatives Considered:


Alternative 34.5 kV lines were considered, but the U99 Line was selected due to its proximity to the customer.

Projected In-Service: 03/31/2025

Project Status: Conceptual



| Legend | |
|---------|--|
| 500 kV | |
| 345 kV | |
| 230 kV | |
| 138 kV | |
| 115 kV | |
| 69 kV | |
| 46 kV | |
| 34.5 kV | |
| 23 kV | |
| New | |





Need Number: JCPL-2024-035

Process Stage: Solution Meeting 02/13/2024

Previously Presented: Need Meeting 05/16/2024

Project Driver:

Customer Service


Specific Assumption Reference:

New customer connection requests will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.

Problem Statement:

New Customer Connection – A retail customer requested 34.5 kV service for load of approximately 1.5 MVA near Werner Substation.

Requested in-service date is 01/01/2025







Need number(s): JCPL-2024-035

Process Stage: Solution Meeting SRRTEP-MA - 02/13/2025

Proposed Solution:

Raritan River - Werner 34.5 kV U99 Line Customer Connection: Tap the Raritan River - Werner 34.5 kV U99 Line Extend tap line ~200 ft to customer Add SCADA controlled switches Modify relay settings at Raritan River

Substation and Werner Substation. Estimated Cost: \$0.5 M


Transmission Cost Estimate: \$0.5 M

Alternatives Considered:

Alternative 34.5 kV lines were considered, but the U99 Line was selected due to its proximity to the customer

Projected In-Service: 03/31/2025

Project Status: Conceptual



| Legend | | |
|---------|--|--|
| 500 kV | | |
| 345 kV | | |
| 230 kV | | |
| 138 kV | | |
| 115 kV | | |
| 69 kV | | |
| 46 kV | | |
| 34.5 kV | | |
| 23 kV | | |
| New | | |

Appendix

High level M-3 Meeting Schedule

| Assumptions |
|-------------|
|-------------|

| Activity | Timing |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments | 10 days after Assumptions Meeting |

Needs

| Activity | Timing |
|--|------------------------------|
| TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| Stakeholder comments | 10 days after Needs Meeting |

Solutions

| Activity | Timing |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments | 10 days after Solutions Meeting |

Submission of Supplemental Projects & Local Plan

| Activity | Timing |
|---|---|
| Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| Post selected solution(s) | Following completion of DNH analysis |
| Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

2/3/2025 – V1 – Original version posted to pjm.com 2/12/2025 – V2 – JCPL-2024-035 need slide corrected