# Subregional RTEP Committee – Mid-Atlantic FirstEnergy Supplemental Projects

March 13, 2025

# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



## Penelec Transmission Zone M-3 Process SGC Tap - Summit 46 kV Line

### Need Number: PN-2024-002

Process Stage: Solution Meeting SRRTEP-MA - 03/13/2025

### **Project Driver:**

**Operational Flexibility and Efficiency** 

Equipment Material Condition, Performance, and Risk

### **Specific Assumption Reference:**

System Performance Projects Global Factors

- System reliability and performance
- Substation and line equipment limits

### System Performance

Reconductor / Rebuild Transmission Line


### **Problem Statement:**

The Summit – SGC Tap section of the Summit – SGC Tap – Ashville 46 kV Line is 73 years old and 1.36 miles long.

Within the last five years, the line has experienced nine unscheduled outages due to a combination of storm damage, deteriorating cross-arms, and insulators. In addition, there have been five operational outages on this line to avoid thermal overloads.

The SGC Tap – Summit 46 kV Line section is currently limited by terminal equipment, including vintage electromechanical relaying.

Existing Ratings 26/33 MVA SN/SE 33/33 MVA WN/WE





Penelec Transmission Zone M-3 Process SGC Tap - Summit 46 kV Line

Need number(s): PN-2024-002

Process Stage: Solution Meeting SRRTEP-MA - 03/13/2025

**Proposed Solution:** 

**SGC Tap - Summit 46 kV Line:** -Rebuild approximately 1.36 miles of existing line. Estimated Cost: \$3.54 M


Transmission Cost Estimate: \$3.54 M

### **Alternatives Considered:**

Maintain existing condition with elevated risk of equipment failure.

Projected In-Service: 05/29/2026

Project Status: Conceptual



# Appendix

# High level M-3 Meeting Schedule

## Assumptions

| Activity                                      | Timing                             |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments                          | 10 days after Assumptions Meeting  |

## Needs

## Solutions

## Submission of Supplemental Projects & Local Plan

| Activity                                       | Timing                       |
|--|------------------------------|
| TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| Stakeholder comments                           | 10 days after Needs Meeting  |
|  |                              |

| Activity   | Timing                           |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments                               | 10 days after Solutions Meeting  |

| Activity  | Timing   |
|---|--|
| Do No Harm (DNH) analysis for selected solution       | Prior to posting selected solution   |
| Post selected solution(s)                             | Following completion of DNH analysis   |
| Stakeholder comments                                  | 10 days prior to Local Plan Submission for integration into RTEP                               |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after<br>posting of selected solutions |

# **Revision History**

03/03/2024 – V1 – Original version posted to pjm.com