

# Transmission Expansion Advisory Committee FirstEnergy Supplemental Projects

January 7, 2025

# Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Numbers:** APS-2024-071

**Process Stage:** Solution Meeting 01/07/2025

**Previously Presented:** Need Meeting 08/06/2024

**Project Driver:**

*Equipment Material Condition, Performance and Risk*

**Specific Assumption Reference:**

System Performance Projects Global Factors

- System reliability and performance

Add/Replace Transformers


Past System Reliability/Performance

**Problem Statement:**

- The Pruntytown No. 3 500/138 kV Transformer is approximately 48 years old and is approaching end of life.
- The transformer has experienced an increase in moisture content.
- The transformer parts and relaying are obsolete.
- The transformer and relaying equipment cannot be repaired due to a lack of replacement parts and available expertise in the outdated technology.
- Existing transformer ratings:
  - 430 / 552 MVA (SN / SSTE)
  - 505 / 585 MVA (WN / WSTE)

Continued on next slide...

## APS Transmission Zone M-3 Process Pruntytown No. 3 500/138 kV Transformer



# APS Transmission Zone M-3 Process Pruntytown No. 3 500/138 kV Transformer

**Need Number:** APS-2024-071

**Process Stage:** Solution Meeting 1/07/2025

## Proposed Solution:

- At Pruntytown Substation:
  - Replace the existing 500/138 kV Transformer No. 3
  - Replace transformer conductor, circuit breakers, disconnect switches and relaying

## Anticipated Transformer Circuit Ratings:

- 500/138 kV Transformer No. 3 :
  - Before Proposed Solution: 430 / 552 / 505 / 585 MVA (SN / SSTE / WN / WSTE)
  - After Proposed Solution (anticipated): 448 / 582 / 527 / 618 MVA (SN / SSTE / WN / WSTE)

## Alternatives Considered:

- Maintain the transformer with increased risk of failure.

**Estimated Project Cost:** \$ 15.77 M

**Projected In-Service:** 6/30/2029











**Project Status:** Conceptual

**Model:** 2024 RTEP model for 2029 Summer (50/50)

Pruntytown 138 kV



Pruntytown 500 kV

| Legend  |   |
|---------|---|
| 500 kV  |  |
| 345 kV  |  |
| 230 kV  |  |
| 138 kV  |  |
| 115 kV  |  |
| 69 kV   |  |
| 46 kV   |  |
| 34.5 kV |  |
| 23 kV   |  |
| New     |  |

# Re-Present Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

**Need Number:** APS-2023-029 (s3150.1, s3150.2)

**Process Stage:** Re-Present Solutions Meeting – 01/07/2025

**Previously Presented:** Solution Meeting – 02/06/2024  
Need Meeting – 7/11/2023

**Project Driver(s):**  
Customer Service


## Specific Assumption Reference(s)

New customer connection request will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.

## Problem Statement

New Customer Connection- A customer has requested 230 kV transmission service for approximately 300 MW of load near the Doubs-Sage #206 230 kV Line.

**Requested In-Service Date:** May 15, 2025





**Need Number:** APS-2023-029 (~~s3150.1~~, s3150.2)

**Process Stage:** ~~Re-Engineering~~ Re-Present Solutions Meeting – 01/07/2025

**Proposed Solution:**


- Build a six breaker, ~~two~~ **three** bay (expandable to four bays), breaker-and-a-half substation (Quantum 400)
- Loop the Doubs – Lime Kiln #231 230 kV Line in and out of the new substation
- Modify line relay settings at Doubs and Lime Kiln substations
- Provide two feeds to the customer facility

**Estimated Project Cost:** ~~\$20.8M~~ 23.2M

**Projected In-Service:** ~~09/01/2025~~ 12/31/2025

**Status:** ~~Pre-Engineering~~ Engineering

## APS Transmission Zone M-3 Process New Customer Lime Kiln



| Legend  |  |
|---------|--|
| 500 kV  |  |
| 230 kV  |  |
| 138 kV  |  |
| 69 kV   |  |
| 34.5 kV |  |
| 23 kV   |  |
| New     |  |





**Need Number:** APS-2023-029 (s3150.1, s3150.2)

**Process Stage:** Re-Present Solutions Meeting – 01/07/2025

**Proposed Solution:**

**230 kV Transmission Substation (Quantum 400)**

- Expand Quantum 400 station to a ~~nine~~ ten breaker, breaker-and-a-half substation
- Loop the Doubs – Sage #206 230 kV Line in and out of the new substation
- Modify line relay settings at Doubs and Sage substations

**Alternatives Considered:**


- No other feasible alternatives to serve the customer's load

**Estimated Project Cost:** ~~\$14.6M~~-\$8M

**Projected In-Service:** 12/31/2027 (coordinate with APS-2023-017)

**Status:** ~~Conceptual~~ Engineering

**Model:** 2028 RTEP case with 2022W3 solution



| Legend  |  |
|---------|--|
| 500 kV  |  |
| 230 kV  |  |
| 138 kV  |  |
| 69 kV   |  |
| 34.5 kV |  |
| 23 kV   |  |
| New     |  |



# Appendix

# High Level M-3 Meeting Schedule

## Assumptions

| Activity                                      | Timing                             |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments                          | 10 days after Assumptions Meeting  |

## Needs

| Activity                                       | Timing                       |
|--|------------------------------|
| TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| Stakeholder comments                           | 10 days after Needs Meeting  |

## Solutions

| Activity   | Timing                           |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments                               | 10 days after Solutions Meeting  |

## Submission of Supplemental Projects & Local Plan

| Activity  | Timing  |
|---|---|
| Do No Harm (DNH) analysis for selected solution       | Prior to posting selected solution  |
| Post selected solution(s)                             | Following completion of DNH analysis  |
| Stakeholder comments                                  | 10 days prior to Local Plan Submission for integration into RTEP                            |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

# Revision History

12/27/2024– V1 – Original version posted to pjm.com