

Sunbury - Susquehanna 500 kV line bifurcation and reroute through Kelayres 500 kV Station

General Information

Proposing entity name	Proprietary Information.
Does the entity who is submitting this proposal intend to be the Designated Entity for this proposed project?	Proprietary Information.
Company proposal ID	Proprietary Information.
PJM Proposal ID	317
Project title	Sunbury - Susquehanna 500 kV line bifurcation and reroute through Kelayres 500 kV Station
Project description	Bifurcate the Sunbury - Susquehanna 500 kV line bringing both segments into a new Kelayres 500 kV Station on separate towers. From the bifurcation point, build a 13-mile long extension to Kelayres, resulting in a Susquehanna - Kelayres 500 kV line. For this line extension, construct with Triple-Bundled 1590 kcmil 45/7 ACSR conductor. Double circuit this line with the Nescopeck - Tomhicken 230 kV line on existing PPL ROW. This line would replace the 12-mile Nescopeck - Harwood 230 kV line (a line already being constructed at 500 kV design standards in the Supplemental Project it is associated with. Construct approximately 1 additional mile of new 500 kV line between Harwood Substation and Kelayres Substation to complete the line route into Kelayres. From the bifurcation point, build a 24-mile long extension to Kelayres, resulting in a Sunbury - Kelayres 500 kV line. For this line extension, construct with Triple-Bundled 1113 kcmil 54/19 ACSS conductor following a path that is approximately 75% PPL EU Future-Use ROW, and 25% greenfield. Expand existing Slykerville 230 kV Station to add a 500 kV yard. Build a new Kelayres 500 kV breaker and a half substation with 3 bays, six 500 kV 4,000 amp circuit breakers, and twelve 500 kV 4,000 amp MODs. Add two 890 MVA 500/230 kV transformers at Kelayres (Slykerville 230 kV Station in Supplemental Project s3549.2 would be renamed Kelayres with the addition of this 500 kV yard).
Email	Proprietary Information.
Project in-service date	05/2030
Tie-line impact	No
Interregional project	No
Is the proposer offering a binding cap on capital costs?	Yes

Additional benefits

Proprietary Information.

Project Components

- 1. Kelayres 500 kV yard expansion
- 2. Susquehanna - Kelayres 500 kV line
- 3. Sunbury - Kelayres 500 kV line

Substation Upgrade Component

Component title	Kelayres 500 kV yard expansion		
Project description	Proprietary Information.		
Substation name	Slykerville		
Substation zone	PPL		
Substation upgrade scope	Expand existing Slykerville 230 kV Station to add a 500 kV yard. Build a new Kelayres 500 kV breaker and a half substation with 3 bays, six 500 kV 4,000 amp circuit breakers, and twelve 500 kV 4,000 amp MODs. Add two 890 MVA 500/230 kV transformers at Kelayres (Slykerville 230 kV Station in Supplemental Project s3549.2 would be renamed Kelayres with the addition of this 500 kV yard). Future site expandability to accommodate up to 5 breaker and a half bays in the 500 kV yard (planned to accommodate all lines from this Developer's various proposals that terminate into Kelayres in this window; proposals 2025-W1-769, 2025-W1-918, 2025-W1-855 or 2025-W1-317, and 2025-W1-434 or 2025-W1-946).		

Transformer Information

Transformer	Name		Capacity (MVA)
	Kelayres T1		890
	High Side	Low Side	Tertiary
Voltage (kV)	500	230	
Name		Capacity (MVA)	

Transformer	Kelayres T2	890	
	High Side	Low Side	Tertiary
Voltage (kV)	500	230	
New equipment description	Three breaker and a half bays (bay equipment all rated at 4,000 amps) Six 500 kV 4,000 amp circuit breakers Twelve 500 kV 4,000 amp MODs Two 890 MVA 500/230 kV transformers Future site expandability to accommodate up to 5 breaker and a half bays		
Substation assumptions	Site secured under Supplemental Project s3549.2. Space available for expansion on existing site.		
Real-estate description	No new real estate is required to accommodate this project.		
Construction responsibility	Proprietary Information.		
Benefits/Comments	Proprietary Information.		
Component Cost Details - In Current Year \$			
Engineering & design	Proprietary Information.		
Permitting / routing / siting	Proprietary Information.		
ROW / land acquisition	Proprietary Information.		
Materials & equipment	Proprietary Information.		
Construction & commissioning	Proprietary Information.		
Construction management	Proprietary Information.		
Overheads & miscellaneous costs	Proprietary Information.		
Contingency	Proprietary Information.		
Total component cost	\$72,920,345.00		
Component cost (in-service year)	\$85,415,283.51		
Transmission Line Upgrade Component			
Component title	Susquehanna - Kelayres 500 kV line		

Project description	Proprietary Information.	
Impacted transmission line	Nescopeck - Tomhicken 230 kV line, Nescopeck - Harwood 230 kV line (230 kV DCT lines)	
Point A	Nescopeck	
Point B	Harwood	
Point C		
Terrain description	To develop the Nescopeck - Kelayres 500 kV line, the 12-mile Nescopeck - Harwood 230 kV line (a line already being constructed at 500 kV design standards for Supplemental Project s3528.10) will be converted to 500 kV. Construct approximately 1 additional mile of new 500 kV line between Harwood Substation and Kelayres Substation to complete the line route into Kelayres.	
Existing Line Physical Characteristics		
Operating voltage	230	
Conductor size and type	Triple-Bundled 1590 ACSR	
Hardware plan description	Designed at 500 kV standards with assemblies and glass insulators.	
Tower line characteristics	Double circuit 500 kV construction on steel monopoles.	
Proposed Line Characteristics		
	Designed	Operating
Voltage (kV)	500.000000	500.000000
	Normal ratings	Emergency ratings
Summer (MVA)	2707.000000	3112.000000
Winter (MVA)	3207.000000	3566.000000
Conductor size and type	Triple-Bundled 1590 kcmil 45/7 ACSR conductor	
Shield wire size and type	OPGW	
Rebuild line length	12 miles	

Rebuild portion description	12 of the total 13 miles of the line involves upgrading one side of an existing double-circuit line to 500 kV.
Right of way	Developer intends to expand ROW between Harwood and Kelayres for the additional one mile of line.
Construction responsibility	Proprietary Information.
Benefits/Comments	Proprietary Information.
Component Cost Details - In Current Year \$	
Engineering & design	Proprietary Information.
Permitting / routing / siting	Proprietary Information.
ROW / land acquisition	Proprietary Information.
Materials & equipment	Proprietary Information.
Construction & commissioning	Proprietary Information.
Construction management	Proprietary Information.
Overheads & miscellaneous costs	Proprietary Information.
Contingency	Proprietary Information.
Total component cost	\$20,866,002.91
Component cost (in-service year)	\$24,441,403.21
Greenfield Transmission Line Component	
Component title	Sunbury - Kelayres 500 kV line
Project description	Proprietary Information.
Point A	Sunbury
Point B	Kelayres
Point C	

	Normal ratings	Emergency ratings
Summer (MVA)	3610.000000	4150.000000
Winter (MVA)	4276.000000	4755.000000
Conductor size and type	Triple-Bundled 1113 kcmil 54/19 ACSS conductor	
Nominal voltage	AC	
Nominal voltage	500	
Line construction type	Overhead	
General route description	The route traverses south from the Sunbury - Susquehanna line through Developer future-use ROW past Rock Glen towards Zion Grove. From Zion Grove to Kelayres the route traverses east through proposed greenfield corridor. Approximately 75% of the route is in existing PPL EU Future-Use ROW. The other 25% of the route will be greenfield ROW.	
Terrain description	The future-use segment of line traverses mountainous heavily-wooded terrain, then transitions to commercial industrial areas and warehousing near Harwood/Kelayres.	
Right-of-way width by segment	Developer proposes 200-foot ROW width for the project with ability to compress to 150 feet in pinch points.	
Electrical transmission infrastructure crossings	No major transmission infrastructure crossings	
Civil infrastructure/major waterway facility crossing plan	No major transmission infrastructure, highway, or river crossings.	
Environmental impacts	An extensive review of the proposed project alignment found that this proposed scope will require a suite of permits and agency consultations that are common for transmission development in this region of Pennsylvania. PPL anticipates needing to apply for a Individual Permit in compliance with the National Pollutant Discharge Elimination System as administered by the Pennsylvania Department of Environmental Protection PA DEP. We anticipate 6 stream and wetland crossings that will necessitate permitting under the PADEP, along with impacts to federally protected tree roosting bat species due to vegetation clearing activities that will be mitigated by time-of-year tree clearing restrictions. Based on our extensive work experience in the area, we anticipate anticipate 3-4 rounds of consultations with the PA Historical & Museum Commission regarding project impacts to prehistoric and historic resources, along with associated field surveys due to the presence of greenfield soils. Depending on the location of our final off-ROW temporary construction accesses the project may require approximately 10 PennDOT temporary driveway accesses and at least 1 overhead crossing of Interstate 81.	

Tower characteristics	Developer proposes a single-circuit 500 kV construction on monopole steel structures.
Construction responsibility	Proprietary Information.
Benefits/Comments	Proprietary Information.
Component Cost Details - In Current Year \$	
Engineering & design	Proprietary Information.
Permitting / routing / siting	Proprietary Information.
ROW / land acquisition	Proprietary Information.
Materials & equipment	Proprietary Information.
Construction & commissioning	Proprietary Information.
Construction management	Proprietary Information.
Overheads & miscellaneous costs	Proprietary Information.
Contingency	Proprietary Information.
Total component cost	\$133,635,827.51
Component cost (in-service year)	\$156,534,395.08

Congestion Drivers

None

Existing Flowgates

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-LLVD3	207967	LOFT	207967	LOFT	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD4	207966	BWAY	207966	BWAY	N/A	230	229	N-1 Voltage Drop	Included
2025W1-32GD-LL34	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N11-WVM207967	207967	LOFT	207967	LOFT	N/A	230	229	N-1-1 Voltage Magnitude	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N11-WVM20795	207969	TRES	207969	TRES	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N11-WVM20807	208072	SIEG	208072	SIEG	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N11-WVM20795	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N11-WVM20795	207963	SLYK	207963	SLYK	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N11-WVM20795	207966	BWAY	207966	BWAY	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-SVD71	211376	BELT 1	211376	BELT 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-32GD-LL39	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-SVD70	211377	BELT 2	211377	BELT 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-32GD-LL40	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-SVD69	211379	BELT	211379	BELT	N/A	69	229	N-1 Voltage Drop	Included
2025W1-32GD-LL41	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD5	207963	SLYK	207963	SLYK	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVD74	211347	WHCE	211347	WHCE	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD6	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1 Voltage Drop	Included
2025W1-32GD-LL36	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-SVD73	211366	ASHF TP2	211366	ASHF TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD7	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1 Voltage Drop	Included
2025W1-32GD-LL37	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-32GD-LL38	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD13	211161	SIEG	211161	SIEG	N/A	138	229	N-1 Voltage Drop	Included
2025W1-32GD-LL43	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD14	211007	NOEN TP2	211007	NOEN TP2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-32GD-LL44	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD15	211006	NOEN TP1	211006	NOEN TP1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD78	211336	WGAT 1	211336	WGAT 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD77	211337	WGAT 2	211337	WGAT 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD76	211345	WHCE 1	211345	WHCE 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD75	211346	WHCE 2	211346	WHCE 2	N/A	69	229	N-1 Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-SVD82	211268	TREI TP1	211268	TREI TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207963	207963	SLYK	207963	SLYK	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD20	210996	NHAM TP1	210996	NHAM TP1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD81	211270	TREI	211270	TREI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207960	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD21	210616	EGYP 2	210616	EGYP 2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD80	211272	TREI TP2	211272	TREI TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207959	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD22	210615	EGYP 1	210615	EGYP 1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD79	211273	TREI DC	211273	TREI DC	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD208072	208072	SIEG	208072	SIEG	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD16	211005	NOEN	211005	NOEN	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207969	207969	TRES	207969	TRES	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD17	210999	NHAM 2	210999	NHAM 2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD84	211160	SIEG	211160	SIEG	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207967	207967	LOFT	207967	LOFT	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD18	210998	NHAM 1	210998	NHAM 1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD83	211193	SSLA 2	211193	SSLA 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-SVD207966	207966	BWAY	207966	BWAY	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD19	210997	NHAM TP2	210997	NHAM TP2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N11-SVM208072	208072	SIEG	208072	SIEG	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-WVD63	210570	DRAG 2	210570	DRAG 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-ST49	207972	TOMH	207977	HARW	2	230	229	N-1-1 Thermal	Included
2025W1-N1-WVD64	210569	DRAG 1	210569	DRAG 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-ST50	207972	TOMH	207977	HARW	2	230	229	N-1-1 Thermal	Included
2025W1-N1-WVD65	210568	DRAG	210568	DRAG	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-ST51	207972	TOMH	207977	HARW	1	230	229	N-1-1 Thermal	Included
2025W1-N1-WVD66	210405	EPHA TI2	210405	EPHA TI2	N/A	69	229	Baseline Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N11-SVM207963	207963	SLYK	207963	SLYK	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-WVD59	210829	LIGA 1	210829	LIGA 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-SVM207966	207966	BWAY	207966	BWAY	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-WVD60	210828	LIGA 2	210828	LIGA 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-SVM207967	207967	LOFT	207967	LOFT	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-WVD61	210827	LIGA TAP	210827	LIGA TAP	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-SVM207969	207969	TRES	207969	TRES	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-WVD62	210601	EPAL	210601	EPAL	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-SVM207959	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N11-SVM207960	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-LLVM6	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-LLVM7	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVD49	211611	HIRU	211611	HIRU	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVM2	207969	TRES	207969	TRES	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-LLVM3	207967	LOFT	207967	LOFT	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVD47	211696	LEHI	211696	LEHI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVM4	207966	BWAY	207966	BWAY	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVD46	211697	LEHI TP	211697	LEHI TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVM5	207963	SLYK	207963	SLYK	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N11-ST52	207972	TOMH	207977	HARW	1	230	229	N-1-1 Thermal	Included
2025W1-N1-LLVM1	208072	SIEG	208072	SIEG	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N11-WVM207959	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1-1 Voltage Magnitude	Included
2025W1-N1-LLVD2	207969	TRES	207969	TRES	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVM4	207966	BWAY	207966	BWAY	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N11-WVD208072	208072	SIEG	208072	SIEG	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-SVM3	207967	LOFT	207967	LOFT	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVM2	207969	TRES	207969	TRES	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVM1	208072	SIEG	208072	SIEG	N/A	230	229	N-1 Voltage Magnitude	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-LLVD1	208072	SIEG	208072	SIEG	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVD64	211427	CARB	211427	CARB	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVM7	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N11-WVD207966	207966	BWAY	207966	BWAY	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-SVM6	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N11-WVD207967	207967	LOFT	207967	LOFT	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-SVM5	207963	SLYK	207963	SLYK	N/A	230	229	N-1 Voltage Magnitude	Included
2025W1-N1-SVD61	211446	CHRI TP	211446	CHRI TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-WVD207969	207969	TRES	207969	TRES	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-WVD41	211062	PSPA TP2	211062	PSPA TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD42	211057	PONO 1	211057	PONO 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD43	211056	PNWG TP2	211056	PNWG TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD44	211055	PNWG TP1	211055	PNWG TP1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD39	211193	SSLA 2	211193	SSLA 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD40	211160	SIEG	211160	SIEG	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD90	210405	EPHA TI2	210405	EPHA TI2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD91	210404	EPHA TI1	210404	EPHA TI1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD86	210601	EPAL	210601	EPAL	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD87	210570	DRAG 2	210570	DRAG 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD88	210569	DRAG 1	210569	DRAG 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD89	210568	DRAG	210568	DRAG	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD31	211949	WEIS	211949	WEIS	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD45	211054	PONO 2	211054	PONO 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-SVD30	211950	WEIS TP2	211950	WEIS TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD83	210757	KECE2TP1	210757	KECE2TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD46	211052	APRF TP	211052	APRF TP	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-SVD29	211951	WEIS TP1	211951	WEIS TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD84	210756	KECE1TP2	210756	KECE1TP2	N/A	69	229	N-1 Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-WVD47	211051	APRF	211051	APRF	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD85	210755	KECE1TP1	210755	KECE1TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD48	211031	PAZI	211031	PAZI	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD52	211021	PALM 1	211021	PALM 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD53	210972	NBET 2	210972	NBET 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD54	210971	NBET 1	210971	NBET 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD55	210914	MICK TP2	210914	MICK TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD49	211030	PAZI 2	211030	PAZI 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD50	211029	PAZI 1	211029	PAZI 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD51	211022	PALM 2	211022	PALM 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD56	210913	MICK 2	210913	MICK 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD57	210912	MICK 1	210912	MICK 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD58	210911	MICK TP1	210911	MICK TP1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N11-WVD207959	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N11-WVD207960	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD72	210913	MICK 2	210913	MICK 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD68	211021	PALM 1	211021	PALM 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD69	210972	NBET 2	210972	NBET 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD70	210971	NBET 1	210971	NBET 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD71	210914	MICK TP2	210914	MICK TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD64	211031	PAZI	211031	PAZI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD65	211030	PAZI 2	211030	PAZI 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD66	211029	PAZI 1	211029	PAZI 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD67	211022	PALM 2	211022	PALM 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N11-WVD207963	207963	SLYK	207963	SLYK	N/A	230	229	N-1-1 Voltage Drop	Included
2025W1-N1-LLVD63	211051	APRF	211051	APRF	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD30	211347	WHCE	211347	WHCE	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD31	211346	WHCE 2	211346	WHCE 2	N/A	69	229	Baseline Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-WVD32	211345	WHCE 1	211345	WHCE 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD33	211337	WGAT 2	211337	WGAT 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD29	211366	ASHF TP2	211366	ASHF TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD79	210761	KECE 1-1	210761	KECE 1-1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD80	210760	KECE 2-2	210760	KECE 2-2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD81	210759	KECE 2-1	210759	KECE 2-1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD82	210758	KECE2TP2	210758	KECE2TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD75	210829	LIGA 1	210829	LIGA 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD38	211268	TREI TP1	211268	TREI TP1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD76	210828	LIGA 2	210828	LIGA 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD77	210827	LIGA TAP	210827	LIGA TAP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD78	210762	KECE 1-2	210762	KECE 1-2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD34	211336	WGAT 1	211336	WGAT 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD35	211273	TREI DC	211273	TREI DC	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD73	210912	MICK 1	210912	MICK 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD36	211272	TREI TP2	211272	TREI TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD74	210911	MICK TP1	210911	MICK TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD37	211270	TREI	211270	TREI	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-SVD8	207963	SLYK	207963	SLYK	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVD7	207966	BWAY	207966	BWAY	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVD6	207967	LOFT	207967	LOFT	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-SVD5	207969	TRES	207969	TRES	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-WVD26	211379	BELT	211379	BELT	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD27	211377	BELT 2	211377	BELT 2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-SVD10	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-WVD28	211376	BELT 1	211376	BELT 1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-SVD9	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-WVD22	211696	LEHI	211696	LEHI	N/A	69	229	Baseline Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-WVD23	211611	HIRU	211611	HIRU	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD24	211446	CHRI TP	211446	CHRI TP	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD25	211427	CARB	211427	CARB	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD19	211950	WEIS TP2	211950	WEIS TP2	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD20	211949	WEIS	211949	WEIS	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD21	211697	LEHI TP	211697	LEHI TP	N/A	69	229	Baseline Voltage Drop	Included
2025W1-GD-S478	207973	FRAC	208072	SIEG	1	230	229	Generation Deliverability	Included
2025W1-N1-SVD107	210601	EPAL	210601	EPAL	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD45	211337	WGAT 2	211337	WGAT 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD3	207967	LOFT	207967	LOFT	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-SVD106	210827	LIGA TAP	210827	LIGA TAP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD46	211336	WGAT 1	211336	WGAT 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD105	210828	LIGA 2	210828	LIGA 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD47	211273	TREI DC	211273	TREI DC	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD48	211272	TREI TP2	211272	TREI TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD111	210405	EPHA TI2	210405	EPHA TI2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD110	210568	DRAG	210568	DRAG	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD109	210569	DRAG 1	210569	DRAG 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD43	211346	WHCE 2	211346	WHCE 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD1	208072	SIEG	208072	SIEG	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-SVD108	210570	DRAG 2	210570	DRAG 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD44	211345	WHCE 1	211345	WHCE 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD2	207969	TRES	207969	TRES	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-LLVD49	211270	TREI	211270	TREI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-32GD-S146	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD50	211268	TREI TP1	211268	TREI TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-32GD-S147	200022	SUSQ	208116	SUSQTR21	21	500/230	229	2032 Generation Deliverability	Included
2025W1-N1-LLVD51	211193	SSLA 2	211193	SSLA 2	N/A	69	229	N-1 Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-LLVD52	211190	SSLA 1	211190	SSLA 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD56	211062	PSPA TP2	211062	PSPA TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD57	211061	PSPA TP1	211061	PSPA TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD58	211057	PONO 1	211057	PONO 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD59	211056	PNWG TP2	211056	PNWG TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD53	211160	SIEG	211160	SIEG	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD54	211064	PSPA COL	211064	PSPA COL	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD55	211063	PSPA	211063	PSPA	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVD18	211951	WEIS TP1	211951	WEIS TP1	N/A	69	229	Baseline Voltage Drop	Included
2025W1-N1-WVD6	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-WVD7	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-WVD4	207966	BWAY	207966	BWAY	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-WVD5	207963	SLYK	207963	SLYK	N/A	230	229	Baseline Voltage Drop	Included
2025W1-N1-SVD4	208072	SIEG	208072	SIEG	N/A	230	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD60	211055	PNWG TP1	211055	PNWG TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD61	211054	PONO 2	211054	PONO 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD62	211052	APRF TP	211052	APRF TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD85	211062	PSPA TP2	211062	PSPA TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD23	210504	WIBR 2	210504	WIBR 2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD24	210503	WIBR 1	210503	WIBR 1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD25	210502	WIBR TP2	210502	WIBR TP2	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD26	210501	WIBR TP1	210501	WIBR TP1	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-SVD89	211054	PONO 2	211054	PONO 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD88	211055	PNWG TP1	211055	PNWG TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD87	211056	PNWG TP2	211056	PNWG TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD86	211057	PONO 1	211057	PONO 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD93	211030	PAZI 2	211030	PAZI 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD31	211698	LNFD	211698	LNFD	N/A	69	229	N-1 Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-SVD92	211031	PAZI	211031	PAZI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD32	211697	LEHI TP	211697	LEHI TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD91	211051	APRF	211051	APRF	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD90	211052	APRF TP	211052	APRF TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD27	210437	BLMO	210437	BLMO	N/A	138	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD28	211951	WEIS TP1	211951	WEIS TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD29	211950	WEIS TP2	211950	WEIS TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD94	211029	PAZI 1	211029	PAZI 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD30	211949	WEIS	211949	WEIS	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD96	211021	PALM 1	211021	PALM 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD34	211611	HIRU	211611	HIRU	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD95	211022	PALM 2	211022	PALM 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD35	211446	CHRI TP	211446	CHRI TP	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD36	211427	CARB	211427	CARB	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD37	211379	BELT	211379	BELT	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD100	210914	MICK TP2	210914	MICK TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVM4	207966	BWAY	207966	BWAY	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-WVM5	207963	SLYK	207963	SLYK	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-SVD98	210971	NBET 1	210971	NBET 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVM6	207960	EPAL TR2	207960	EPAL TR2	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-SVD97	210972	NBET 2	210972	NBET 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD33	211696	LEHI	211696	LEHI	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-WVM7	207959	EPAL TR1	207959	EPAL TR1	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-WVM1	208072	SIEG	208072	SIEG	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-WVM2	207969	TRES	207969	TRES	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-WVM3	207967	LOFT	207967	LOFT	N/A	230	229	Baseline Voltage Magnitude	Included
2025W1-N1-SVD104	210829	LIGA 1	210829	LIGA 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD42	211347	WHCE	211347	WHCE	N/A	69	229	N-1 Voltage Drop	Included

FG #	Fr Bus No.	From Bus Name	To Bus No.	To Bus Name	CKT	Voltage	TO Zone	Analysis type	Status
2025W1-N1-SVD103	210911	MICK TP1	210911	MICK TP1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD102	210912	MICK 1	210912	MICK 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-SVD101	210913	MICK 2	210913	MICK 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD38	211377	BELT 2	211377	BELT 2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD39	211376	BELT 1	211376	BELT 1	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD40	211366	ASHF TP2	211366	ASHF TP2	N/A	69	229	N-1 Voltage Drop	Included
2025W1-N1-LLVD41	211365	ASHF TP1	211365	ASHF TP1	N/A	69	229	N-1 Voltage Drop	Included

New Flowgates

Proprietary Information.

Financial Information

Capital spend start date 02/2026

Construction start date 03/2028

Project Duration (In Months) 51

Cost Containment Commitment

Cost cap (in current year) Proprietary Information.

Cost cap (in-service year) Proprietary Information.

Components covered by cost containment

1. Kelayres 500 kV yard expansion - PPL
2. Susquehanna - Kelayres 500 kV line - PPL
3. Sunbury - Kelayres 500 kV line - PPL

Cost elements covered by cost containment

Engineering & design	Yes
Permitting / routing / siting	Yes
ROW / land acquisition	Yes
Materials & equipment	Yes
Construction & commissioning	Yes
Construction management	Yes
Overheads & miscellaneous costs	Yes
Taxes	No
AFUDC	No
Escalation	Yes
Additional Information	Proprietary Information.
Is the proposer offering a binding cap on ROE?	No
Is the proposer offering a Debt to Equity Ratio cap?	Proprietary Information.

Additional Comments

None