

Sub Region RTEP Mid-Atlantic Committee DPL Supplemental Projects

March 20, 2019

Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: DPL-2019-0002

Process Stage: Solutions Meeting 03/20/2020

Previously Presented: Needs Meeting 6/28/2019


Project Driver: Equipment Material Condition, Performance and Risk

Specific Assumption Reference:

Transmission infrastructure replacements (EOL/condition/obsolescence) that are consistent with efficient asset management decisions

Problem Statement:

Grasonville Substation is in a deteriorated condition and has experienced flooding issues



Need Number: DPL-2019-0003

Process Stage: Solutions Meeting 03/20/2019

Previously Presented: Needs Meeting 10/21/2019


Project Driver: Customer Service

Specific Assumption Reference:

Address customer outage exposure

Problem Statement:

Customers in the Queenstown area historically experience poor service reliability due to high customer counts on feeders and minimal distribution automation capability. MD PSC has mandated that DPL improve reliability in the state.



Need Number: DPL-2019-0002, DPL-2019-0003

Process Stage: Solutions Meeting 03/20/2020

Proposed Solution:

- Construct new 4-breaker ring bus substation west of existing Grasonville Substation on Grasonville to Stevensville 69 kV line.
- Construct new 4-breaker ring bus substation west of existing Wye Mills Substation on Wye Mills to Stevensville 69 kV line.
- Retire existing Grasonville Substation.

Estimated Cost: \$13.5M


Alternatives Considered:

1. Construct new 4-breaker ring bus west of Wye Mills on Wye Mills-Stevensville 69 kV line, raise Grasonville Substation - \$10M
 - Leaves access issue to Grasonville Substation during flood events
 - Limits distribution automation capability
2. Construct new 4-breaker ring bus west of existing Grasonville Substation, retire Grasonville Substation - \$7M
 - Limits distribution automation capability

Projected In-Service: 6/1/2023

Project Status: Engineering

Model: PJM 2024 RTEP Model



Questions?



Appendix

High level M-3 Meeting Schedule

Assumptions	Activity	Timing
	Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
	Stakeholder comments	10 days after Assumptions Meeting
Needs	Activity	Timing
	TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
	Stakeholder comments	10 days after Needs Meeting
Solutions	Activity	Timing
	TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
	Stakeholder comments	10 days after Solutions Meeting
Submission of Supplemental Projects & Local Plan	Activity	Timing
	Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
	Post selected solution(s)	Following completion of DNH analysis
	Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
	Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

Revision History

3/10/2020 – V1 – Original version posted to pjm.com

3/11/2020 – V2 – Corrected the solution date on slide #4 and update map on slide #3