Sub-Regional RTEP Committee – Mid-Atlantic PPL Supplemental Projects September 14,2023

Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: PPL-2019-0007

Meeting Date: 09/14/2023


Process Stage: Need

Supplemental Project Driver: Equipment Material Condition, Performance and Risk;

Problem Statement:

The Lycoming – Williamsport #1 & #2 69kv lines are a reliability risk due to poor asset health. The lines are in poor condition with the original assets being installed in 1930. These are two single circuit lines at 1.75 and 2.1 miles, respectively. The lines have the original 2/0 and 4/0 Cu conductor and are primarily wood poles with steel poles interspersed. On the lines, 62 of the 88 poles are wood with the remainder steel. There have 3 outages on this line since 2015:

Cause	Momentary	Permanent	Total
Foreign Interference (Other utility)	1	0	1
Lightning	2	0	2
Grand Total	3	0	3



Need Number: PPL-2023-0007

Meeting Date: 09/14/2023

Process Stage: Need

Need Slide Presented: 05/18/2023


Supplemental Project Driver: Equipment Material Condition, Performance, and Risk.

Operational Flexibility and Efficiency.

Problem Statement:

The Sunbury-Lock Haven 69kV line is a reliability risk due to poor asset health. The line is in poor condition with the original assets installed in 1949. The line consists of 420 wood poles, 10 towers, and 349 steel poles. The 556 ACSR conductor was installed in 1971. The line has experienced 11 operations since 2017. Transfer capability is limited in the Lock Haven area due to the long line lengths (~40 miles) and the network operation. There is customer outage exposure when taking line sections out for maintenance.


Cause	Momentary	Permanent	Total
Foreign Interference (Animal)	2	0	2
Lightning	4	0	4
Vegetation	1	2	3
Failed AC Substation Equipment	1	0	1
Foreign Interference – Machinery	1	0	1
Grand Total	9	2	11



Need Number: PPL-2023-0009 Meeting Date: 09/14/2023 Process Stage: Need Supplemental Project Driver: Customer Service

Problem Statement:

PPL Distribution has submitted a request for a second 69kV feed at New Kingston Substation to feed a second 69-12kV transformer. There are several customers adding a combined load of 6.5 MW to New Kingston substation.



Need Number: PPL-2023-0010

Meeting Date: 09/14/2023


Process Stage: Need

Supplemental Project Driver: Equipment Material Condition, Performance and Risk;

Problem Statement:

The Hunlock-Glen Brook 69kV Line is a reliability risk due to poor asset health. The line is in poor condition with the original assets installed in 1929. The PPL section of this line is 4 miles long. The section to be rebuilt (3.5 miles) is the original 3/0 copper conductor and primarily wood poles with steel poles interspersed. In the section to be rebuilt, 90 of the 107 poles are wood with the remainder steel. There have been two outages on this section since 2015.

Cause	Momentary	Permanent	Total
Unknown	1	0	1
Vegetation	1	0	1
Grand Total	2	0	2



Need Number: PPL-2023-0011

Meeting Date: 09/14/2023


Process Stage: Need

Supplemental Project Driver: Equipment Material Condition, Performance and Risk;

Problem Statement:

The Selinsgrove 69kV tap is a reliability risk due to poor asset health. The line is in poor condition with the original assets installed in 1968. This is a 1.45 mile tap with the original 556 ACSR conductor and primarily wood poles with steel poles interspersed. On the tap, 30 of the 46 poles are wood with the remainder steel. There has been one outage on this section since 2015.

Cause	Momentary	Permanent	Total
Vegetation	0	1	1
Grand Total	0	1	1




Need Number: PPL-2023-0012 Meeting Date: 09/14/2023

Process Stage: Need

Supplemental Project Driver: Customer Service

Problem Statement:

• A customer has submitted a request to have their facility served from a 69kV transmission line in Frailey, PA. The load is approximately 10 MVA.



Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process

Need Number: PPL-2023-0008

Meeting Date: 09/14/2023


Process Stage: Solution

Need Slide Presented: 07/20/2023

Supplemental Project Driver: Equipment Material Condition, Performance and Risk;

Problem Statement:

The Buxmont 2 - Upper Hanover Tap 69kV Line is a reliability risk due to poor asset health. The line is in poor condition with the original assets installed in 1951. This is a 9.14 mile tap line with the original 2/0F copperweld copper conductor and is primarily H-frame wood poles with steel poles interspersed. 101 of the 155 poles in the line section are wood with 56 remaining from the original install. Nine structures have recently failed inspection. Since 2015, there have been 3 momentary outages and 1 permanent outage.



Need Number: PPL-2023-0008


Proposed Solution:

Rebuild the Buxmont 2 - Upper Hanover Tap 69kV line (~9.14 miles) to single circuit, future double circuit 69kV operation with 556 ACSR conductor.

Alternatives Considered:

1. Retirement of the line section would reduce operational flexibility and limit the ability to restore customers in the event of an outage.

Estimated Project Cost: \$18M Projected In-Service: 5/31/2026 Project Status: Conceptual Model: 2027





Appendix

High level M-3 Meeting Schedule

Assumptions

Activity	Timing
Posting of TO Assumptions Meeting information	20 days before Assumptions Meeting
Stakeholder comments	10 days after Assumptions Meeting

Needs

Solutions

Submission of Supplemental Projects & Local Plan

Activity	Timing
TOs and Stakeholders Post Needs Meeting slides	10 days before Needs Meeting
Stakeholder comments	10 days after Needs Meeting

Activity	Timing
TOs and Stakeholders Post Solutions Meeting slides	10 days before Solutions Meeting
Stakeholder comments	10 days after Solutions Meeting

Activity	Timing
Do No Harm (DNH) analysis for selected solution	Prior to posting selected solution
Post selected solution(s)	Following completion of DNH analysis
Stakeholder comments	10 days prior to Local Plan Submission for integration into RTEP
Local Plan submitted to PJM for integration into RTEP	Following review and consideration of comments received after posting of selected solutions

Revision History

9/01/2023 – V1 – Original version posted to pjm.com 9/25/2023 –V2 – Tables added on slides 3/4/6/7 for more information