Subregional RTEP Committee – Western FirstEnergy Supplemental Projects

August 18, 2023

Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



APS Transmission Zone M-3 Process Bedington – Marlowe BMA 138 kV Line New Customer

Need Number: APS-2023-030 Process Stage: Need Meeting – 08/18/2023

Supplemental Project Driver(s):

Customer Service

Specific Assumption Reference(s):


New customer connection request will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.

Problem Statement

New Customer Connection – Customer requested 138 kV transmission service for approximately 64 MVA of total load near the Bedington – Marlowe BMA 138 kV Line.

Requested In-Service Date:

2/28/2025





Need Number: APS-2023-039 Process Stage: Need Meeting – 08/18/2023

Supplemental Project Driver(s):

Customer Service

Specific Assumption Reference(s):

New customer connection request will be evaluated per FirstEnergy's "Requirements for Transmission Connected Facilities" document and "Transmission Planning Criteria" document.


Problem Statement

New Customer Connection – Potomac Edison Distribution has requested a new 138 kV delivery point near the Inwood – Stonewall 138 kV Line. The anticipated load of the new customer connection is 12 MVA.

Requested In-Service Date:

2/23/2024

APS Transmission Zone M-3 Process Inwood – Stonewall 138 kV Line New Customer





Need Number: APS-2023-040 Process Stage: Need Meeting 8/18/2023

Project Driver(s):

- Equipment Material Condition
- Performance and Risk

Specific Assumption Reference(s)

- Substation Condition Rebuild/Replacement
- Substation/line equipment limits


Problem Statement

- Existing switches at Millville Substation cannot be operated reliably.
 - Severe alignment issues result in improper closures, requiring a hammer to manually close, resulting in a safety issues
 - Switch mounting insulators often break during this process, resulting in live parts falling, creating potential safety incidents and system faults.

The Old Chapel – Millville 138 kV line is limited by terminal equipment

- Existing line rating:
 - 299/358/353/410 MVA (SN/SE/WN/WE)
- Existing conductor rating:
 - 353/406/353/428 MVA (SN/SE/WN/WE)

APS Transmission Zone M-3 Process Millville 138 kV Substation



Solutions

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



Need Number: APS-2023-027 Process Stage: Solution Meeting 8/18/2023 Previously Presented: Need Meeting 7/21/2023

Project Driver(s):

- Equipment Material Condition
- Performance and Risk


Specific Assumption Reference(s)

- Substation Condition Rebuild/Replacement
- Substation/line equipment limits

Problem Statement

- Existing switches are beyond reliable operation.
 - Severe alignment issues result in improper closures, requiring a hammer to manually close, resulting in a safety issues
 - Switch mounting insulators often break during this process, resulting in live parts falling, creating a potential accidents and system faults.
- The Boonsboro Marlowe 138 kV line is limited by Substation conductor
 - Existing line rating:
 - 300/358/349/410 MVA (SN/SE/WN/WE)
- The Bedington Marlowe 138 kV line is limited by Substation conductor
 - Existing line rating:
 - 265/349/349/410 MVA (SN/SE/WN/WE)

APS Transmission Zone M-3 Process Marlowe 138 kV Substation





APS Transmission Zone M-3 Process Marlowe 138 kV Substation

Paramount Ringgold Halfway Antietam Garfield Tap Cherry Run Catoctin East Hagerstown Marlowe R.P. Smith Harmony Jct. Tap Marlowe Nipetown Bedington rostown Jct. Boonsboro .__ Bedington Walkersville Boonsboro Eagle 5-arm FringMiles:k Shepherdstown Opequon Kearneysville Transmission Lines Substations Vanville Inwood Sleepy Hollow 0 Lovettsville Charles Town Millville Stonewall Subs Identified V Feagan's Mi

Need Number: APS-2023-027

Process Stage: Solution Meeting 08/18/2023

Proposed Solution:

- At Marlowe Substation:
 - On the Boonsboro 138 kV line exit, replace:
 - 1200 A manual disconnect switches with (2) 2000 A motor-operated disconnect switches
 - Limiting substation conductor
 - On the Bedington BMA 138 kV line exit, replace:
 - 1200 A manual disconnect switches with (2) 2000 A motor-operated disconnect switches
 - Limiting substation conductor

Transmission Line Ratings:

- Boonsboro Marlowe 138 kV Line
 - Before Proposed Solution: 300 / 358 / 349 / 410 MVA (SN / SE / WN / WE)
 - After Proposed Solution: 300 / 358 / 369 / 410 MVA (SN / SE / WN / WE)
- Bedington Marlowe BMA 138 kV Line
 - Before Proposed Solution: 265 / 349 / 349 / 410 MVA (SN / SE / WN / WE)
 - After Proposed Solution: 265 / 349 / 349 / 435 MVA (SN / SE / WN / WE)

Alternatives Considered:

No other solutions considered.

Estimated Project Cost: \$ 0.3 M

Projected In-Service: 10/27/2023

Project Status: Construction

Model: 2022 RTEP model for 2027 Summer (50/50)

Appendix

SRRTEP Committee: Western – FirstEnergy Supplemental 08/18/2023

High Level M-3 Meeting Schedule

Assumptions

| Activity | Timing |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments | 10 days after Assumptions Meeting |

Needs

Solutions

Submission of Supplemental Projects & Local Plan

| Activity | Timing |
|--|------------------------------|
| TOs and Stakeholders Post Needs Meeting slides | 10 days before Needs Meeting |
| Stakeholder comments | 10 days after Needs Meeting |

| Activity | Timing |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments | 10 days after Solutions Meeting |

| Activity | Timing |
|---|--|
| Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| Post selected solution(s) | Following completion of DNH analysis |
| Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

8/8/2023–V1 – Original version posted to pjm.com