# Transmission Expansion Advisory Committee –FirstEnergy (JCP&L) Supplemental Projects

May 11, 2021

### Solution

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



### JCP&L Transmission Zone M-3 Process Gillette – Traynor 230 kV Misoperation Relay Replacement

Need Number: JCPL-2019-015

Process Stage: Solution Meeting 5/11/2021

Previously Presented: Need Meeting 4/11/2019

**Project Driver:** 

Equipment Material Condition, Performance and Risk

Operational Flexibility and Efficiency

#### **Specific Assumption Reference:**

System Performance Projects Global Factors


- · System reliability and performance
- · Substation/line equipment limits
- Upgrade Relay Schemes
- Relay schemes that have a history of misoperation
- Obsolete and difficult to repair communication equipment (DTT, Blocking, etc.)
- Communication technology upgrades
- Bus protection schemes

#### **Problem Statement:**

- FirstEnergy has identified protection schemes using a certain vintage of relays and communication equipment that have a history of misoperation.
- Proper operation of the protection scheme requires all the separate components perform adequately during a fault.
- In many cases the protection equipment cannot be repaired due to a lack of replacement parts and available expertise in the outdated technology.
- Transmission line ratings are limited by terminal equipment.

Transmission line ratings are limited by terminal equipment. Gillette – Traynor 230 kV Line (substation conductor)

- Existing line rating: 678 / 813 MVA (SN / SE)
- Existing conductor rating: 709 / 869 MVA (SN / SE)





### JCP&L Transmission Zone M-3 Process Gillette – Traynor 230 kV Misoperation Relay Replacement

Need Number: JCPL-2019-015

**Process State:** Solutions Meeting 5/11/2021

**Proposed Solution:** 

Gillette 230 kV Substation:

Replace line relaying, line trap, and CCVT.

Replace substation conductor

Traynor 230 kV Substation:

Replace line relaying, line trap, and CCVT.

Replace substation conductor

#### **Transmission Line Ratings:**

Gillette – DOT Summit 230 kV Line

Before Proposed Solution: 678 / 802 MVA (SN/SE)

After Proposed Solution: 709 / 869 MVA (SN/SE)

DOT Summit – Traynor 230 kV Line

Before Proposed Solution: 678 / 813 MVA (SN/SE)

After Proposed Solution: 709 / 869 MVA (SN/SE)

#### **Alternatives Considered:**


None

**Estimated Project Cost: \$2M** 

**Projected In-Service:** 6/1/2021

**Project Status:** Construction

Model: 2020 RTEP model for 2025 Summer (50/50)



| Legend  |  |  |
|---------|--|--|
| 500 kV  |  |  |
| 345 kV  |  |  |
| 230 kV  |  |  |
| 138 kV  |  |  |
| 115 kV  |  |  |
| 69 kV   |  |  |
| 46 kV   |  |  |
| 34.5 kV |  |  |
| 23 kV   |  |  |
| New     |  |  |

## Questions?



# **Appendix**

## High level M-3 Meeting Schedule

| Assumptions      | Activity  | Timing  |  |
|------------------|---|---|--|
|                  | Posting of TO Assumptions Meeting information         | 20 days before Assumptions Meeting  |  |
|                  | Stakeholder comments                                  | 10 days after Assumptions Meeting   |  |
|                  |   |   |  |
| Needs            | Activity  | Timing  |  |
|                  | TOs and Stakeholders Post Needs Meeting slides        | 10 days before Needs Meeting  |  |
|                  | Stakeholder comments                                  | 10 days after Needs Meeting   |  |
|                  |   |   |  |
| Solutions        | Activity  | Timing  |  |
|                  | TOs and Stakeholders Post Solutions Meeting slides    | 10 days before Solutions Meeting  |  |
|                  | Stakeholder comments                                  | 10 days after Solutions Meeting   |  |
|                  |   |   |  |
| Submission of    | Activity  | Timing  |  |
| Supplemental     | Do No Harm (DNH) analysis for selected solution       | Prior to posting selected solution  |  |
| Projects & Local | Post selected solution(s)                             | Following completion of DNH analysis  |  |
| Plan             | Stakeholder comments                                  | 10 days prior to Local Plan Submission for integration into RTEP                            |  |
|                  | Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |  |

### **Revision History**

4/28/2021 – V1 – Original version posted to pjm.com