Transmission Expansion Advisory Committee – Penelec Supplemental Projects

January 11, 2022

Needs

Stakeholders must submit any comments within 10 days of this meeting in order to provide time necessary to consider these comments prior to the next phase of the M-3 process



Need Number: PN-2022-001

Process Stage: Need Meeting 1/11/2022

Project Driver:

Equipment Material Condition, Performance and Risk

Specific Assumption Reference:

Line Condition Rebuild/Replacement

- Age/condition of wood pole transmission line structures
- System characteristics including lightning and grounding performance, galloping overlap, insulation coordination, structural capacity needs, clearance margins, and future needs (e.g., fiber path)

System Performance Projects Global Factors

Substation/line equipment limits

Problem Statement:


The Piney – Grandview – Titusville – Union City – Erie South 115 kV line is exhibiting deterioration.

- Total line distance is approximately 82 miles.
- 556 out of 697 structures failed inspection (80% failure rate).
- Failure reasons include age, woodpecker damage, top rot, phase raised, failed sound test, and weatherization.

The design of the Glory – Trade City – Timblin – Piney 115 kV line is substandard.

- Total line distance is approximately 48 miles.
- Line was originally constructed in the 1930s for subtransmission operation and was later converted to 115 kV.
- The line is a worst performer for lightning strikes and phase-to-phase conductor contact despite the structures being modified in the 1970s for phase clearance and in approximately 2006 to raise the static wire.

Penelec Transmission Zone M-3 Process



Questions?



Appendix

High level M-3 Meeting Schedule

Assumptions

| Activity | Timing |
|---|------------------------------------|
| Posting of TO Assumptions Meeting information | 20 days before Assumptions Meeting |
| Stakeholder comments | 10 days after Assumptions Meeting |

Needs

Solutions

Submission of Supplemental Projects & Local Plan

| Timing |
|------------------------------|
| 10 days before Needs Meeting |
| 10 days after Needs Meeting |
| |

| Activity | Timing |
|--|----------------------------------|
| TOs and Stakeholders Post Solutions Meeting slides | 10 days before Solutions Meeting |
| Stakeholder comments | 10 days after Solutions Meeting |

| Activity | Timing |
|---|--|
| Do No Harm (DNH) analysis for selected solution | Prior to posting selected solution |
| Post selected solution(s) | Following completion of DNH analysis |
| Stakeholder comments | 10 days prior to Local Plan Submission for integration into RTEP |
| Local Plan submitted to PJM for integration into RTEP | Following review and consideration of comments received after posting of selected solutions |

Revision History

12/30/2021 - V1 – Original version posted to pjm.com 1/3/2022 – V2 – Corrected a typo on slide #1