

***Generation Interconnection
Feasibility Study Report***

For

***PJM Generation Interconnection Request
Queue Position AE1-051***

East Carbondale - Lackawanna 69kV

0 MW Energy / 10.0 MW Capacity

January 2019

Introduction

This Feasibility Study has been prepared in accordance with the PJM Open Access Transmission Tariff, 36.2, as well as the Feasibility Study Agreement between the Interconnection Customer (IC) and PJM Interconnection, LLC (PJM), Transmission Provider (TP). The Interconnected Transmission Owner (ITO) is PPL Electric Utilities (PPL EU).

Preface

The intent of the feasibility study is to determine a plan, with ballpark cost and construction time estimates, to connect the subject generation to the PJM network at a location specified by the Interconnection Customer. The Interconnection Customer may request the interconnection of generation as a capacity resource or as an energy-only resource. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: (1) Direct Connections, which are new facilities and/or facilities upgrades needed to connect the generator to the PJM network, and (2) Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system.

In some instances a generator interconnection may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection, may also contribute to the need for the same network reinforcement. The possibility of sharing the reinforcement costs with other projects may be identified in the feasibility study, but the actual allocation will be deferred until the impact study is performed.

The Feasibility Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer is responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

General

The IC has proposed an uprate to an existing wind-battery generating facility located Wayne County, Pennsylvania. The AE1-051 represents a request for an increase to the previous Z2-107/K-21/D-05 projects, which all share the same property and connection point. The Z2-107/K-21/D-05 projects have a capability of 74.5 MW with 9.0 MW being recognized as Capacity.

AE1-051 will maintain capability of 74.5 MW (no change from previous queue positions Z2-107/K21/D05) with a requested uprate of 10 MWC of additional output being recognized by PJM as Capacity.

The total capability of the previous Z2-107/K-21/D-05 projects and AE1-051 will be 74.5 MW with 19.0 MW of this output being recognized by PJM as Capacity. The proposed in-service date for this project is September 01, 2020. **This study does not imply a PPL EU commitment to this in-service date.** See AE1-051 project capability summary below:

	Maximum Facility Output (MW)	Capacity Interconnection Rights, (MW)
Existing Z2-107/K-21/D-05	74.5	9
Incremental MW under AE1-051	0	10
Total (Z2-107/K-21/D-05 + AE1-051)	74.5	19

Point of Interconnection (POI)

AE1-051 will interconnect with the PPL EU transmission system via the East Carbondale – Lackawanna 69kV line. The Point of Interconnection will be where the Customer Interconnection Facilities interconnect with the Transmission Owner Interconnection Facilities. Those specifications can be found below under the Interconnection Customer Requirements.

Cost Summary

Queue project AE1-051 will be responsible for the following estimated costs:

Description	Total Cost
Attachment Facilities	\$0
Direct Connection Network Upgrades	\$0
Non Direct Connection Network Upgrades	\$40,000
Total Costs	\$40,000

Estimated Schedule

The estimated time to complete the scope of work is 4-6 months after the PJM three-party Interconnection Service Agreement (ISA) and Interconnection Construction Service Agreement (ICSA) are signed and PPL EU receives Notice to Proceed from the IC.

Assumptions

- Availability of optimal transmission line route assumptions are not applicable for this uprate
- Outage feasibility not assessed until Facilities Study
- No major environmental, real estate, or permitting issues

Attachment Facilities

None

Direct Connection Network Upgrades

None

Non Direct Connection Network Upgrades

- Conduct a full relay settings analysis to determine sufficient system protection
 - Review of the existing IC relay settings and engineering package (submitted by IC to PPL EU)
 - Review settings of existing PPL IC IPR and POC protective relays
 - Model IC revised capacity in CAPE
 - Conduct a wide area short-circuit study two busses away from the IC facilities
 - Identify affected relays and revise settings as needed
 - Implement revised settings as needed
 - Perform system tests and checks to ensure revised settings functionality

The total preliminary cost estimate for the Non Direct Connection Upgrades is given in the table below. These costs do not include CIAC Tax Gross-up.

Description	Total Cost
Relay Settings Analysis, CAPE Revisions and Short Circuit Study	\$40,000
Total Non-Direct Connection Facility Costs	\$40,000

Interconnection Customer Requirements

Requirement from the PJM Open Access Transmission Tariff:

1. The Interconnection Customer may be required to install and/or pay for metering as necessary to properly track real time output of the facility as well as installing metering which shall be used for billing purposes. See Section 8 of Appendix 2 to the Interconnection Service Agreement as well as Section 4 of PJM Manual 14D for additional information.

PPL EU Interconnection Requirements

PPL EU applicable technical standards that address requirements for interconnection of generation, transmission, and end user facilities can be found at the following link:

<https://pjm.com/planning/design-engineering/to-tech-standards/private-ppl.aspx>

PPL EU Point(s) of Interconnection (POI) Requirements

AE1-051 will utilize the same POI of the previous Z2-107/K-21/D-05 projects. The POI is where the PPL EU tap line terminates (with insulators) at the first deadend structure inside the K21 IC substation. The scope of work provided in this Feasibility Study is for facilities to be constructed on the PPL EU side of the POI.

Revenue Metering and SCADA Requirements

PJM Requirements

The Interconnection Customer will be required to install equipment necessary to provide Revenue Metering (KWH, KVARH) and real time data (KW, KVAR) for IC's generating Resource. See PJM Manuals M-01 and M-14D, and PJM Tariff Sections 24.1 and 24.2.

PPL EU Requirements

Installation of revenue grade Bi-directional Metering Equipment will be required in the vicinity of the POI to measure kWh and kVARh. PPL EU will design and supply the required metering equipment; all installation costs would be borne by the IC including CTs/PTs. All metering equipment must meet applicable PPL EU tariff requirements as well as being compliant with all applicable requirements of the PJM agreements. The equipment must provide bidirectional revenue metering (kWh and kVARh) and real-time data (kW, kVAR, circuit breaker status, and generator bus voltages) for the IC's generating resource. The metering equipment should be housed in a control cabinet or similar enclosure and must be accessible to PPL EU metering personnel.

Network Impacts

The Queue Project AE1-051 was evaluated as a 0 MW (Capacity 10 MW) injection at EAST CARBONDALE-LACKAWANNA 69KV substation in the ITO region. Project AE1-051 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AE1-051 was studied with a commercial probability of 53%. Potential network impacts were as follows:

Summer Peak Analysis – 2022

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

Multiple Facility Contingency

(Double Circuit Tower Line contingencies were studied for the full energy output. The contingencies of Line with Failed Breaker and Bus Fault will be performed for the Impact Study.)

None

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

Steady-State Voltage Requirements

(Summary of the VAR requirements based upon the results of the steady-state voltage studies)

Not required

Short Circuit

(Summary of impacted circuit breakers)

New circuit breakers found to be over-duty:

None

Contributions to previously identified circuit breakers found to be over-duty:

None.

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. Network Impacts, initially caused by the addition of this project generation)

None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None

Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The IC can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

None

Light Load Analysis

Light Load Studies to be conducted during later study phases (as required by PJM Manual 14B)