



**Generation Interconnection
Feasibility Study Report
for
Queue Project AF2-304
SURRY-HOPEWELL 230 KV
89 MW Capacity / 150 MW Energy**

July 2020

Table of Contents

1	Introduction.....	4
2	Preface.....	4
3	General.....	5
4	Point of Interconnection.....	5
4.1	Primary Point of Interconnection	5
4.2	Secondary Point of Interconnection.....	5
5	Cost Summary	6
6	Transmission Owner Scope of Work.....	6
7	Schedule.....	7
8	Transmission Owner Analysis.....	8
8.1	Power Flow Analysis	8
9	Interconnection Customer Requirements.....	8
9.1	System Protection.....	8
9.2	Compliance Issues and Interconnection Customer Requirements	8
9.3	Power Factor Requirements.....	9
10	Revenue Metering and SCADA Requirements	9
10.1	PJM Requirements	9
10.2	Meteorological Data Reporting Requirements	9
10.3	Interconnected Transmission Owner Requirements.....	9
11	Summer Peak - Load Flow Analysis - Primary POI	10
11.1	Generation Deliverability	10
11.2	Multiple Facility Contingency	10
11.3	Contribution to Previously Identified Overloads.....	10
11.4	Potential Congestion due to Local Energy Deliverability.....	11
11.5	System Reinforcements - Summer Peak Load Flow - Primary POI.....	12
11.6	Flow Gate Details - Primary POI	13
11.6.1	Index 1	14
11.6.2	Index 2	18
11.6.3	Index 3	21
11.6.4	Index 4	24
11.6.5	Index 5	26

11.7	Queue Dependencies	28
11.8	Contingency Descriptions - Primary POI.....	30
12	Short Circuit Analysis - Primary POI.....	33
13	Summer Peak - Load Flow Analysis - Secondary POI	34
13.1	Generation Deliverability	34
13.2	Multiple Facility Contingency	34
13.3	Contribution to Previously Identified Overloads.....	34
13.4	Potential Congestion due to Local Energy Deliverability.....	35
13.5	Flow Gate Details - Secondary POI.....	37
13.5.1	Index 1	38
13.5.2	Index 2	41
13.5.3	Index 3	45
13.5.4	Index 4	47
13.5.5	Index 5	51
13.5.6	Index 6	56
13.5.7	Index 7	59
13.6	Contingency Descriptions - Secondary POI.....	61
14	Affected Systems	65
14.1	TVA.....	65
14.2	Duke Energy Progress.....	65

1 Introduction

This Feasibility Study has been prepared in accordance with the PJM Open Access Transmission Tariff, 36.2, as well as the Feasibility Study Agreement between the Interconnection Customer (IC), and PJM Interconnection, LLC (PJM), Transmission Provider (TP). The Interconnected Transmission Owner (ITO) is Dominion.

2 Preface

The intent of the feasibility study is to determine a plan, with ballpark cost and construction time estimates, to connect the subject generation to the PJM network at a location specified by the Interconnection Customer. The Interconnection Customer may request the interconnection of generation as a capacity resource or as an energy-only resource. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: (1) Direct Connections, which are new facilities and/or facilities upgrades needed to connect the generator to the PJM network, and (2) Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system.

In some instances a generator interconnection may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection, may also contribute to the need for the same network reinforcement. Cost allocation rules for network upgrades can be found in PJM Manual 14A, Attachment B. The possibility of sharing the reinforcement costs with other projects may be identified in the feasibility study, but the actual allocation will be deferred until the impact study is performed.

The Interconnection Customer seeking to interconnect a wind or solar generation facility shall maintain meteorological data facilities as well as provide that meteorological data which is required per Schedule H to the Interconnection Service Agreement and Section 8 of Manual 14D.

An Interconnection Customer with a proposed new Customer Facility that has a Maximum Facility Output equal to or greater than 100 MW shall install and maintain, at its expense, phasor measurement units (PMUs). See Section 8.5.3 of Appendix 2 to the Interconnection Service Agreement as well as section 4.3 of PJM Manual 14D for additional information.

The Feasibility Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer is responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

3 General

The Interconnection Customer (IC), has proposed a Solar; Storage generating facility located in Prince George County, Virginia. The installed facilities will have a total capability of 150 MW with 89 MW of this output being recognized by PJM as Capacity. The Capacity Interconnection Rights associated with this request are being transferred from the deactivated Hopewell James River Cogeneration unit. The proposed in-service date for this project is August 03, 2023. This study does not imply a TO commitment to this in-service date.

Queue Number	AF2-304
Project Name	SURRY-HOPEWELL 230 KV
State	Virginia
County	Prince George
Transmission Owner	Dominion
MFO	150
MWE	150
MWC	89
Fuel	Solar; Storage
Basecase Study Year	2023

Any new service customers who can feasibly be commercially operable prior to June 1st of the basecase study year are required to request interim deliverability analysis.

4 Point of Interconnection

4.1 Primary Point of Interconnection

AF2-304 will interconnect with the Dominion transmission system. The primary Point of Interconnection (POI) is a single line tap between Surry 230 kV substation and Hopewell 230 kV substation. The IC is responsible for securing right-of-way, permits and constructing the proposed attachment line from the storage facility site to the proposed new substation. Attachment 1 shows a one-line diagram of the proposed interconnection facilities. The IC may not install any facilities on Dominion’s right-of-way without first obtaining the necessary approval from Dominion Energy.

4.2 Secondary Point of Interconnection

The IC requested that a secondary POI of a single line tap between Colonial Pipeline 230 kV substation and Hopewell 230 kV substation be reviewed for network impacts. This report does not provide costs for the physical interconnection of the secondary point of interconnection. It was solely analyzed for network impacts. Results are shown in the “Summer Peak - Load Flow Analysis - Secondary POI” section of this report.

5 Cost Summary

The AF2-304 project will be responsible for the following costs:

Description	Total Cost
Total Physical Interconnection Costs	\$ 10,400,000
Total System Network Upgrade Costs	\$ 64,185,000
Total Costs	\$ 74,585,000

This cost excludes a Federal Income Tax Gross Up charges. This tax may or may not be charged based on whether this project meets the eligibility requirements of IRS Notice 88-129. If at a future date it is determined that the Federal Income Tax Gross charge is required, the Transmission Owner shall be reimbursed by the Interconnection Customer for such taxes.

Cost allocations for any System Upgrades will be provided in the System Impact Study Report.

6 Transmission Owner Scope of Work

Dominion assessed the impact of the proposed Queue Project AF2-304 was evaluated as a 89 MW Capacity (150.0 MW Energy) injection at a single line tap between Surry 230 kV substation and Hopewell 230 kV substation in the Dominion Transmission System, for compliance with NERC Reliability Criteria on Dominion Transmission System. The system was assessed using the summer 2023 AF2 case provided to Dominion by PJM. When performing a generation analysis, Dominion's main analysis will be load flow study results under single contingency (both normal and stressed system conditions). Dominion Criteria considers a transmission facility overloaded if it exceeds 94% of its emergency rating under normal and stressed system conditions. A full listing of Dominion's Planning Criteria and interconnection requirements can be found in the Company's Facility Connection Requirements which are publicly available at: <http://www.dominionenergy.com>.

The results of these studies evaluate the system under a limited set of operating conditions and do not guarantee the full delivery of the capacity and associated energy of this proposed generation facility under all operating conditions. NERC Planning and Operating Reliability Criteria allow for the re-dispatch of generating units to resolve projected and actual deficiencies in real time and planning studies. Specifically, in Planning Studies, NERC Planning Event 3 and 6 Contingency Conditions (Loss of generator, transmission circuit, transformer, shunt device, or Single Pole of a DC line followed by the loss of a generator, transmission circuit, transformer, shunt device or single pole of a DC line) allow for re-dispatch of generating units to resolve potential reliability deficiencies. For Dominion Planning Criteria the re-dispatch of generating units for these contingency conditions is allowed as long as the projected loading does not exceed 100% of a facility Load Dump Rating.

The required Attachment Facilities, Direct Connection and Non-Direct Connection work for the interconnection of the AF2-304 generation project to the Dominion Transmission System is detailed in the

following sections. The associated one-line with the generation project attachment facilities and primary direct and non-direct connection are shown in Attachment 1.

Note that the ITO findings were made from a conceptual review of this project. A more detailed review of the connection facilities and their cost will be identified in a future study phases. Further note that the cost estimate data contained in this document should be considered high level estimates since it was produced without a detailed engineering review. The applicant will be responsible for the actual cost of construction. ITO herein reserves the right to return to any issues in this document and, upon appropriate justification, request additional monies to complete any reinforcements to the transmission systems. The total physical interconnection costs is given in the table below:

Description	Total Cost
Attachment Facilities Substation (Metering)	\$600,000
Attachment Facilities Transmission (One span)	\$1,500,000
Build three breaker 230 kV Switching Station	\$6,500,000
Re-arrange existing section of Surry – Hopewell 230 kV	\$1,800,000
Total Physical Interconnection Costs	\$ 10,400,000

To accommodate the proposed AF2-304 Project, Dominion Energy will build a new three breaker 230 kV Switching Station, install one span of overhead 230 kV line to the point of interconnection (“POI”) including 230 kV interconnection metering, and re-arrange the existing section of the line between Surry and Hopewell 230 kV substations.

It is estimated to take 24-30 months to complete this work upon execution of an Interconnection Construction Service Agreement (ICSA). These preliminary cost estimates are based on typical engineering costs. A more detailed engineering cost estimates are normally done when the IC provides an exact site plan location for the generation substation during the Facility Study phase. See Attachment One.

7 Schedule

The schedule for the required Network Impact Reinforcements will be more clearly identified in future study phases. The estimate elapsed time to complete each of the required reinforcements is identified in the “System Reinforcements” section of the report.

8 Transmission Owner Analysis

8.1 Power Flow Analysis

PJM performed a power flow analysis of the transmission system using a 2023 summer peak load flow model and the results were verified by Dominion. Additionally, Dominion performed an analysis of its transmission system and no deficiencies were identified.

9 Interconnection Customer Requirements

9.1 System Protection

The IC must design its Customer Facilities in accordance with all applicable standards, including the standards in Dominion’s “Dominion Energy Electric Transmission Generator Interconnection Requirements” documented in Dominion’s Facility Interconnection Requirements “Exhibit C” located at:

<https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>. Preliminary Protection requirements will be provided as part of the Facilities Study. Detailed Protection Requirements will be provided once the project enters the construction phase.

9.2 Compliance Issues and Interconnection Customer Requirements

The proposed Customer Facilities must be designed in accordance with Dominion’s “Dominion’s Facility Interconnection Requirements” document located at: <https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>. In particular, the IC is responsible for the following:

1. The purchase and installation of a fully rated protection device (circuit breaker, circuit switcher, fuse) to protect the IC’s GSU transformer(s).
2. The purchase and installation of the minimum required Dominion generation interconnection relaying and control facilities as described in the System Protection noted above. This includes over/under voltage protection, over/under frequency protection, and zero sequence voltage protection relays.
3. The purchase and installation of supervisory control and data acquisition (“SCADA”) equipment to provide information in a compatible format to the Dominion Transmission System Control Center.
4. Compliance with the Dominion and PJM generator power factor and voltage control requirements.

The GSU(s) associated with the IC queue request shall meet the grounding requirements as noted in Dominion’s “Dominion’s Facility Interconnection Requirements” document located at:

<https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>.

The IC will also be required to meet all PJM, SERC, and NERC reliability criteria and operating procedures for standards compliance. For example, the IC will need to properly locate and report the over and under voltage and over and under frequency system protection elements for its units as well as the submission of the generator model and protection data required to satisfy the PJM and SERC audits. Failure to comply with

these requirements may result in a disconnection of service if the violation is found to compromise the reliability of the Dominion system.

9.3 Power Factor Requirements

The IC shall design its non-synchronous Customer Facility with the ability to maintain a power factor of at least 0.95 leading (absorbing VARs) to 0.95 lagging (supplying VARs) measured at the high-side of the facility substation transformer(s) connected to the Dominion transmission system.

10 Revenue Metering and SCADA Requirements

10.1 PJM Requirements

The Interconnection Customer will be required to install equipment necessary to provide Revenue Metering (KWH, KVARH) and real time data (KW, KVAR) for IC's generating Resource. See PJM Manuals M-01 and M-14D, and PJM Tariff Section 8 of Attachment O.

10.2 Meteorological Data Reporting Requirements

The solar generation facility shall provide the Transmission Provider with site-specific meteorological data including:

- Back panel temperature (Fahrenheit)
- Irradiance (Watts/meter²)
- Ambient air temperature (Fahrenheit) - (Accepted, not required)
- Wind speed (meters/second) – (Accepted, not required)
- Wind direction (decimal degrees from true north) – (Accepted, not required)

10.3 Interconnected Transmission Owner Requirements

See Section 3.4.6 “Metering and telecommunications” of Dominion’s “Dominion’s Facility Interconnection Requirements” document located at: <https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>.

11 Summer Peak - Load Flow Analysis - Primary POI

The Queue Project AF2-304 was evaluated as a 61.0 MW (Capacity 0.0 MW) injection tapping the Hopewell to Surry 230 kV line, Ckt. 2 in the Dominion area. For the primary POI, the Hopewell Units were included in the model and AF2-304 is modeled only as the additional energy (i.e. 61 MW Energy) because the primary POI is the same bus as the existing Hopewell James River units. Project AF2-304 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AF2-304 was studied with a commercial probability of 53.0 %. Potential network impacts were as follows:

11.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

11.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC D C	MW IMPACT
97805018	314525	6KINGFOR K	230.0	DVP	314522	6CHCKTU K	230.0	DVP	1	DVP_P4-2: 531T582	breaker	830.0	98.87	100.03	DC	9.69

11.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC D C	MW IMPACT
97804918	313896	6COLONIAL TR	230.0	DVP	314303	6HOPEWL L	230.0	DVP	1	DVP_P4-2: 240T2041	breaker	830.0	119.23	120.9	DC	13.77
97804919	313896	6COLONIAL TR	230.0	DVP	314303	6HOPEWL L	230.0	DVP	1	DVP_P4-2: 240TAB2-190	breaker	830.0	109.64	111.3	DC	13.79
97804700	314303	6HOPEWL L	230.0	DVP	314287	6CHESTF B	230.0	DVP	1	DVP_P4-2: 56372	breaker	549.0	201.3	203.99	DC	14.78
97804701	314303	6HOPEWL L	230.0	DVP	314287	6CHESTF B	230.0	DVP	1	DVP_P4-2: 228T268	breaker	549.0	186.43	190.76	DC	23.75
97804702	314303	6HOPEWL L	230.0	DVP	314287	6CHESTF B	230.0	DVP	1	DVP_P4-2: G5T228	breaker	549.0	161.65	165.98	DC	23.75
97804730	314303	6HOPEWL L	230.0	DVP	314286	6CHESTF A	230.0	DVP	1	DVP_P4-2: 211T2124	breaker	549.0	181.1	185.86	DC	26.12

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC/D C	MW IMPAC T
98579123	314538	6SURRY	230.0	DVP	314522	6CHCKTU K	230.0	DVP	1	DVP_P7-1: LN 223-226	tower	830.0	100.14	101.83	DC	13.99

11.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC/D C	MW IMPAC T
98091498	313896	6COLONIAL TR	230.0	DVP	314303	6HOPEWELL	230.0	DVP	1	960130 AF2-304 TAP 230 942551 AE2-270 230 1	operation	678.679992676	126.99	128.67	DC	11.33
98091072	314303	6HOPEWELL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	DVP_P 1-2: LN 211	operation	449.320007324	207.43	212.55	DC	22.94
98091078	314303	6HOPEWELL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	Base Case	operation	449.320007324	144.17	147.42	DC	14.58
98091113	314303	6HOPEWELL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P 1-2: LN 228	operation	449.320007324	197.47	202.75	DC	23.75
98091120	314303	6HOPEWELL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	Base Case	operation	449.320007324	129.33	132.72	DC	15.24
98091640	314525	6KINGFOR K	230.0	DVP	314522	6CHCKTU K	230.0	DVP	1	DVP_P 1-2: LN 531	operation	678.679992676	104.8	106.02	DC	8.29
98091607	314538	6SURRY	230.0	DVP	942550	AE2-270 TAP	230.0	DVP	2	DVP_P 1-2: LN 2197	operation	678.679992676	107.64	113.09	DC	36.87
98091305	925330	AB2-190 TAP	230.0	DVP	314303	6HOPEWELL	230.0	DVP	2	DVP_P 1-2: LN 2197	operation	678.679992676	147.17	151.75	DC	31.01
98091520	942550	AE2-270 TAP	230.0	DVP	960130	AF2-304 TAP	230.0	DVP	2	DVP_P 1-2: LN 2197	operation	678.679992676	118.9	124.34	DC	36.87
98091528	960130	AF2-304 TAP	230.0	DVP	925330	AB2-190 TAP	230.0	DVP	2	DVP_P 1-2: LN 2197	operation	678.679992676	118.9	123.48	DC	31.01

11.5 System Reinforcements - Summer Peak Load Flow - Primary POI

ID	Idx	Facility	Upgrade Description	Cost
97804918,97804919	2	6COLONIAL TR 230.0 kV - 6HOPEWLL 230.0 kV Ckt 1	<u>DVP</u> dom-205 (1327) : Rebuild 1.63 miles of 230 kV Line 2197 from Hopewell to Colonial Trail with 2-636 ACSR. Project Type : FAC Cost : \$2,445,000 Time Estimate : 30-36 Months	\$2,445,000
97804730	4	6HOPEWLL 230.0 kV - 6CHESTF A 230.0 kV Ckt 1	<u>DVP</u> b2922 (1079) : PJM Baseline Upgrade b2922. Rebuild 8 of 11 miles of 230kV Lines #211 and #228 to current standard with a summer emergency rating of 1046 MVA for rebuilt section. Proposed conductor is 2-636 ACSR. The baseline project has a projected in-service date of 12/01/2020. Project Type : FAC Cost : \$0 dom-074 (1163) : Rebuild 3 miles of 230 kV Line 228 from Hopewell to Chesterfield with 2-636 ACSR. Project Type : FAC Cost : \$7,500,000 Time Estimate : 30-36 Months	\$15,000,000
97804702,97804701,97804700	3	6HOPEWLL 230.0 kV - 6CHESTF B 230.0 kV Ckt 1	dom-075 (1164) : Rebuild 3 miles of 230 kV Line 211 from Hopewell to Chesterfield with 2-636 ACSR. Project Type : FAC Cost : \$7,500,000 Time Estimate : 30-36 Months	
97805018	1	6KINGFORK 230.0 kV - 6CHCKTUK 230.0 kV Ckt 1	<u>DVP</u> dom-216 (1338) : Rebuild 7.8 miles of 230 kV Line 289 from Kings Fork to Chuckatuck with 2-636 ACSR. Project Type : FAC Cost : \$11,700,000 Time Estimate : 30-36 Months	\$11,700,000
98579123	5	6SURRY 230.0 kV - 6CHCKTUK 230.0 kV Ckt 1	<u>DVP</u> dom-217 (1339) : Rebuild 23.36 miles of 230 kV Line 290 from Surry to Chuckatuck with 2-636 ACSR. Project Type : FAC Cost : \$35,040,000 Time Estimate : 36-40 Months	\$35,040,000
			TOTAL COST	\$64,185,000

11.6 Flow Gate Details - Primary POI

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

11.6.1 Index 1

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97805018	314525	6KINGFORK	DVP	314522	6CHCKTUK	DVP	1	DVP_P4-2: 531T582	breaker	830.0	98.87	100.03	DC	9.69

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314189	6PAPERMILL	-2.7380	Adder	-3.22
314539	3UNCAMP	1.7104	50/50	1.7104
314541	3WATKINS	0.4582	50/50	0.4582
314639	6TANGLEW	0.2490	50/50	0.2490
315073	1STONECA	-2.3005	Adder	-2.71
315115	1S HAMPT1	1.0389	50/50	1.0389
315294	1DOMTR10	5.1307	Adder	6.04
315605	6W1-029WIND	0.5695	50/50	0.5695
315611	6Z1-036WIND	4.3637	50/50	4.3637
315614	AA2-178 C	1.0057	50/50	1.0057
900672	V4-068 E	0.1407	Adder	0.17
901082	W1-029 E	22.1309	50/50	22.1309
907092	X1-038 E	4.2760	50/50	4.2760
913392	Y1-086 E	1.0154	Adder	1.19
916042	Z1-036 E (Suspended)	29.2369	50/50	29.2369
916192	Z1-068 E	0.5326	Adder	0.63
917122	Z2-027 E	0.6187	50/50	0.6187
917332	Z2-043 E	0.4811	Adder	0.57
917512	Z2-088 E OP1	1.2458	Adder	1.47
918492	AA1-063AE OP	1.5127	Adder	1.78
918512	AA1-065 E OP	1.9431	Adder	2.29
918532	AA1-067 E	0.2730	Adder	0.32
919152	AA1-139 E	2.4162	Adder	2.84
919692	AA2-053 E OP	1.2489	Adder	1.47
920042	AA2-088 E OP	5.1751	Adder	6.09
920672	AA2-174 E OP	0.1443	Adder	0.17
920692	AA2-178 E	2.4986	50/50	2.4986
923801	AB2-015 C OP	5.8860	50/50	5.8860
923802	AB2-015 E OP	4.8265	50/50	4.8265
923831	AB2-022 C	1.0646	Adder	1.25
923832	AB2-022 E	0.5732	Adder	0.67
924501	AB2-099 C (Suspended)	0.2681	Adder	0.32
924502	AB2-099 E (Suspended)	0.1149	Adder	0.14
924812	AB2-134 E OP	-7.7791	Adder	-9.15
925061	AB2-161 C O1 (Suspended)	1.4147	Adder	1.66
925062	AB2-161 E O1 (Suspended)	2.3083	Adder	2.72
925122	AB2-169 E	2.5644	Adder	3.02
925331	AB2-190 C	-11.8200	Adder	-13.91
925522	AC1-027 E	0.3180	Adder	0.37
925861	AC1-065 C	-1.5347	Adder	-1.81

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
926201	AC1-098 C	2.1285	Adder	2.5
926202	AC1-098 E	1.2681	Adder	1.49
926211	AC1-099 C	0.7133	Adder	0.84
926212	AC1-099 E	0.4189	Adder	0.49
926781	AC1-164 C	-11.2195	Adder	-13.2
927021	AC1-189 C	2.9245	Adder	3.44
927022	AC1-189 E	1.4568	Adder	1.71
927141	AC1-208 C	2.8584	Adder	3.36
927142	AC1-208 E	1.2692	Adder	1.49
932591	AC2-079 C O1	3.7229	50/50	3.7229
932592	AC2-079 E O1	6.0742	50/50	6.0742
932631	AC2-084 C	3.0343	Adder	3.57
932632	AC2-084 E	1.4945	Adder	1.76
932831	AC2-110 C	-0.6139	Adder	-0.72
932832	AC2-110 E	-1.0016	Adder	-1.18
933271	AC2-138 C	-0.2800	Adder	-0.33
933731	AC2-196 C	0.5775	Adder	0.68
933732	AC2-196 E	0.3846	Adder	0.45
933991	AD1-023 C	6.4975	Adder	7.64
933992	AD1-023 E	3.5373	Adder	4.16
934061	AD1-033 C	2.3926	Adder	2.81
934062	AD1-033 E	1.5951	Adder	1.88
934392	AD1-063 E	-0.4746	Adder	-0.56
934521	AD1-076 C	27.1205	Adder	31.91
934522	AD1-076 E	13.8097	Adder	16.25
934571	AD1-082 C	3.2241	Adder	3.79
934572	AD1-082 E	1.8392	Adder	2.16
935111	AD1-144 C	3.0750	50/50	3.0750
935112	AD1-144 E	1.6802	50/50	1.6802
936242	AD2-030 E	-0.6007	Adder	-0.71
936301	AD2-039 C	-0.6139	Adder	-0.72
936302	AD2-039 E	-1.0016	Adder	-1.18
936341	AD2-044 C	-0.0875	Adder	-0.1
936342	AD2-044 E	-0.0992	Adder	-0.12
936401	AD2-051 C O1	4.1939	Adder	4.93
936402	AD2-051 E O1	1.8008	Adder	2.12
936661	AD2-085 C	2.2089	50/50	2.2089
936662	AD2-085 E	3.6040	50/50	3.6040
937221	AD2-160 C O1	2.1130	Adder	2.49
937222	AD2-160 E O1	1.1080	Adder	1.3
937251	AD2-164 (Withdrawn : 06/30/2020)	-6.0834	Adder	-7.16
937541	AD2-215 C	3.1067	50/50	3.1067
937542	AD2-215 E	1.6485	50/50	1.6485
938031	AE1-004 C	-0.6139	Adder	-0.72
938171	AE1-026 C O1	15.7783	Adder	18.56
938172	AE1-026 E O1	4.1627	Adder	4.9
938221	AE1-035 C	1.0849	Adder	1.28
938222	AE1-035 E	0.5344	Adder	0.63
938531	AE1-072 C O1	6.8950	Adder	8.11
938532	AE1-072 E O1	3.5944	Adder	4.23
938771	AE1-103 C O1	2.5656	50/50	2.5656
938772	AE1-103 E O1	3.5429	50/50	3.5429

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
939311	AE1-162 C	-0.9682	Adder	-1.14
939423	AE1-174 BAT (Withdrawn : 06/16/2020)	0.6995	50/50	0.6995
940061	AE2-000BC O1	6.7014	Adder	7.88
940062	AE2-000BE O1	4.4676	Adder	5.26
940491	AE2-034 C	4.3726	50/50	4.3726
940492	AE2-034 E	1.8740	50/50	1.8740
940552	AE2-041 BAT	3.7220	Merchant Transmission	3.7220
941101	AE2-104 C O1	2.8654	50/50	2.8654
941102	AE2-104 E O1	4.5556	50/50	4.5556
941281	AE2-122 C O1	8.2133	Adder	9.66
941282	AE2-122 E O1	33.1427	Adder	38.99
941291	AE2-123 C O1	8.4407	Adder	9.93
941292	AE2-123 E O1	32.9152	Adder	38.72
941301	AE2-124 C O1	7.8992	Adder	9.29
941302	AE2-124 E O1	34.6606	Adder	40.78
941501	AE2-147 C	11.0043	50/50	11.0043
941502	AE2-147 E	7.3362	50/50	7.3362
941541	AE2-151 C	0.4917	Adder	0.58
941542	AE2-151 E	0.2647	Adder	0.31
942131	AE2-225 C	2.0525	50/50	2.0525
942132	AE2-225 E	1.3683	50/50	1.3683
942171	AE2-229 C	2.0525	50/50	2.0525
942172	AE2-229 E	1.3683	50/50	1.3683
942341	AE2-247 C	0.9529	50/50	0.9529
942342	AE2-247 E	1.3159	50/50	1.3159
942401	AE2-253 C	2.2225	Adder	2.61
942402	AE2-253 E	0.9985	Adder	1.17
942552	AE2-270 BAT	19.5180	50/50	19.5180
942851	AE2-304 C	0.4105	50/50	0.4105
942852	AE2-304 E	0.1596	50/50	0.1596
943171	AE2-346 C	0.6435	Adder	0.76
943172	AE2-346 E	0.2758	Adder	0.32
943461	AF1-017 C	0.8621	50/50	0.8621
943462	AF1-017 E	1.4067	50/50	1.4067
943472	AF1-018 BAT	3.7220	Merchant Transmission	3.7220
943611	AF1-032 C	1.6762	50/50	1.6762
943612	AF1-032 E	0.8894	50/50	0.8894
944581	AF1-123 C O1	14.5293	Adder	17.09
944582	AF1-123 E O1	33.2679	Adder	39.14
944591	AF1-124 C O1	14.5293	Adder	17.09
944592	AF1-124 E O1	33.2679	Adder	39.14
944601	AF1-125 C O1	14.5293	Adder	17.09
944602	AF1-125 E O1	33.2679	Adder	39.14
944871	AF1-152 C	3.6681	50/50	3.6681
944872	AF1-152 E	2.4454	50/50	2.4454
945363	AF1-201 BAT	3.4952	50/50	3.4952
945711	AF1-236 C O1	47.8698	50/50	47.8698
945712	AF1-236 E O1	78.1033	50/50	78.1033
957491	AF2-043 C	2.0525	50/50	2.0525
957492	AF2-043 E	1.3683	50/50	1.3683
957521	AF2-046 C	4.1768	Adder	9.27
957522	AF2-046 E	2.1009	Adder	4.66

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
957531	AF2-047 C	10.3902	50/50	10.3902
957532	AF2-047 E	5.2263	50/50	5.2263
957791	AF2-073 C (Withdrawn : 07/02/2020)	8.2114	50/50	8.2114
957792	AF2-073 E (Withdrawn : 07/02/2020)	5.2499	50/50	5.2499
957801	AF2-074 C (Withdrawn : 07/02/2020)	3.6495	50/50	3.6495
957802	AF2-074 E (Withdrawn : 07/02/2020)	2.3333	50/50	2.3333
957821	AF2-076 C O1	4.9881	50/50	4.9881
957822	AF2-076 E O1	3.3254	50/50	3.3254
957861	AF2-080 C	1.4077	Adder	3.12
957862	AF2-080 E	0.6241	Adder	1.39
957871	AF2-081 C O1	1.9920	Adder	4.42
957872	AF2-081 E O1	0.8537	Adder	1.9
958161	AF2-110 C	1.1813	50/50	1.1813
958162	AF2-110 E	1.8477	50/50	1.8477
959511	AF2-242	1.7464	Adder	3.88
959731	AF2-264 C	0.5519	Adder	1.23
959732	AF2-264 E	0.2718	Adder	0.6
960133	AF2-304 BAT	9.6892	50/50	9.6892
960361	AF2-327 C (Withdrawn : 07/22/2020)	0.5117	Adder	1.14
960362	AF2-327 E (Withdrawn : 07/22/2020)	0.1279	Adder	0.28
960831	AF2-374 C	0.2777	Adder	0.62
960832	AF2-374 E	0.4531	Adder	1.01
961091	AF2-400 C	0.3178	50/50	0.3178
961092	AF2-400 E	0.5215	50/50	0.5215
961111	AF2-402 C O1	0.2664	Adder	0.59
961112	AF2-402 E O1	0.4356	Adder	0.97
WEC	WEC	0.2230	Confirmed LTF	0.2230
LGEE	LGEE	0.4148	Confirmed LTF	0.4148
CPL	CPL	1.9084	Confirmed LTF	1.9084
CBM-W2	CBM-W2	8.0590	Confirmed LTF	8.0590
NY	NY	0.0907	Confirmed LTF	0.0907
CBM-W1	CBM-W1	8.4943	Confirmed LTF	8.4943
TVA	TVA	1.6282	Confirmed LTF	1.6282
O-066	O-066	1.5523	Confirmed LTF	1.5523
CBM-S2	CBM-S2	12.7160	Confirmed LTF	12.7160
CBM-S1	CBM-S1	9.2186	Confirmed LTF	9.2186
G-007	G-007	0.2444	Confirmed LTF	0.2444
MADISON	MADISON	0.3790	Confirmed LTF	0.3790
MEC	MEC	1.2871	Confirmed LTF	1.2871

11.6.2 Index 2

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804918	313896	6COLONIAL TR	DVP	314303	6HOPEWELL	DVP	1	DVP_P4-2: 240T2041	breaker	830.0	119.23	120.9	DC	13.77

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315073	1STONECA	-4.9401	Adder	-5.81
315116	1SURRY 1	32.8978	50/50	32.8978
315117	1GRAVELC	1.1529	50/50	1.1529
315119	1GRAVEL3	3.3420	50/50	3.3420
315120	1GRAVEL4	3.3848	50/50	3.3848
315121	1GRAVEL5	3.3420	50/50	3.3420
315122	1GRAVEL6	3.3809	50/50	3.3809
901082	W1-029 E	9.5233	Adder	11.2
913392	Y1-086 E	0.6842	Adder	0.8
916192	Z1-068 E	0.6779	Adder	0.8
917122	Z2-027 E	0.3246	Adder	0.38
919152	AA1-139 E	2.0854	Adder	2.45
923831	AB2-022 C	0.7173	Adder	0.84
923832	AB2-022 E	0.3862	Adder	0.45
924811	AB2-134 C OP	6.2609	50/50	6.2609
924812	AB2-134 E OP	35.6897	50/50	35.6897
925331	AB2-190 C	25.2907	50/50	25.2907
925332	AB2-190 E	10.8389	50/50	10.8389
925522	AC1-027 E	0.4169	Adder	0.49
926661	AC1-147 C	0.8910	Adder	1.05
926662	AC1-147 E	0.5233	Adder	0.62
927221	AC1-216 C O1	4.7801	50/50	4.7801
927222	AC1-216 E O1	21.7879	50/50	21.7879
932041	AC2-012 C	4.0306	Adder	4.74
932042	AC2-012 E	6.5762	Adder	7.74
933731	AC2-196 C	0.5968	Adder	0.7
933732	AC2-196 E	0.3975	Adder	0.47
934011	AD1-025 C	47.6200	50/50	47.6200
934012	AD1-025 E	28.2080	50/50	28.2080
934061	AD1-033 C	2.5336	Adder	2.98
934062	AD1-033 E	1.6891	Adder	1.99
935111	AD1-144 C	0.7313	Adder	0.86
935112	AD1-144 E	0.3996	Adder	0.47
935161	AD1-151 C O1	20.3229	50/50	20.3229
935162	AD1-151 E O1	13.5486	50/50	13.5486
936041	AD2-007 C	2.2748	50/50	2.2748
936042	AD2-007 E	1.5671	50/50	1.5671
936051	AD2-008 C	8.2905	50/50	8.2905
936052	AD2-008 E	18.0471	50/50	18.0471
937221	AD2-160 C O1	1.9165	Adder	2.25
937222	AD2-160 E O1	1.0050	Adder	1.18

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937251	AD2-164 (Withdrawn : 06/30/2020)	1.6250	Adder	1.91
937541	AD2-215 C	0.7389	Adder	0.87
937542	AD2-215 E	0.3921	Adder	0.46
938531	AE1-072 C O1	5.6597	Adder	6.66
938532	AE1-072 E O1	2.9504	Adder	3.47
939311	AE1-162 C	2.0568	50/50	2.0568
939312	AE1-162 E	1.3712	50/50	1.3712
940251	AE2-007 O1	66.4959	Adder	78.23
940891	AE2-078 C	2.6910	50/50	2.6910
940892	AE2-078 E	1.3862	50/50	1.3862
940901	AE2-079 C	2.6910	50/50	2.6910
940902	AE2-079 E	1.3862	50/50	1.3862
941281	AE2-122 C O1	10.1907	Adder	11.99
941282	AE2-122 E O1	41.1218	Adder	48.38
941291	AE2-123 C O1	10.4728	Adder	12.32
941292	AE2-123 E O1	40.8396	Adder	48.05
941301	AE2-124 C O1	9.4265	Adder	11.09
941302	AE2-124 E O1	41.3623	Adder	48.66
941501	AE2-147 C	4.7354	Adder	5.57
941502	AE2-147 E	3.1569	Adder	3.71
941591	AE2-156 O1	7.0023	Adder	8.24
942131	AE2-225 C	0.6740	Adder	0.79
942132	AE2-225 E	0.4493	Adder	0.53
942171	AE2-229 C	0.6740	Adder	0.79
942172	AE2-229 E	0.4493	Adder	0.53
942401	AE2-253 C	2.0158	Adder	2.37
942402	AE2-253 E	0.9056	Adder	1.07
942551	AE2-270	33.8715	50/50	33.8715
943611	AF1-032 C	0.5504	Adder	0.65
943612	AF1-032 E	0.2921	Adder	0.34
943621	AF1-033 C	2.6910	50/50	2.6910
943622	AF1-033 E	1.3862	50/50	1.3862
944501	AF1-115 C O1	8.1952	50/50	8.1952
944502	AF1-115 E O1	4.0364	50/50	4.0364
944581	AF1-123 C O1	14.1609	Adder	16.66
944582	AF1-123 E O1	32.4245	Adder	38.15
944591	AF1-124 C O1	14.1609	Adder	16.66
944592	AF1-124 E O1	32.4245	Adder	38.15
944601	AF1-125 C O1	14.1609	Adder	16.66
944602	AF1-125 E O1	32.4245	Adder	38.15
944871	AF1-152 C	1.5785	Adder	1.86
944872	AF1-152 E	1.0523	Adder	1.24
957491	AF2-043 C	0.3572	Adder	0.79
957492	AF2-043 E	0.2382	Adder	0.53
957631	AF2-057	0.7495	Adder	1.66
957711	AF2-065 C	17.2745	50/50	17.2745
957712	AF2-065 E	16.5970	50/50	16.5970
957821	AF2-076 C O1	0.8678	Adder	1.93
957822	AF2-076 E O1	0.5785	Adder	1.28
957871	AF2-081 C O1	1.7193	Adder	3.82
957872	AF2-081 E O1	0.7368	Adder	1.64
960101	AF2-301 C	2.4855	50/50	2.4855

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
960102	AF2-301 E	1.6570	50/50	1.6570
960132	AF2-304 E O1	13.7744	50/50	13.7744
WEC	WEC	0.0047	Confirmed LTF	0.0047
LGEE	LGEE	0.0137	Confirmed LTF	0.0137
CPL	CPL	0.6906	Confirmed LTF	0.6906
CBM-W2	CBM-W2	1.2121	Confirmed LTF	1.2121
NY	NY	0.2218	Confirmed LTF	0.2218
CBM-W1	CBM-W1	0.0125	Confirmed LTF	0.0125
TVA	TVA	0.3290	Confirmed LTF	0.3290
O-066	O-066	2.8762	Confirmed LTF	2.8762
CBM-S2	CBM-S2	4.2310	Confirmed LTF	4.2310
CBM-S1	CBM-S1	1.6614	Confirmed LTF	1.6614
G-007	G-007	0.4472	Confirmed LTF	0.4472
MADISON	MADISON	0.1835	Confirmed LTF	0.1835
MEC	MEC	0.1017	Confirmed LTF	0.1017

11.6.3 Index 3

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804700	314303	6HOPEWLL	DVP	314287	6CHESTF B	DVP	1	DVP_P4-2: 56372	breaker	549.0	201.3	203.99	DC	14.78

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315060	1CHESTF5 (Deactivation : 31/05/2023)	37.5742	Adder	44.2
315073	1STONECA	13.1251	50/50	13.1251
315074	1HOPCGN1 (Deactivation : 25/06/2019)	15.8253	50/50	15.8253
315075	1HOPCGN2 (Deactivation : 25/06/2019)	15.6203	50/50	15.6203
315076	1HOPPOLC	3.1307	50/50	3.1307
315077	1HOPHCF1	4.8935	50/50	4.8935
315078	1HOPHCF2	4.8935	50/50	4.8935
315079	1HOPHCF3	4.8935	50/50	4.8935
315080	1HOPHCF4	7.4287	50/50	7.4287
315116	1SURRY 1	23.2824	50/50	23.2824
315120	1GRAVEL4	2.3955	50/50	2.3955
315122	1GRAVEL6	2.3927	50/50	2.3927
916192	Z1-068 E	0.6279	Adder	0.74
919152	AA1-139 E	1.9477	Adder	2.29
924811	AB2-134 C OP	2.9915	50/50	2.9915
924812	AB2-134 E OP	17.0527	50/50	17.0527
925331	AB2-190 C	28.0896	50/50	28.0896
925332	AB2-190 E	12.0384	50/50	12.0384
925522	AC1-027 E	0.3850	Adder	0.45
926661	AC1-147 C	0.8045	Adder	0.95
926662	AC1-147 E	0.4725	Adder	0.56
927221	AC1-216 C O1	2.2840	50/50	2.2840
927222	AC1-216 E O1	10.4104	50/50	10.4104
932041	AC2-012 C	3.6396	Adder	4.28
932042	AC2-012 E	5.9382	Adder	6.99
933731	AC2-196 C	0.5668	Adder	0.67
933732	AC2-196 E	0.3775	Adder	0.44
934011	AD1-025 C	22.7531	50/50	22.7531
934012	AD1-025 E	13.4779	50/50	13.4779
934061	AD1-033 C	2.3976	Adder	2.82
934062	AD1-033 E	1.5984	Adder	1.88
935111	AD1-144 C	0.6248	Adder	0.74
935112	AD1-144 E	0.3414	Adder	0.4
935161	AD1-151 C O1	22.5720	50/50	22.5720
935162	AD1-151 E O1	15.0480	50/50	15.0480
936041	AD2-007 C	1.0869	50/50	1.0869
936042	AD2-007 E	0.7488	50/50	0.7488
936051	AD2-008 C	3.9613	50/50	3.9613
936052	AD2-008 E	8.6230	50/50	8.6230

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
936762	AD2-097 E	-4.6231	Adder	-5.44
937221	AD2-160 C O1	1.7988	Adder	2.12
937222	AD2-160 E O1	0.9433	Adder	1.11
937251	AD2-164 (Withdrawn : 06/30/2020)	1.6949	Adder	1.99
937541	AD2-215 C	0.6312	Adder	0.74
937542	AD2-215 E	0.3349	Adder	0.39
939311	AE1-162 C	1.3014	Adder	1.53
939312	AE1-162 E	0.8676	Adder	1.02
940251	AE2-007 O1	60.7387	Adder	71.46
940542	AE2-040 BAT	1.5771	Merchant Transmission	1.5771
940891	AE2-078 C	1.6591	Adder	1.95
940892	AE2-078 E	0.8547	Adder	1.01
940901	AE2-079 C	1.6591	Adder	1.95
940902	AE2-079 E	0.8547	Adder	1.01
941281	AE2-122 C O1	9.4573	Adder	11.13
941282	AE2-122 E O1	38.1623	Adder	44.9
941291	AE2-123 C O1	9.7191	Adder	11.43
941292	AE2-123 E O1	37.9004	Adder	44.59
941301	AE2-124 C O1	8.7739	Adder	10.32
941302	AE2-124 E O1	38.4988	Adder	45.29
941591	AE2-156 O1	6.3521	Adder	7.47
942151	AE2-227 C	0.7603	Adder	0.89
942152	AE2-227 E	0.5069	Adder	0.6
942401	AE2-253 C	1.8920	Adder	2.23
942402	AE2-253 E	0.8501	Adder	1.0
942551	AE2-270	36.1035	50/50	36.1035
943621	AF1-033 C	1.6591	Adder	1.95
943622	AF1-033 E	0.8547	Adder	1.01
944501	AF1-115 C O1	5.0527	Adder	5.94
944502	AF1-115 E O1	2.4887	Adder	2.93
944581	AF1-123 C O1	14.3997	Adder	16.94
944582	AF1-123 E O1	32.9712	Adder	38.79
944591	AF1-124 C O1	14.3997	Adder	16.94
944592	AF1-124 E O1	32.9712	Adder	38.79
944601	AF1-125 C O1	14.3997	Adder	16.94
944602	AF1-125 E O1	32.9712	Adder	38.79
944631	AF1-128 O1	29.2405	Adder	34.4
946012	AF1-266 BAT	9.4801	Merchant Transmission	9.4801
957631	AF2-057	0.6768	Adder	1.5
957711	AF2-065 C	18.4128	50/50	18.4128
957712	AF2-065 E	17.6907	50/50	17.6907
957871	AF2-081 C O1	1.6058	Adder	3.56
957872	AF2-081 E O1	0.6882	Adder	1.53
958142	AF2-108 BAT	1.3579	50/50	1.3579
959641	AF2-255 C	0.1007	Adder	0.22
959642	AF2-255 E	0.0672	Adder	0.15
960101	AF2-301 C	0.8591	Adder	1.91
960102	AF2-301 E	0.5727	Adder	1.27
960132	AF2-304 E O1	14.7791	50/50	14.7791
LGEE	LGEE	0.0068	Confirmed LTF	0.0068
CPLE	CPLE	0.7111	Confirmed LTF	0.7111
CBM-W2	CBM-W2	1.3186	Confirmed LTF	1.3186

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
NY	NY	0.2959	Confirmed LTF	0.2959
TVA	TVA	0.3724	Confirmed LTF	0.3724
O-066	O-066	3.8304	Confirmed LTF	3.8304
CBM-S2	CBM-S2	4.7338	Confirmed LTF	4.7338
CBM-S1	CBM-S1	1.8659	Confirmed LTF	1.8659
TILTON	TILTON	0.0013	Confirmed LTF	0.0013
G-007	G-007	0.5959	Confirmed LTF	0.5959
MADISON	MADISON	0.2197	Confirmed LTF	0.2197
MEC	MEC	0.0953	Confirmed LTF	0.0953

11.6.4 Index 4

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804730	314303	6HOPEWLL	DVP	314286	6CHESTF A	DVP	1	DVP_P4-2: 211T2124	breaker	549.0	181.1	185.86	DC	26.12

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315073	1STONECA	24.1256	50/50	24.1256
315074	1HOPCGN1 (Deactivation : 25/06/2019)	29.0889	50/50	29.0889
315075	1HOPCGN2 (Deactivation : 25/06/2019)	28.7119	50/50	28.7119
315076	1HOPPOLC	5.7546	50/50	5.7546
315077	1HOPHCF1	8.9949	50/50	8.9949
315078	1HOPHCF2	8.9949	50/50	8.9949
315079	1HOPHCF3	8.9949	50/50	8.9949
315080	1HOPHCF4	13.6549	50/50	13.6549
315116	1SURRY 1	38.2271	50/50	38.2271
315120	1GRAVEL4	3.9331	50/50	3.9331
315122	1GRAVEL6	3.9286	50/50	3.9286
924811	AB2-134 C OP	5.2848	50/50	5.2848
924812	AB2-134 E OP	30.1257	50/50	30.1257
925331	AB2-190 C	49.8770	50/50	49.8770
925332	AB2-190 E	21.3758	50/50	21.3758
926661	AC1-147 C	1.0430	Adder	1.23
926662	AC1-147 E	0.6126	Adder	0.72
927221	AC1-216 C O1	4.0349	50/50	4.0349
927222	AC1-216 E O1	18.3912	50/50	18.3912
932041	AC2-012 C	4.7185	Adder	5.55
932042	AC2-012 E	7.6987	Adder	9.06
934011	AD1-025 C	40.1961	50/50	40.1961
934012	AD1-025 E	23.8104	50/50	23.8104
935111	AD1-144 C	0.8595	Adder	1.01
935112	AD1-144 E	0.4696	Adder	0.55
935161	AD1-151 C O1	40.0797	50/50	40.0797
935162	AD1-151 E O1	26.7198	50/50	26.7198
936041	AD2-007 C	1.9202	50/50	1.9202
936042	AD2-007 E	1.3228	50/50	1.3228
936051	AD2-008 C	6.9980	50/50	6.9980
936052	AD2-008 E	15.2335	50/50	15.2335
937541	AD2-215 C	0.8684	Adder	1.02
937542	AD2-215 E	0.4608	Adder	0.54
939311	AE1-162 C	2.0341	Adder	2.39
939312	AE1-162 E	1.3561	Adder	1.6
940251	AE2-007 O1	77.8376	Adder	91.57
940891	AE2-078 C	2.6455	Adder	3.11
940892	AE2-078 E	1.3628	Adder	1.6
940901	AE2-079 C	2.6455	Adder	3.11
940902	AE2-079 E	1.3628	Adder	1.6

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
941591	AE2-156 O1	8.1966	Adder	9.64
942551	AE2-270	63.7515	50/50	63.7515
943621	AF1-033 C	2.6455	Adder	3.11
943622	AF1-033 E	1.3628	Adder	1.6
944501	AF1-115 C O1	8.0566	Adder	9.48
944502	AF1-115 E O1	3.9682	Adder	4.67
957631	AF2-057	0.8775	Adder	1.95
957711	AF2-065 C	32.5133	50/50	32.5133
957712	AF2-065 E	31.2382	50/50	31.2382
960101	AF2-301 C	1.2807	Adder	2.84
960102	AF2-301 E	0.8538	Adder	1.9
960132	AF2-304 E O1	26.1202	50/50	26.1202
LGEE	LGEE	0.0029	Confirmed LTF	0.0029
CPL	CPL	1.0478	Confirmed LTF	1.0478
CBM-W2	CBM-W2	1.6298	Confirmed LTF	1.6298
NY	NY	0.3650	Confirmed LTF	0.3650
TVA	TVA	0.4676	Confirmed LTF	0.4676
O-066	O-066	4.7242	Confirmed LTF	4.7242
EDWARDS	EDWARDS	0.0007	Confirmed LTF	0.0007
CBM-S2	CBM-S2	6.3869	Confirmed LTF	6.3869
CBM-S1	CBM-S1	2.3260	Confirmed LTF	2.3260
TILTON	TILTON	0.0076	Confirmed LTF	0.0076
G-007	G-007	0.7332	Confirmed LTF	0.7332
MADISON	MADISON	0.2843	Confirmed LTF	0.2843
MEC	MEC	0.1081	Confirmed LTF	0.1081
BLUEG	BLUEG	0.0069	Confirmed LTF	0.0069
TRIMBLE	TRIMBLE	0.0056	Confirmed LTF	0.0056

11.6.5 Index 5

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
98579123	314538	6SURRY	DVP	314522	6CHCKTUK	DVP	1	DVP_P7-1: LN 223-226	tower	830.0	100.14	101.83	DC	13.99

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314539	3UNCAMP	-0.8117	Adder	-0.95
314541	3WATKINS	-0.2170	Adder	-0.26
315060	1CHESTF5 (Deactivation : 31/05/2023)	14.9896	Adder	17.63
315073	1STONECA	3.5033	Adder	4.12
315074	1HOPCGN1 (Deactivation : 25/06/2019)	4.2240	Adder	4.97
315075	1HOPCGN2 (Deactivation : 25/06/2019)	4.1692	Adder	4.9
315077	1HOPHCF1	1.5366	50/50	1.5366
315078	1HOPHCF2	1.5366	50/50	1.5366
315079	1HOPHCF3	1.5366	50/50	1.5366
315080	1HOPHCF4	2.3327	50/50	2.3327
315116	1SURRY 1	48.1557	50/50	48.1557
315117	1GRAVELC	1.6877	50/50	1.6877
315119	1GRAVEL3	4.8920	50/50	4.8920
315120	1GRAVEL4	4.9547	50/50	4.9547
315121	1GRAVEL5	4.8920	50/50	4.8920
315122	1GRAVEL6	4.9490	50/50	4.9490
315294	1DOMTR10	-3.0713	Adder	-3.61
315611	6Z1-036WIND	-2.3517	Adder	-2.77
907092	X1-038 E	-2.0292	Adder	-2.39
923801	AB2-015 C OP	-2.7901	Adder	-3.28
923831	AB2-022 C	-0.7518	Adder	-0.88
924811	AB2-134 C OP	2.8523	50/50	2.8523
924812	AB2-134 E OP	16.2592	50/50	16.2592
925331	AB2-190 C	24.5202	50/50	24.5202
925332	AB2-190 E	10.5086	50/50	10.5086
926661	AC1-147 C	-0.6074	Adder	-0.71
927221	AC1-216 C O1	2.1777	50/50	2.1777
927222	AC1-216 E O1	9.9259	50/50	9.9259
933731	AC2-196 C	-0.5014	Adder	-0.59
934011	AD1-025 C	21.6943	50/50	21.6943
934012	AD1-025 E	12.8507	50/50	12.8507
935111	AD1-144 C	-1.4275	Adder	-1.68
935161	AD1-151 C O1	19.7037	50/50	19.7037
935162	AD1-151 E O1	13.1358	50/50	13.1358
936041	AD2-007 C	1.0363	50/50	1.0363
936042	AD2-007 E	0.7139	50/50	0.7139
936051	AD2-008 C	3.7769	50/50	3.7769
936052	AD2-008 E	8.2217	50/50	8.2217

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937251	AD2-164 (Withdrawn : 06/30/2020)	-1.3329	Adder	-1.57
937541	AD2-215 C	-1.4422	Adder	-1.7
938173	AE1-026 BAT	6.9372	Merchant Transmission	6.9372
940891	AE2-078 C	3.7757	50/50	3.7757
940892	AE2-078 E	1.9451	50/50	1.9451
940901	AE2-079 C	3.7757	50/50	3.7757
940902	AE2-079 E	1.9451	50/50	1.9451
941592	AE2-156 BAT	5.6200	Merchant Transmission	5.6200
942131	AE2-225 C	-1.0065	Adder	-1.18
942171	AE2-229 C	-1.0065	Adder	-1.18
942551	AE2-270	34.6995	50/50	34.6995
942851	AE2-304 C	-0.2228	Adder	-0.26
943621	AF1-033 C	3.7757	50/50	3.7757
943622	AF1-033 E	1.9451	50/50	1.9451
944501	AF1-115 C O1	11.4988	50/50	11.4988
944502	AF1-115 E O1	5.6636	50/50	5.6636
944631	AF1-128 O1	11.6650	Adder	13.72
957632	AF2-057 BAT	0.6011	Merchant Transmission	0.6011
957711	AF2-065 C	17.6967	50/50	17.6967
957712	AF2-065 E	17.0028	50/50	17.0028
960101	AF2-301 C	3.1305	50/50	3.1305
960102	AF2-301 E	2.0870	50/50	2.0870
960132	AF2-304 E O1	13.9922	50/50	13.9922
NEWTON	NEWTON	0.5738	Confirmed LTF	0.5738
FARMERCITY	FARMERCITY	0.0323	Confirmed LTF	0.0323
G-007A	G-007A	0.0120	Confirmed LTF	0.0120
VFT	VFT	0.0258	Confirmed LTF	0.0258
CALDERWOOD	CALDERWOOD	0.4140	Confirmed LTF	0.4140
NY	NY	0.0188	Confirmed LTF	0.0188
PRAIRIE	PRAIRIE	1.5136	Confirmed LTF	1.5136
CHEOAH	CHEOAH	0.4234	Confirmed LTF	0.4234
EDWARDS	EDWARDS	0.1761	Confirmed LTF	0.1761
TILTON	TILTON	0.3131	Confirmed LTF	0.3131
GIBSON	GIBSON	0.2806	Confirmed LTF	0.2806
BLUEG	BLUEG	0.8715	Confirmed LTF	0.8715
TRIMBLE	TRIMBLE	0.2771	Confirmed LTF	0.2771
CATAWBA	CATAWBA	0.4228	Confirmed LTF	0.4228

11.7 Queue Dependencies

The Queue Projects below are listed in one or more indices for the overloads identified in your report. These projects contribute to the loading of the overloaded facilities identified in your report. The percent overload of a facility and cost allocation you may have towards a particular reinforcement could vary depending on the action of these earlier projects. The status of each project at the time of the analysis is presented in the table. This list may change as earlier projects withdraw or modify their requests.

Queue Number	Project Name	Status
AA1-063A	Carolina–Seaboard 115kV	In Service
AA1-065	Earleys 230kV	In Service
AA1-067	Everetts 34.5kV	In Service
AA1-139	Hickory-Shawboro 230kV	In Service
AA2-053	Carolina-Jackson 115kV	In Service
AA2-088	Boykins-Handsome 115kV	In Service
AA2-174	Carolina-Jackson 115kV	In Service
AA2-178	Mackeys 230kV	Under Construction
AB2-015	Franklin 115kV	Engineering and Procurement
AB2-022	Elizabeth City 34.5kV	Engineering and Procurement
AB2-099	Ahoskie 34.5kV	Suspended
AB2-134	Hopewell-Surry 230kV	In Service
AB2-161	Waverly #2 DP 115kV	Suspended
AB2-169	Pantago-Five Points 115kV	Partially in Service - Under Construction
AB2-190	Hopewell-Surry 230kV	Engineering and Procurement
AC1-027	Pendleton 34.5kV	In Service
AC1-065	Harmony Village-Shackleford 115kV	Engineering and Procurement
AC1-098	Dawson-South Justice 115kV	Engineering and Procurement
AC1-099	Dawson-South Justice 115kV	Engineering and Procurement
AC1-147	Grassfield 34.5kV	Engineering and Procurement
AC1-164	Chickahominy 230kV	Engineering and Procurement
AC1-189	Chinquapin-Everetts 230kV	Active
AC1-208	Cox-Whitakers 115kV	Engineering and Procurement
AC1-216	Hopewell-Surry 230kV	Under Construction
AC2-012	Grassfield-Great Bridge 115kV	Active
AC2-079	Ivor-Oakridge 115kV	Active
AC2-084	Dawson-South Justice 115kV	Active
AC2-110	Harmony Village-Shackleford 115kV	Engineering and Procurement
AC2-138	Northern Neck 34.5kV	Under Construction
AC2-196	Fentress 34.5kV	Engineering and Procurement
AD1-023	Cashie-Trowbridge 230 kV	Active
AD1-025	Hopewell-Surry 230 kV	Active
AD1-033	Fentress-Landstown 230 kV	Active
AD1-063	Harmony Village 34.5 kV	In Service
AD1-076	Trowbridge 230 kV	Active
AD1-082	Bakers Pond-Ivor 115kV	Active
AD1-144	Kings Fork 34.5 kV	Engineering and Procurement
AD1-151	Hopewell-Surry 230 kV	Active
AD2-007	Hopewell-Surry 230 kV	Active

Queue Number	Project Name	Status
AD2-008	Hopewell-Surry 230 kV	Active
AD2-030	Wan 34.5 kV	In Service
AD2-039	Harmony Village-Shackleford 115 kV	Engineering and Procurement
AD2-044	Northern Neck 34.5 kV	Under Construction
AD2-051	Earleys – Northampton 230kV	Active
AD2-085	Myrtle-Windsor DP 115kV	Active
AD2-097	Spruance NUG 230kV	In Service
AD2-160	Hickory-Moyock 230kV	Active
AD2-164	Peninsula 34.5kV	Withdrawn
AD2-215	Kings Fork 34.5 kV	Engineering and Procurement
AE1-004	Harmony Village-Shackleford 115 kV	Engineering and Procurement
AE1-026	Cashie 230 kV	Active
AE1-035	Earleys 230 kV	Engineering and Procurement
AE1-072	Shawboro-Sligo 230 kV	Active
AE1-103	Holland-Union Camp 115 kV	Active
AE1-162	Smithfield 34.5 kV	Engineering and Procurement
AE1-174	Light Foot 34.5 kV	Withdrawn
AE2-000B	N/A	N/A
AE2-007	Chesapeake 230 kV	Active
AE2-034	Mackeys 230 kV	Active
AE2-040	Sapony 34.5 kV	Active
AE2-041	Harmony Village 230 kV	Active
AE2-078	Poolesville 34.5 kV	Engineering and Procurement
AE2-079	Poolesville 34.5 kV	Engineering and Procurement
AE2-104	Suffolk 115 kV	Active
AE2-122	Birdneck-Landstown 230 kV	Active
AE2-123	Birdneck-Landstown 230 kV	Active
AE2-124	Landstown 230 kV	Active
AE2-147	Swamp 230 kV	Active
AE2-151	Earleys 34.5kV	Engineering and Procurement
AE2-156	Yadkin 115 kV	Active
AE2-225	Suffolk 34 kV	Engineering and Procurement
AE2-227	Iron Bridge 34 kV	Active
AE2-229	Suffolk 34 kV	Engineering and Procurement
AE2-247	Myrtle-Windsor 115 kV	Active
AE2-253	Hickory-Moyock 230 kV	Active
AE2-270	Hopewell-Surry 230 kV	Active
AE2-304	South Hertford 34 kV	Engineering and Procurement
AE2-346	Ahoskie 34.5 kV	Active
AF1-017	Myrtle-Windsor 115 kV	Active
AF1-018	Harmony Village 230 kV	Active
AF1-032	Suffolk 34.5 kV	Engineering and Procurement
AF1-033	Poolesville 34 kV	Engineering and Procurement
AF1-115	Poolesville 230 kV	Active
AF1-123	Fentress 500 kV	Active
AF1-124	Fentress 500 kV	Active
AF1-125	Fentress 500 kV	Active
AF1-128	Chesterfield 230 kV	Active
AF1-152	Swamp 230 kV	Active
AF1-201	Hayes-Whitemarsh 115 kV	Active
AF1-236	Mackeys 230 kV	Active
AF1-266	Clubhouse-Sapony 230 kV	Active

Queue Number	Project Name	Status
AF2-043	Suffolk 34.5 kV	Active
AF2-046	Tunis-Mapleton 115 kV	Active
AF2-047	Creswell-Riders Creek 115 kV	Active
AF2-057	Grassfield 34.5 kV	Active
AF2-065	Surry-Hopewell 230 kV	Active
AF2-073	Nucor Steel-Suffolk 230 kV	Withdrawn
AF2-074	Nucor Steel-Suffolk 230 kV	Withdrawn
AF2-076	Suffolk-Nucor Steel 230 kV	Active
AF2-080	Chinquapin-Everetts 230 kV	Active
AF2-081	Moyock 230 kV	Active
AF2-108	Locks 34.5 kV	Active
AF2-110	Suffolk 115 kV	Active
AF2-242	Wharton 115 kV	Active
AF2-255	Iron Bridge 34.5 kV	Active
AF2-264	Tunis 34.5 kV	Active
AF2-301	Poolesville-Winchester 230 kV	Active
AF2-304	Surry-Hopewell 230 kV	Active
AF2-327	Wakefield 13 kV	Withdrawn
AF2-374	Woodland 34.5 kV	Active
AF2-400	Franklin 13.2 kV	Active
AF2-402	Ivor-Oak Ridge 115 kV	Active
V4-068	Murphy's 34.5kV	In Service
W1-029	Winfall 230kV	In Service
X1-038	Union Camp 115kV	In Service
Y1-086	Morgans Corner	In Service
Z1-036	WinFall-Chowan 230kV	Suspended
Z1-068	Birdneck 34.5kV	Under Construction
Z2-027	Pasquotank 34.5kV	In Service
Z2-043	Kelford 34.5kV	In Service
Z2-088	Tarboro-Everetts 230kV	In Service

11.8 Contingency Descriptions - Primary POI

Contingency Name	Contingency Definition
DVP_P4-2: 211T2124	CONTINGENCY 'DVP_P4-2: 211T2124' /* HOPEWELL 230 KV OPEN BRANCH FROM BUS 314287 TO BUS 314303 CKT 1 /* 6CHESTF B 230.00 - 6HOPEWLL 230.00 OPEN BRANCH FROM BUS 314269 TO BUS 314291 CKT 1 /* 6PRGEORG 230.00 - 3PRGEORG 115.00 OPEN BRANCH FROM BUS 314269 TO BUS 314303 CKT 1 /* 6PRGEORG 230.00 - 6HOPEWLL 230.00 OPEN BUS 314269 /* ISLAND: 6PRGEORG 230.00 END
960130 AF2-304 TAP 230 942551 AE2-270 230 1	CONTINGENCY '960130 AF2-304 TAP 230 942551 AE2-270 230 1' OPEN BRANCH FROM BUS 960130 TO BUS 942550 CKT 2 END

Contingency Name	Contingency Definition
DVP_P1-2: LN 228	CONTINGENCY 'DVP_P1-2: LN 228' OPEN BRANCH FROM BUS 314286 TO BUS 314303 CKT 1 /* 6CHESTF A 230.00 - 6HOPEWLL 230.00 END
DVP_P4-2: 240TAB2-190	CONTINGENCY 'DVP_P4-2: 240TAB2-190' /* AB2-190 TAP 230 KV OPEN BRANCH FROM BUS 314303 TO BUS 925330 CKT 2 /* 6HOPEWLL 230.00 - AB2- 190 TAP 230.00 OPEN BUS 925331 /* AB2-190 C 230.00 KV OPEN BUS 925332 /* ISLAND: AB2-190 E 230.00 END
DVP_P1-2: LN 211	CONTINGENCY 'DVP_P1-2: LN 211' OPEN BRANCH FROM BUS 314287 TO BUS 314303 CKT 1 /* 6CHESTF B 230.00 - 6HOPEWLL 230.00 END
DVP_P7-1: LN 223-226	CONTINGENCY 'DVP_P7-1: LN 223-226' /* . OPEN BRANCH FROM BUS 314475 TO BUS 314514 CKT 1 /* 6HARBORV 230.00 - 6YADKIN 230.00 OPEN BRANCH FROM BUS 314475 TO BUS 314533 CKT 1 /* 6HARBORV 230.00 - 6SMITFLD 230.00 OPEN BRANCH FROM BUS 314533 TO BUS 314538 CKT 1 /* 6SMITFLD 230.00 - 6SURRY 230.00 OPEN BUS 314475 /* ISLAND: 6HARBORV 230.00 OPEN BUS 314533 /* ISLAND: 6SMITFLD 230.00 OPEN BRANCH FROM BUS 314453 TO BUS 314484 CKT 1 /* 6CHRHLND 230.00 - 6HARBORV226 230.00 OPEN BRANCH FROM BUS 314484 TO BUS 314523 CKT 1 /* 6HARBORV226 230.00 - 6CRITTDN 230.00 OPEN BRANCH FROM BUS 314523 TO BUS 314538 CKT 1 /* 6CRITTDN 230.00 - 6SURRY 230.00 OPEN BUS 314484 /* ISLAND: 6HARBORV226 230.00 OPEN BUS 314523 /* ISLAND: 6CRITTDN 230.00 END
DVP_P4-2: 228T268	CONTINGENCY 'DVP_P4-2: 228T268' /* HOPEWELL 230 KV OPEN BRANCH FROM BUS 314286 TO BUS 314303 CKT 1 /* 6CHESTF A 230.00 - 6HOPEWLL 230.00 OPEN BRANCH FROM BUS 314303 TO BUS 315074 CKT 1 /* 6HOPEWLL 230.00 - 1HOPCGN1 13.800 OPEN BRANCH FROM BUS 314303 TO BUS 315075 CKT 1 /* 6HOPEWLL 230.00 - 1HOPCGN2 13.800 OPEN BUS 315074 /* ISLAND: 1HOPCGN1 13.800 OPEN BUS 315075 /* ISLAND: 1HOPCGN2 13.800 END

Contingency Name	Contingency Definition
DVP_P1-2: LN 2197	CONTINGENCY 'DVP_P1-2: LN 2197' OPEN BRANCH FROM BUS 313896 TO BUS 314303 CKT 1 /* 6COLONIAL TR230.00 - 6HOPEWLL 230.00 END
DVP_P4-2: 56372	CONTINGENCY 'DVP_P4-2: 56372' /* CARSON 500 KV OPEN BRANCH FROM BUS 314902 TO BUS 314914 CKT 1 /* 8CARSON 500.00 - 8MDLTHAN 500.00 OPEN BRANCH FROM BUS 314282 TO BUS 314902 CKT 1 /* 6CARSON 230.00 - 8CARSON 500.00 END
DVP_P4-2: 531T582	CONTINGENCY 'DVP_P4-2: 531T582' /* SURRY 500 KV OPEN BRANCH FROM BUS 314924 TO BUS 314928 CKT 1 /* 8SURRY 500.00 - 8SUFFOLK 500.00 OPEN BRANCH FROM BUS 314924 TO BUS 314931 CKT 1 /* 8SURRY 500.00 - 8SKIFF CREEK500.00 END
DVP_P4-2: G5T228	CONTINGENCY 'DVP_P4-2: G5T228' /* CHESTERFIELD 230 230 KV OPEN BRANCH FROM BUS 314286 TO BUS 314303 CKT 1 /* 6CHESTF A 230.00 - 6HOPEWLL 230.00 OPEN BRANCH FROM BUS 314286 TO BUS 315060 CKT 1 /* 6CHESTF A 230.00 - 1CHESTF5 22.000 OPEN BUS 315060 /* ISLAND: 1CHESTF5 22.000 END
DVP_P1-2: LN 531	CONTINGENCY 'DVP_P1-2: LN 531' OPEN BRANCH FROM BUS 314924 TO BUS 314928 CKT 1 /* 8SURRY 500.00 - 8SUFFOLK 500.00 END
Base Case	
DVP_P4-2: 240T2041	CONTINGENCY 'DVP_P4-2: 240T2041' /* HOPEWELL 230 KV OPEN BRANCH FROM BUS 314303 TO BUS 925330 CKT 2 /* 6HOPEWLL 230.00 - AB2- 190 TAP 230.00 OPEN BUS 315077 /* 1HOPHCF1 13.800 KV OPEN BUS 315078 /* 1HOPHCF2 13.800 KV OPEN BUS 315079 /* 1HOPHCF3 13.800 KV OPEN BUS 315080 /* 1HOPHCF4 13.800 KV END

12 Short Circuit Analysis - Primary POI

Short circuit analysis will be provided in the System Impact Study report.

13 Summer Peak - Load Flow Analysis - Secondary POI

The Queue Project AF2-304 was evaluated as a 150.0 MW (Capacity 89.0 MW) injection tapping the Hopewell to Surry 230 kV line, Ckt. 1 in the Dominion area. For the secondary POI, AF2-304 is injecting at a different bus from the existing Hopewell James River units; therefore, the Hopewell units were removed from the model and the full AF2-304 project (150 MW Energy and 89 MW Capacity) were modeled. Project AF2-304 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AF2-304 was studied with a commercial probability of 53.0 %. Potential network impacts were as follows:

13.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

13.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC D C	MW IMPAC T
97804918	313896	6COLONIALTR	230.0	DVP	314303	6HOPEWELL	230.0	DVP	1	DVP_P4-2: 240T2041	breaker	830.0	99.39	108.54	DC	75.83
148845118	313896	6COLONIALTR	230.0	DVP	314303	6HOPEWELL	230.0	DVP	1	DVP_P4-2: 56372	breaker	830.0	95.05	103.93	DC	73.63
97805018	314525	6KINGFOR K	230.0	DVP	314522	6CHCKTU K	230.0	DVP	1	DVP_P4-2: 531T582	breaker	830.0	98.86	100.03	DC	9.72
98579123	314538	6SURRY	230.0	DVP	314522	6CHCKTU K	230.0	DVP	1	DVP_P7-1: LN 223-226	tower	830.0	99.11	103.27	DC	34.54

13.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJEC T LOADIN G %	POST PROJEC T LOADIN G %	AC D C	MW IMPAC T
97804799	314287	6CHESTFB	230.0	DVP	314276	6BASIN	230.0	DVP	1	DVP_P4-2: 562T563	breaker	812.0	146.28	147.11	DC	14.95
98091150	314287	6CHESTFB	230.0	DVP	314276	6BASIN	230.0	DVP	1	DVP_P1-2: LN 563	single	663.640014648	147.48	148.86	DC	9.12
98091153	314287	6CHESTFB	230.0	DVP	314276	6BASIN	230.0	DVP	1	DVP_P1-2: LN 217	single	663.640014648	105.14	106.79	DC	10.9
98579133	314287	6CHESTFB	230.0	DVP	314225	6CHARC TY	230.0	DVP	1	DVP_P7-1: LN 208-259	tower	1204.0	100.61	102.29	DC	20.21

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJE CT LOADIN G %	POST PROJE CT LOADIN G %	AC D C	MW IMPAC T
97804700	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P4-2: 56372	breaker	549.0	199.61	206.22	DC	36.23
97804702	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P4-2: GST228	breaker	549.0	186.47	197.07	DC	58.2
97804730	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	DVP_P4-2: 211T2124	breaker	549.0	172.2	183.87	DC	64.01
98091075	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	DVP_P1-2: LN 211	single	449.320007324	155.06	162.28	DC	33.36
98091079	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	DVP_P1-2: LN 259	single	449.320007324	138.14	143.21	DC	23.13
98091083	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	Base Case	single	449.320007324	112.8	117.51	DC	21.2
98091115	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P1-2: LN 228	single	449.320007324	157.67	165.16	DC	34.53
98091119	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P1-2: LN 208	single	449.320007324	145.03	150.33	DC	23.77
98091124	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	Base Case	single	449.320007324	103.6	108.54	DC	22.16

13.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJE CT LOADIN G %	POST PROJE CT LOADIN G %	AC D C	MW IMPAC T
98091500	313896	6COLONIALTR	230.0	DVP	314303	6HOPEWLL	230.0	DVP	1	DVP_P1-2: LN 240	operation	678.679992676	115.04	126.23	DC	75.87
98091615	314225	6CHARCTY	230.0	DVP	314227	6LAKESIDE	230.0	DVP	1	DVP_P1-2: LN 563	operation	984.179992676	111.96	112.49	DC	15.04
98091552	314236	6NRTHEST	230.0	DVP	314218	6ELMONT	230.0	DVP	1	DVP_P1-2: LN 557	operation	678.679992676	121.61	121.76	DC	13.42
98091149	314287	6CHESTFB	230.0	DVP	314276	6BASIN	230.0	DVP	1	DVP_P1-2: LN 563	operation	663.640014648	174.63	175.54	DC	15.38
98091599	314287	6CHESTFB	230.0	DVP	314225	6CHARCTY	230.0	DVP	1	DVP_P1-2: LN 563	operation	984.179992676	115.62	116.15	DC	15.04

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADIN G %	POST PROJECT LOADIN G %	AC DC	MW IMPACT
98091072	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	DVP_P1-2: LN211	operation	449.320007324	198.03	210.55	DC	56.22
98091078	314303	6HOPEWLL	230.0	DVP	314286	6CHESTFA	230.0	DVP	1	Base Case	operation	449.320007324	137.62	145.58	DC	35.74
98091113	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	DVP_P1-2: LN228	operation	449.320007324	227.79	240.75	DC	58.2
98091120	314303	6HOPEWLL	230.0	DVP	314287	6CHESTFB	230.0	DVP	1	Base Case	operation	449.320007324	125.96	134.28	DC	37.34
98091640	314525	6KINGFOR K	230.0	DVP	314522	6CHCKTUK	230.0	DVP	1	DVP_P1-2: LN531	operation	678.679992676	104.79	106.01	DC	8.32
98091607	314538	6SURRY	230.0	DVP	942550	AE2-270 TAP	230.0	DVP	2	DVP_P1-2: LN2197	operation	678.679992676	107.64	112.66	DC	33.87
96976769	314905	8CHANCE	500.0	DVP	314900	8BRISTER	500.0	DVP	1	DVP_P1-2: LN594	operation	2442.12011719	144.63	144.66	DC	29.43
96976859	314908	8ELMONT	500.0	DVP	314911	8LADYSMITH	500.0	DVP	1	DVP_P1-2: LN576	operation	4070.19995117	118.94	118.95	DC	49.72
96976779	314911	8LADYSMITH	500.0	DVP	314922	8POSSUM	500.0	DVP	1	DVP_P1-2: LN581	operation	2442.12011719	140.52	140.55	DC	25.98
96976791	314911	8LADYSMITH	500.0	DVP	314905	8CHANCE	500.0	DVP	1	DVP_P1-2: LN573	operation	2738.2199707	130.64	130.66	DC	30.07
96976818	314927	8YADKIN	500.0	DVP	314928	8SUFFOLK	500.0	DVP	1	DVP_P1-2: LN579	operation	2442.12011719	127.16	127.6	DC	24.53
98091305	925330	AB2-190 TAP	230.0	DVP	314303	6HOPEWLL	230.0	DVP	2	DVP_P1-2: LN2197	operation	678.679992676	147.18	152.18	DC	33.87
149218027	942550	AE2-270 TAP	230.0	DVP	925330	AB2-190 TAP	230.0	DVP	2	DVP_P1-2: LN2197	operation	678.679992676	118.91	123.9	DC	33.87

13.5 Flow Gate Details - Secondary POI

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

13.5.1 Index 1

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804918	313896	6COLONIAL TR	DVP	314303	6HOPEWELL	DVP	1	DVP_P4-2: 240T2041	breaker	830.0	99.39	108.54	DC	75.83

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315073	1STONECA	-4.9401	Adder	-5.81
315116	1SURRY 1	32.8978	50/50	32.8978
315117	1GRAVELC	1.1529	50/50	1.1529
315119	1GRAVEL3	3.3420	50/50	3.3420
315120	1GRAVEL4	3.3848	50/50	3.3848
315121	1GRAVEL5	3.3420	50/50	3.3420
315122	1GRAVEL6	3.3809	50/50	3.3809
913392	Y1-086 E	0.6842	Adder	0.8
916192	Z1-068 E	0.6779	Adder	0.8
919152	AA1-139 E	2.0854	Adder	2.45
923831	AB2-022 C	0.7173	Adder	0.84
923832	AB2-022 E	0.3862	Adder	0.45
924811	AB2-134 C OP	6.2609	50/50	6.2609
924812	AB2-134 E OP	35.6897	50/50	35.6897
925331	AB2-190 C	25.2907	50/50	25.2907
925332	AB2-190 E	10.8389	50/50	10.8389
925522	AC1-027 E	0.4169	Adder	0.49
926661	AC1-147 C	0.8910	Adder	1.05
926662	AC1-147 E	0.5233	Adder	0.62
927221	AC1-216 C O1	4.7801	50/50	4.7801
927222	AC1-216 E O1	21.7879	50/50	21.7879
932041	AC2-012 C	4.0306	Adder	4.74
932042	AC2-012 E	6.5762	Adder	7.74
933731	AC2-196 C	0.5968	Adder	0.7
933732	AC2-196 E	0.3975	Adder	0.47
934011	AD1-025 C	47.6200	50/50	47.6200
934012	AD1-025 E	28.2080	50/50	28.2080
934061	AD1-033 C	2.5336	Adder	2.98
934062	AD1-033 E	1.6891	Adder	1.99
935111	AD1-144 C	0.7313	Adder	0.86
935112	AD1-144 E	0.3996	Adder	0.47
935161	AD1-151 C O1	20.3229	50/50	20.3229
935162	AD1-151 E O1	13.5486	50/50	13.5486
936041	AD2-007 C	2.2748	50/50	2.2748
936042	AD2-007 E	1.5671	50/50	1.5671
936051	AD2-008 C	8.2905	50/50	8.2905
936052	AD2-008 E	18.0471	50/50	18.0471
937221	AD2-160 C O1	1.9165	Adder	2.25
937222	AD2-160 E O1	1.0050	Adder	1.18
937251	AD2-164 (Withdrawn : 06/30/2020)	1.6250	Adder	1.91
937541	AD2-215 C	0.7389	Adder	0.87

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937542	AD2-215 E	0.3921	Adder	0.46
938531	AE1-072 C O1	5.6597	Adder	6.66
938532	AE1-072 E O1	2.9504	Adder	3.47
939311	AE1-162 C	2.0568	50/50	2.0568
939312	AE1-162 E	1.3712	50/50	1.3712
940251	AE2-007 O1	66.4959	Adder	78.23
940891	AE2-078 C	2.6910	50/50	2.6910
940892	AE2-078 E	1.3862	50/50	1.3862
940901	AE2-079 C	2.6910	50/50	2.6910
940902	AE2-079 E	1.3862	50/50	1.3862
941281	AE2-122 C O1	10.1907	Adder	11.99
941282	AE2-122 E O1	41.1218	Adder	48.38
941291	AE2-123 C O1	10.4728	Adder	12.32
941292	AE2-123 E O1	40.8396	Adder	48.05
941301	AE2-124 C O1	9.4265	Adder	11.09
941302	AE2-124 E O1	41.3623	Adder	48.66
941591	AE2-156 O1	7.0023	Adder	8.24
942131	AE2-225 C	0.6740	Adder	0.79
942132	AE2-225 E	0.4493	Adder	0.53
942171	AE2-229 C	0.6740	Adder	0.79
942172	AE2-229 E	0.4493	Adder	0.53
942401	AE2-253 C	2.0158	Adder	2.37
942402	AE2-253 E	0.9056	Adder	1.07
942551	AE2-270	33.8715	50/50	33.8715
943611	AF1-032 C	0.5504	Adder	0.65
943612	AF1-032 E	0.2921	Adder	0.34
943621	AF1-033 C	2.6910	50/50	2.6910
943622	AF1-033 E	1.3862	50/50	1.3862
944501	AF1-115 C O1	8.1952	50/50	8.1952
944502	AF1-115 E O1	4.0364	50/50	4.0364
957491	AF2-043 C	0.3572	Adder	0.79
957492	AF2-043 E	0.2382	Adder	0.53
957631	AF2-057	0.7495	Adder	1.66
957711	AF2-065 C	17.2745	50/50	17.2745
957712	AF2-065 E	16.5970	50/50	16.5970
957821	AF2-076 C O2	0.8858	Adder	1.97
957822	AF2-076 E O2	0.5905	Adder	1.31
957871	AF2-081 C O2	1.7205	Adder	3.82
957872	AF2-081 E O2	0.7374	Adder	1.64
960101	AF2-301 C	2.4855	50/50	2.4855
960102	AF2-301 E	1.6570	50/50	1.6570
960131	AF2-304 C O2	44.9913	50/50	44.9913
960132	AF2-304 E O2	30.8367	50/50	30.8367
WEC	WEC	0.0047	Confirmed LTF	0.0047
LGEE	LGEE	0.0137	Confirmed LTF	0.0137
CPL	CPL	0.6906	Confirmed LTF	0.6906
CBM-W2	CBM-W2	1.2121	Confirmed LTF	1.2121
NY	NY	0.2218	Confirmed LTF	0.2218
CBM-W1	CBM-W1	0.0125	Confirmed LTF	0.0125
TVA	TVA	0.3290	Confirmed LTF	0.3290
O-066	O-066	2.8762	Confirmed LTF	2.8762
CBM-S2	CBM-S2	4.2310	Confirmed LTF	4.2310

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
CBM-S1	CBM-S1	1.6614	Confirmed LTF	1.6614
G-007	G-007	0.4472	Confirmed LTF	0.4472
MADISON	MADISON	0.1835	Confirmed LTF	0.1835
MEC	MEC	0.1017	Confirmed LTF	0.1017

13.5.2 Index 2

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97805018	314525	6KINGFORK	DVP	314522	6CHCKTUK	DVP	1	DVP_P4-2: 531T582	breaker	830.0	98.86	100.03	DC	9.72

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314189	6PAPERMILL	-2.7380	Adder	-3.22
314539	3UNCAMP	1.7104	50/50	1.7104
314541	3WATKINS	0.4582	50/50	0.4582
314639	6TANGLEW	0.2490	50/50	0.2490
315073	1STONECA	-2.3005	Adder	-2.71
315115	1S HAMPT1	1.0389	50/50	1.0389
315294	1DOMTR10	5.1307	Adder	6.04
315605	6W1-029WIND	0.5695	50/50	0.5695
315611	6Z1-036WIND	4.3637	50/50	4.3637
315614	AA2-178 C	1.0057	50/50	1.0057
900672	V4-068 E	0.1407	Adder	0.17
901082	W1-029 E	22.1309	50/50	22.1309
907092	X1-038 E	4.2760	50/50	4.2760
913392	Y1-086 E	1.0154	Adder	1.19
916042	Z1-036 E (Suspended)	29.2369	50/50	29.2369
916192	Z1-068 E	0.5326	Adder	0.63
917122	Z2-027 E	0.6187	50/50	0.6187
917332	Z2-043 E	0.4811	Adder	0.57
917512	Z2-088 E OP1	1.2458	Adder	1.47
918492	AA1-063AE OP	1.5127	Adder	1.78
918512	AA1-065 E OP	1.9431	Adder	2.29
918532	AA1-067 E	0.2730	Adder	0.32
919152	AA1-139 E	2.4162	Adder	2.84
919692	AA2-053 E OP	1.2489	Adder	1.47
920042	AA2-088 E OP	5.1751	Adder	6.09
920672	AA2-174 E OP	0.1443	Adder	0.17
920692	AA2-178 E	2.4986	50/50	2.4986
923801	AB2-015 C OP	5.8860	50/50	5.8860
923802	AB2-015 E OP	4.8265	50/50	4.8265
923831	AB2-022 C	1.0646	Adder	1.25
923832	AB2-022 E	0.5732	Adder	0.67
924501	AB2-099 C (Suspended)	0.2681	Adder	0.32
924502	AB2-099 E (Suspended)	0.1149	Adder	0.14
924812	AB2-134 E OP	-7.7791	Adder	-9.15
925061	AB2-161 C O1 (Suspended)	1.4147	Adder	1.66
925062	AB2-161 E O1 (Suspended)	2.3083	Adder	2.72
925122	AB2-169 E	2.5644	Adder	3.02
925331	AB2-190 C	-11.8200	Adder	-13.91
925522	AC1-027 E	0.3180	Adder	0.37
925861	AC1-065 C	-1.5347	Adder	-1.81

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
926201	AC1-098 C	2.1285	Adder	2.5
926202	AC1-098 E	1.2681	Adder	1.49
926211	AC1-099 C	0.7133	Adder	0.84
926212	AC1-099 E	0.4189	Adder	0.49
926781	AC1-164 C	-11.2195	Adder	-13.2
927021	AC1-189 C	2.9245	Adder	3.44
927022	AC1-189 E	1.4568	Adder	1.71
927141	AC1-208 C	2.8584	Adder	3.36
927142	AC1-208 E	1.2692	Adder	1.49
932591	AC2-079 C O1	3.7229	50/50	3.7229
932592	AC2-079 E O1	6.0742	50/50	6.0742
932631	AC2-084 C	3.0343	Adder	3.57
932632	AC2-084 E	1.4945	Adder	1.76
932831	AC2-110 C	-0.6139	Adder	-0.72
932832	AC2-110 E	-1.0016	Adder	-1.18
933271	AC2-138 C	-0.2800	Adder	-0.33
933731	AC2-196 C	0.5775	Adder	0.68
933732	AC2-196 E	0.3846	Adder	0.45
933991	AD1-023 C	6.4975	Adder	7.64
933992	AD1-023 E	3.5373	Adder	4.16
934061	AD1-033 C	2.3926	Adder	2.81
934062	AD1-033 E	1.5951	Adder	1.88
934392	AD1-063 E	-0.4746	Adder	-0.56
934521	AD1-076 C	27.1205	Adder	31.91
934522	AD1-076 E	13.8097	Adder	16.25
934571	AD1-082 C	3.2241	Adder	3.79
934572	AD1-082 E	1.8392	Adder	2.16
935111	AD1-144 C	3.0750	50/50	3.0750
935112	AD1-144 E	1.6802	50/50	1.6802
936242	AD2-030 E	-0.6007	Adder	-0.71
936301	AD2-039 C	-0.6139	Adder	-0.72
936302	AD2-039 E	-1.0016	Adder	-1.18
936341	AD2-044 C	-0.0875	Adder	-0.1
936342	AD2-044 E	-0.0992	Adder	-0.12
936401	AD2-051 C O1	4.1939	Adder	4.93
936402	AD2-051 E O1	1.8008	Adder	2.12
936661	AD2-085 C	2.2089	50/50	2.2089
936662	AD2-085 E	3.6040	50/50	3.6040
937221	AD2-160 C O1	2.1130	Adder	2.49
937222	AD2-160 E O1	1.1080	Adder	1.3
937251	AD2-164 (Withdrawn : 06/30/2020)	-6.0834	Adder	-7.16
937541	AD2-215 C	3.1067	50/50	3.1067
937542	AD2-215 E	1.6485	50/50	1.6485
938031	AE1-004 C	-0.6139	Adder	-0.72
938171	AE1-026 C O1	15.7783	Adder	18.56
938172	AE1-026 E O1	4.1627	Adder	4.9
938221	AE1-035 C	1.0849	Adder	1.28
938222	AE1-035 E	0.5344	Adder	0.63
938531	AE1-072 C O1	6.8950	Adder	8.11
938532	AE1-072 E O1	3.5944	Adder	4.23
938771	AE1-103 C O1	2.5656	50/50	2.5656
938772	AE1-103 E O1	3.5429	50/50	3.5429

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
939311	AE1-162 C	-0.9682	Adder	-1.14
939423	AE1-174 BAT (Withdrawn : 06/16/2020)	0.6995	50/50	0.6995
940061	AE2-000BC O1	6.7014	Adder	7.88
940062	AE2-000BE O1	4.4676	Adder	5.26
940491	AE2-034 C	4.3726	50/50	4.3726
940492	AE2-034 E	1.8740	50/50	1.8740
940552	AE2-041 BAT	3.7220	Merchant Transmission	3.7220
941101	AE2-104 C O1	2.8654	50/50	2.8654
941102	AE2-104 E O1	4.5556	50/50	4.5556
941281	AE2-122 C O1	8.2133	Adder	9.66
941282	AE2-122 E O1	33.1427	Adder	38.99
941291	AE2-123 C O1	8.4407	Adder	9.93
941292	AE2-123 E O1	32.9152	Adder	38.72
941301	AE2-124 C O1	7.8992	Adder	9.29
941302	AE2-124 E O1	34.6606	Adder	40.78
941501	AE2-147 C	11.0043	50/50	11.0043
941502	AE2-147 E	7.3362	50/50	7.3362
941541	AE2-151 C	0.4917	Adder	0.58
941542	AE2-151 E	0.2647	Adder	0.31
942131	AE2-225 C	2.0525	50/50	2.0525
942132	AE2-225 E	1.3683	50/50	1.3683
942171	AE2-229 C	2.0525	50/50	2.0525
942172	AE2-229 E	1.3683	50/50	1.3683
942341	AE2-247 C	0.9529	50/50	0.9529
942342	AE2-247 E	1.3159	50/50	1.3159
942401	AE2-253 C	2.2225	Adder	2.61
942402	AE2-253 E	0.9985	Adder	1.17
942552	AE2-270 BAT	19.5180	50/50	19.5180
942851	AE2-304 C	0.4105	50/50	0.4105
942852	AE2-304 E	0.1596	50/50	0.1596
943171	AE2-346 C	0.6435	Adder	0.76
943172	AE2-346 E	0.2758	Adder	0.32
943461	AF1-017 C	0.8621	50/50	0.8621
943462	AF1-017 E	1.4067	50/50	1.4067
943472	AF1-018 BAT	3.7220	Merchant Transmission	3.7220
943611	AF1-032 C	1.6762	50/50	1.6762
943612	AF1-032 E	0.8894	50/50	0.8894
944581	AF1-123 C O1	14.5293	Adder	17.09
944582	AF1-123 E O1	33.2679	Adder	39.14
944591	AF1-124 C O1	14.5293	Adder	17.09
944592	AF1-124 E O1	33.2679	Adder	39.14
944601	AF1-125 C O1	14.5293	Adder	17.09
944602	AF1-125 E O1	33.2679	Adder	39.14
944871	AF1-152 C	3.6681	50/50	3.6681
944872	AF1-152 E	2.4454	50/50	2.4454
945363	AF1-201 BAT	3.4952	50/50	3.4952
945711	AF1-236 C O1	47.8698	50/50	47.8698
945712	AF1-236 E O1	78.1033	50/50	78.1033
957491	AF2-043 C	2.0525	50/50	2.0525
957492	AF2-043 E	1.3683	50/50	1.3683
957521	AF2-046 C	4.1768	Adder	9.27
957522	AF2-046 E	2.1009	Adder	4.66

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
957531	AF2-047 C	10.3902	50/50	10.3902
957532	AF2-047 E	5.2263	50/50	5.2263
957791	AF2-073 C (Withdrawn : 07/02/2020)	8.2114	50/50	8.2114
957792	AF2-073 E (Withdrawn : 07/02/2020)	5.2499	50/50	5.2499
957801	AF2-074 C (Withdrawn : 07/02/2020)	3.6495	50/50	3.6495
957802	AF2-074 E (Withdrawn : 07/02/2020)	2.3333	50/50	2.3333
957821	AF2-076 C O2	4.9422	50/50	4.9422
957822	AF2-076 E O2	3.2948	50/50	3.2948
957861	AF2-080 C	1.4077	Adder	3.12
957862	AF2-080 E	0.6241	Adder	1.39
957871	AF2-081 C O2	1.9854	Adder	4.41
957872	AF2-081 E O2	0.8509	Adder	1.89
958161	AF2-110 C	1.1813	50/50	1.1813
958162	AF2-110 E	1.8477	50/50	1.8477
959511	AF2-242	1.7464	Adder	3.88
959731	AF2-264 C	0.5519	Adder	1.23
959732	AF2-264 E	0.2718	Adder	0.6
960133	AF2-304 BAT	9.7222	50/50	9.7222
960361	AF2-327 C (Withdrawn : 07/22/2020)	0.5117	Adder	1.14
960362	AF2-327 E (Withdrawn : 07/22/2020)	0.1279	Adder	0.28
960831	AF2-374 C	0.2777	Adder	0.62
960832	AF2-374 E	0.4531	Adder	1.01
961091	AF2-400 C	0.3178	50/50	0.3178
961092	AF2-400 E	0.5215	50/50	0.5215
961111	AF2-402 C O2	0.2618	Adder	0.58
961112	AF2-402 E O2	0.4281	Adder	0.95
WEC	WEC	0.2230	Confirmed LTF	0.2230
LGEE	LGEE	0.4148	Confirmed LTF	0.4148
CPL	CPL	1.9084	Confirmed LTF	1.9084
CBM-W2	CBM-W2	8.0590	Confirmed LTF	8.0590
NY	NY	0.0907	Confirmed LTF	0.0907
CBM-W1	CBM-W1	8.4943	Confirmed LTF	8.4943
TVA	TVA	1.6282	Confirmed LTF	1.6282
O-066	O-066	1.5523	Confirmed LTF	1.5523
CBM-S2	CBM-S2	12.7160	Confirmed LTF	12.7160
CBM-S1	CBM-S1	9.2186	Confirmed LTF	9.2186
G-007	G-007	0.2444	Confirmed LTF	0.2444
MADISON	MADISON	0.3790	Confirmed LTF	0.3790
MEC	MEC	1.2871	Confirmed LTF	1.2871

13.5.3 Index 3

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
98579123	314538	6SURRY	DVP	314522	6CHCKTUK	DVP	1	DVP_P7-1: LN 223-226	tower	830.0	99.11	103.27	DC	34.54

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314539	3UNCAMP	-0.8117	Adder	-0.95
314541	3WATKINS	-0.2170	Adder	-0.26
315060	1CHESTF5 (Deactivation : 31/05/2023)	14.9896	Adder	17.63
315073	1STONECA	3.5033	Adder	4.12
315077	1HOPHCF1	1.5366	50/50	1.5366
315078	1HOPHCF2	1.5366	50/50	1.5366
315079	1HOPHCF3	1.5366	50/50	1.5366
315080	1HOPHCF4	2.3327	50/50	2.3327
315116	1SURRY 1	48.1557	50/50	48.1557
315117	1GRAVELC	1.6877	50/50	1.6877
315119	1GRAVEL3	4.8920	50/50	4.8920
315120	1GRAVEL4	4.9547	50/50	4.9547
315121	1GRAVEL5	4.8920	50/50	4.8920
315122	1GRAVEL6	4.9490	50/50	4.9490
315294	1DOMTR10	-3.0713	Adder	-3.61
315611	6Z1-036WIND	-2.3520	Adder	-2.77
907092	X1-038 E	-2.0292	Adder	-2.39
923801	AB2-015 C OP	-2.7901	Adder	-3.28
923831	AB2-022 C	-0.7518	Adder	-0.88
924811	AB2-134 C OP	2.8523	50/50	2.8523
924812	AB2-134 E OP	16.2592	50/50	16.2592
925331	AB2-190 C	24.5213	50/50	24.5213
925332	AB2-190 E	10.5091	50/50	10.5091
926661	AC1-147 C	-0.6074	Adder	-0.71
927221	AC1-216 C O1	2.1777	50/50	2.1777
927222	AC1-216 E O1	9.9259	50/50	9.9259
933731	AC2-196 C	-0.5014	Adder	-0.59
934011	AD1-025 C	21.6943	50/50	21.6943
934012	AD1-025 E	12.8507	50/50	12.8507
935111	AD1-144 C	-1.4275	Adder	-1.68
935161	AD1-151 C O1	19.7046	50/50	19.7046
935162	AD1-151 E O1	13.1364	50/50	13.1364
936041	AD2-007 C	1.0363	50/50	1.0363
936042	AD2-007 E	0.7139	50/50	0.7139
936051	AD2-008 C	3.7769	50/50	3.7769
936052	AD2-008 E	8.2217	50/50	8.2217
937251	AD2-164 (Withdrawn : 06/30/2020)	-1.3329	Adder	-1.57
937541	AD2-215 C	-1.4422	Adder	-1.7
938173	AE1-026 BAT	6.9372	Merchant Transmission	6.9372
940891	AE2-078 C	3.7757	50/50	3.7757

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
940892	AE2-078 E	1.9451	50/50	1.9451
940901	AE2-079 C	3.7757	50/50	3.7757
940902	AE2-079 E	1.9451	50/50	1.9451
941592	AE2-156 BAT	5.6200	Merchant Transmission	5.6200
942131	AE2-225 C	-1.0065	Adder	-1.18
942171	AE2-229 C	-1.0065	Adder	-1.18
942551	AE2-270	34.6995	50/50	34.6995
942851	AE2-304 C	-0.2228	Adder	-0.26
943621	AF1-033 C	3.7757	50/50	3.7757
943622	AF1-033 E	1.9451	50/50	1.9451
944501	AF1-115 C O1	11.4988	50/50	11.4988
944502	AF1-115 E O1	5.6636	50/50	5.6636
944631	AF1-128 O1	11.6650	Adder	13.72
957632	AF2-057 BAT	0.6011	Merchant Transmission	0.6011
957711	AF2-065 C	17.6967	50/50	17.6967
957712	AF2-065 E	17.0028	50/50	17.0028
960101	AF2-301 C	3.1305	50/50	3.1305
960102	AF2-301 E	2.0870	50/50	2.0870
960131	AF2-304 C O2	20.4967	50/50	20.4967
960132	AF2-304 E O2	14.0483	50/50	14.0483
NEWTON	NEWTON	0.5738	Confirmed LTF	0.5738
FARMERCITY	FARMERCITY	0.0323	Confirmed LTF	0.0323
G-007A	G-007A	0.0120	Confirmed LTF	0.0120
VFT	VFT	0.0258	Confirmed LTF	0.0258
CALDERWOOD	CALDERWOOD	0.4140	Confirmed LTF	0.4140
NY	NY	0.0188	Confirmed LTF	0.0188
PRAIRIE	PRAIRIE	1.5136	Confirmed LTF	1.5136
CHEOAH	CHEOAH	0.4234	Confirmed LTF	0.4234
EDWARDS	EDWARDS	0.1761	Confirmed LTF	0.1761
TILTON	TILTON	0.3131	Confirmed LTF	0.3131
GIBSON	GIBSON	0.2806	Confirmed LTF	0.2806
BLUEG	BLUEG	0.8715	Confirmed LTF	0.8715
TRIMBLE	TRIMBLE	0.2771	Confirmed LTF	0.2771
CATAWBA	CATAWBA	0.4228	Confirmed LTF	0.4228

13.5.4 Index 4

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
98091150	314287	6CHESTF B	DVP	314276	6BASIN	DVP	1	DVP_P1-2: LN 563	single	663.64	147.48	148.86	DC	9.12

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314314	3LOCKS	0.1996	80/20	0.1996
314435	6SAPONY	0.2851	80/20	0.2851
314572	3EMPORIA	0.0358	80/20	0.0358
314704	3LAWRENC	0.1386	80/20	0.1386
315065	1CHESTF6 (Deactivation : 31/05/2023)	172.3323	80/20	172.3323
315076	1HOPPOLC	1.1982	80/20	1.1982
315077	1HOPHCF1	1.8729	80/20	1.8729
315078	1HOPHCF2	1.8729	80/20	1.8729
315079	1HOPHCF3	1.8729	80/20	1.8729
315080	1HOPHCF4	2.8433	80/20	2.8433
315116	1SURRY 1	11.5720	80/20	11.5720
315117	1GRAVELC	0.4056	80/20	0.4056
315119	1GRAVEL3	1.1756	80/20	1.1756
315120	1GRAVEL4	1.1906	80/20	1.1906
315121	1GRAVEL5	1.1756	80/20	1.1756
315122	1GRAVEL6	1.1893	80/20	1.1893
315126	1ROARAP2	0.6066	80/20	0.6066
315136	1ROSEMG1	0.9895	80/20	0.9895
315137	1ROSEMS1	0.6136	80/20	0.6136
315138	1ROSEMG2	0.4638	80/20	0.4638
315139	1GASTONA	1.4669	80/20	1.4669
315141	1GASTONB	1.4669	80/20	1.4669
315294	1DOMTR10	3.3467	Adder	3.94
315611	6Z1-036WIND	2.0089	Adder	2.36
922922	AB1-081 C OP	2.7246	Adder	3.21
923262	AB1-132 C OP (Suspended)	6.4940	80/20	6.4940
923572	AB1-173 C OP	1.0571	80/20	1.0571
923582	AB1-173AC OP	1.0571	80/20	1.0571
923801	AB2-015 C OP	2.8955	Adder	3.41
923831	AB2-022 C	0.6590	Adder	0.78
923911	AB2-031 C O1	1.0492	80/20	1.0492
923991	AB2-040 C O1	3.4452	80/20	3.4452
924501	AB2-099 C (Suspended)	0.1944	Adder	0.23
924511	AB2-100 C	1.1199	80/20	1.1199
924811	AB2-134 C OP	1.2696	80/20	1.2696
925051	AB2-160 C O1 (Suspended)	3.5182	80/20	3.5182
925061	AB2-161 C O1 (Suspended)	1.9112	80/20	1.9112
925171	AB2-174 C O1	0.5804	80/20	0.5804

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
925331	AB2-190 C	11.7746	80/20	11.7746
925591	AC1-034 C	2.0800	Adder	2.45
926071	AC1-086 C	9.5632	80/20	9.5632
926201	AC1-098 C	2.0227	Adder	2.38
926211	AC1-099 C	0.6778	Adder	0.8
926661	AC1-147 C	0.6442	Adder	0.76
927021	AC1-189 C	2.6158	Adder	3.08
927141	AC1-208 C	2.9977	Adder	3.53
927221	AC1-216 C O1	0.9693	80/20	0.9693
932041	AC2-012 C	2.9143	Adder	3.43
932581	AC2-078 C O1	3.0062	80/20	3.0062
932591	AC2-079 C O1	2.7949	80/20	2.7949
932631	AC2-084 C	2.8835	Adder	3.39
933731	AC2-196 C	0.4989	Adder	0.59
933991	AD1-023 C	4.1106	Adder	4.84
934011	AD1-025 C	9.6564	80/20	9.6564
934061	AD1-033 C	2.0984	Adder	2.47
934331	AD1-057 C O1	3.4483	Adder	4.06
934521	AD1-076 C	16.8055	Adder	19.77
934571	AD1-082 C	4.3555	80/20	4.3555
935111	AD1-144 C	0.5087	Adder	0.6
935161	AD1-151 C O1	9.4617	80/20	9.4617
936041	AD2-007 C	0.4613	80/20	0.4613
936051	AD2-008 C	1.6812	80/20	1.6812
936401	AD2-051 C O1	2.8621	Adder	3.37
936661	AD2-085 C	1.6895	80/20	1.6895
937221	AD2-160 C O1	1.6435	Adder	1.93
937541	AD2-215 C	0.5140	Adder	0.6
938171	AE1-026 C O1	10.1013	Adder	11.88
938221	AE1-035 C	0.7278	Adder	0.86
938491	AE1-068 C O1	17.2211	Adder	20.26
938501	AE1-069 C O1	13.4662	Adder	15.84
938531	AE1-072 C O1	4.9590	Adder	5.83
938561	AE1-075 C	-0.6270	Adder	-0.74
938631	AE1-085 C O1	6.3665	80/20	6.3665
938771	AE1-103 C O1	1.2161	Adder	1.43
939191	AE1-149 C O1	8.2500	80/20	8.2500
939311	AE1-162 C	0.8644	80/20	0.8644
939411	AE1-173 C	25.4102	Adder	29.89
940061	AE2-000BC O1	9.0531	80/20	9.0531
940251	AE2-007 O1	49.1584	Adder	57.83
940431	AE2-027 C O1	3.4915	Adder	4.11
940471	AE2-031 C	9.3547	Adder	11.01
940481	AE2-033 C	10.3934	80/20	10.3934
940491	AE2-034 C	2.1870	Adder	2.57
940541	AE2-040 O1	1.8170	80/20	1.8170
940571	AE2-044 C	1.3623	Adder	1.6
940641	AE2-051 C O1	4.8715	Adder	5.73
940651	AE2-052	2.7500	80/20	2.7500
940891	AE2-078 C	0.9794	80/20	0.9794
940901	AE2-079 C	0.9794	80/20	0.9794
941031	AE2-094 C	11.2928	Adder	13.29

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
941101	AE2-104 C O1	1.0955	Adder	1.29
941281	AE2-122 C O1	8.0148	Adder	9.43
941291	AE2-123 C O1	8.2367	Adder	9.69
941301	AE2-124 C O1	7.4801	Adder	8.8
941501	AE2-147 C	4.6160	Adder	5.43
941541	AE2-151 C	0.3580	Adder	0.42
941591	AE2-156 O1	5.0991	Adder	6.0
942001	AE2-212 C	2.5328	80/20	2.5328
942131	AE2-225 C	0.6193	Adder	0.73
942161	AE2-228 C	2.9165	80/20	2.9165
942171	AE2-229 C	0.6193	Adder	0.73
942341	AE2-247 C	0.7346	80/20	0.7346
942371	AE2-250 C O1	6.2494	80/20	6.2494
942401	AE2-253 C	1.7287	Adder	2.03
942471	AE2-260 C O1	8.2162	80/20	8.2162
942551	AE2-270	15.3405	80/20	15.3405
942851	AE2-304 C	0.1849	Adder	0.22
942931	AE2-313 C	10.1289	Adder	11.92
943171	AE2-346 C	0.4667	Adder	0.55
943461	AF1-017 C	0.6646	80/20	0.6646
943611	AF1-032 C	0.5058	Adder	0.6
943621	AF1-033 C	0.9794	80/20	0.9794
943911	AF1-059	5.3269	Adder	6.27
944011	AF1-069 C	3.6898	Adder	4.34
944141	AF1-082	0.8758	Adder	1.03
944501	AF1-115 C O1	2.9828	80/20	2.9828
944581	AF1-123 C O1	12.9513	Adder	15.24
944591	AF1-124 C O1	12.9513	Adder	15.24
944601	AF1-125 C O1	12.9513	Adder	15.24
944871	AF1-152 C	1.5387	Adder	1.81
945711	AF1-236 C O1	23.9422	Adder	28.17
946011	AF1-266	8.7001	80/20	8.7001
946261	AF1-291 C	2.9432	80/20	2.9432
946281	AF1-292 C	0.7554	80/20	0.7554
957491	AF2-043 C	0.3283	Adder	0.73
957521	AF2-046 C	3.0020	Adder	6.66
957531	AF2-047 C	2.7542	Adder	6.11
957631	AF2-057	0.5420	Adder	1.2
957711	AF2-065 C	7.8237	80/20	7.8237
957791	AF2-073 C (Withdrawn : 07/02/2020)	1.5240	Adder	3.38
957801	AF2-074 C (Withdrawn : 07/02/2020)	0.6773	Adder	1.5
957821	AF2-076 C O2	0.8200	Adder	1.82
957861	AF2-080 C	1.2592	Adder	2.8
957871	AF2-081 C O2	1.4897	Adder	3.31
958141	AF2-108	3.0601	80/20	3.0601
958161	AF2-110 C	0.2394	Adder	0.53
959231	AF2-214 C	1.5601	Adder	3.46
959511	AF2-242	1.2762	Adder	2.83
959651	AF2-256 C	0.7291	80/20	0.7291
959661	AF2-257 C	0.7358	80/20	0.7358
959671	AF2-258 C	0.6332	80/20	0.6332

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
959681	AF2-259 C	2.6229	80/20	2.6229
959731	AF2-264 C	0.3985	Adder	0.88
960081	AF2-299 C	1.2732	80/20	1.2732
960101	AF2-301 C	0.4400	Adder	0.98
960121	AF2-303 C O2	2.9779	Adder	6.61
960131	AF2-304 C O2	9.1234	80/20	9.1234
960331	AF2-324 C O2	1.2637	Adder	2.81
960351	AF2-326 C (Withdrawn : 07/22/2020)	0.4122	Adder	0.91
960361	AF2-327 C (Withdrawn : 07/22/2020)	1.7446	80/20	1.7446
960831	AF2-374 C	0.2266	Adder	0.5
961091	AF2-400 C	0.0829	Adder	0.18
961111	AF2-402 C O2	0.6188	80/20	0.6188
WEC	WEC	0.1962	Confirmed LTF	0.1962
LGEE	LGEE	0.3742	Confirmed LTF	0.3742
CPL	CPL	2.5011	Confirmed LTF	2.5011
CBM-W2	CBM-W2	8.6241	Confirmed LTF	8.6241
NY	NY	0.4352	Confirmed LTF	0.4352
CBM-W1	CBM-W1	7.2058	Confirmed LTF	7.2058
TVA	TVA	1.8648	Confirmed LTF	1.8648
CBM-S2	CBM-S2	16.6637	Confirmed LTF	16.6637
CBM-S1	CBM-S1	10.2836	Confirmed LTF	10.2836
MADISON	MADISON	0.5867	Confirmed LTF	0.5867
MEC	MEC	1.2410	Confirmed LTF	1.2410
AA2-074	AA2-074	1.7042	LTF	1.7042

13.5.5 Index 5

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
98579133	314287	6CHESTF B	DVP	314225	6CHARCTY	DVP	1	DVP_P7-1: LN 208-259	tower	1204.0	100.61	102.29	DC	20.21

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
314314	3LOCKS	0.2795	50/50	0.2795
314435	6SAPONY	0.3292	50/50	0.3292
314539	3UNCAMP	0.8811	Adder	1.04
314541	3WATKINS	0.2516	Adder	0.3
315060	1CHESTF5 (Deactivation : 31/05/2023)	24.3596	Adder	28.66
315065	1CHESTF6 (Deactivation : 31/05/2023)	215.9070	50/50	215.9070
315073	1STONECA	6.8767	50/50	6.8767
315076	1HOPPOLC	1.6403	50/50	1.6403
315077	1HOPHCF1	2.5639	50/50	2.5639
315078	1HOPHCF2	2.5639	50/50	2.5639
315079	1HOPHCF3	2.5639	50/50	2.5639
315080	1HOPHCF4	3.8922	50/50	3.8922
315294	1DOMTR10	3.5102	Adder	4.13
315611	6Z1-036WIND	2.1047	Adder	2.48
900672	V4-068 E	0.1089	Adder	0.13
901082	W1-029 E	9.7202	Adder	11.44
907092	X1-038 E	2.2027	Adder	2.59
916042	Z1-036 E (Suspended)	14.1014	Adder	16.59
917122	Z2-027 E	0.3184	Adder	0.37
917332	Z2-043 E	0.4070	Adder	0.48
918492	AA1-063AE OP	1.5347	Adder	1.81
918512	AA1-065 E OP	1.3839	Adder	1.63
919692	AA2-053 E OP	1.4317	Adder	1.68
919702	AA2-057 E OP	1.1396	Adder	1.34
920042	AA2-088 E OP	3.8935	Adder	4.58
920592	AA2-165 E	0.1566	Adder	0.18
920672	AA2-174 E OP	0.1654	Adder	0.19
920692	AA2-178 E	1.3129	Adder	1.54
923262	AB1-132 C OP (Suspended)	6.0619	Adder	7.13
923263	AB1-132 E OP (Suspended)	2.5979	Adder	3.06
923572	AB1-173 C OP	0.9964	Adder	1.17
923573	AB1-173 E OP	0.4650	Adder	0.55
923582	AB1-173AC OP	0.9964	Adder	1.17
923583	AB1-173AE OP	0.4650	Adder	0.55
923801	AB2-015 C OP	3.1458	Adder	3.7
923802	AB2-015 E OP	2.5796	Adder	3.03
923852	AB2-025 E	0.8575	50/50	0.8575
923911	AB2-031 C O1	0.9890	Adder	1.16

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
923912	AB2-031 E O1	0.4871	Adder	0.57
923991	AB2-040 C O1	3.2474	Adder	3.82
923992	AB2-040 E O1	2.6570	Adder	3.13
924501	AB2-099 C (Suspended)	0.2080	Adder	0.24
924502	AB2-099 E (Suspended)	0.0891	Adder	0.1
924511	AB2-100 C	1.2673	50/50	1.2673
924512	AB2-100 E	3.6188	50/50	3.6188
924811	AB2-134 C OP	1.6684	50/50	1.6684
924812	AB2-134 E OP	9.5105	50/50	9.5105
925051	AB2-160 C O1 (Suspended)	4.9263	50/50	4.9263
925052	AB2-160 E O1 (Suspended)	8.0377	50/50	8.0377
925061	AB2-161 C O1 (Suspended)	2.2743	50/50	2.2743
925062	AB2-161 E O1 (Suspended)	3.7107	50/50	3.7107
925122	AB2-169 E	1.8582	Adder	2.19
925172	AB2-174 E O1	2.8792	Adder	3.39
925331	AB2-190 C	15.5467	50/50	15.5467
925332	AB2-190 E	6.6629	50/50	6.6629
926071	AC1-086 C	8.9268	Adder	10.5
926072	AC1-086 E	4.0629	Adder	4.78
926201	AC1-098 C	2.1471	Adder	2.53
926202	AC1-098 E	1.2791	Adder	1.5
926211	AC1-099 C	0.7195	Adder	0.85
926212	AC1-099 E	0.4226	Adder	0.5
926661	AC1-147 C	0.6785	Adder	0.8
926662	AC1-147 E	0.3985	Adder	0.47
927141	AC1-208 C	3.1880	Adder	3.75
927142	AC1-208 E	1.4156	Adder	1.67
927221	AC1-216 C O1	1.2738	50/50	1.2738
927222	AC1-216 E O1	5.8060	50/50	5.8060
932041	AC2-012 C	3.0693	Adder	3.61
932042	AC2-012 E	5.0078	Adder	5.89
932581	AC2-078 C O1	3.7269	50/50	3.7269
932582	AC2-078 E O1	6.0807	50/50	6.0807
932591	AC2-079 C O1	3.2303	50/50	3.2303
932592	AC2-079 E O1	5.2705	50/50	5.2705
932631	AC2-084 C	3.0607	Adder	3.6
932632	AC2-084 E	1.5075	Adder	1.77
933991	AD1-023 C	4.3365	Adder	5.1
933992	AD1-023 E	2.3608	Adder	2.78
934011	AD1-025 C	12.6897	50/50	12.6897
934012	AD1-025 E	7.5168	50/50	7.5168
934331	AD1-057 C O1	3.6776	Adder	4.33
934332	AD1-057 E O1	1.9618	Adder	2.31
934521	AD1-076 C	17.6860	Adder	20.81
934522	AD1-076 E	9.0057	Adder	10.59
934571	AD1-082 C	5.1830	50/50	5.1830
934572	AD1-082 E	2.9566	50/50	2.9566
935111	AD1-144 C	0.5577	Adder	0.66
935112	AD1-144 E	0.3047	Adder	0.36

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
935161	AD1-151 C O1	12.4929	50/50	12.4929
935162	AD1-151 E O1	8.3286	50/50	8.3286
936041	AD2-007 C	0.6062	50/50	0.6062
936042	AD2-007 E	0.4176	50/50	0.4176
936051	AD2-008 C	2.2092	50/50	2.2092
936052	AD2-008 E	4.8091	50/50	4.8091
936401	AD2-051 C O1	3.0421	Adder	3.58
936402	AD2-051 E O1	1.3062	Adder	1.54
936661	AD2-085 C	1.9558	50/50	1.9558
936662	AD2-085 E	3.1911	50/50	3.1911
937541	AD2-215 C	0.5634	Adder	0.66
937542	AD2-215 E	0.2990	Adder	0.35
938171	AE1-026 C O1	10.6695	Adder	12.55
938172	AE1-026 E O1	2.8149	Adder	3.31
938221	AE1-035 C	0.7727	Adder	0.91
938222	AE1-035 E	0.3806	Adder	0.45
938631	AE1-085 C O1	7.8565	50/50	7.8565
938632	AE1-085 E O1	3.9283	50/50	3.9283
938771	AE1-103 C O1	1.3216	Adder	1.55
938772	AE1-103 E O1	1.8251	Adder	2.15
939191	AE1-149 C O1	10.2822	50/50	10.2822
939192	AE1-149 E O1	6.8548	50/50	6.8548
939311	AE1-162 C	0.8674	Adder	1.02
939312	AE1-162 E	0.5783	Adder	0.68
940061	AE2-000BC O1	10.7730	50/50	10.7730
940062	AE2-000BE O1	7.1820	50/50	7.1820
940251	AE2-007 O1	51.5436	Adder	60.64
940431	AE2-027 C O1	7.7825	50/50	7.7825
940432	AE2-027 E O1	5.1883	50/50	5.1883
940481	AE2-033 C	11.9741	50/50	11.9741
940482	AE2-033 E	8.0724	50/50	8.0724
940491	AE2-034 C	2.2977	Adder	2.7
940492	AE2-034 E	0.9847	Adder	1.16
940541	AE2-040 O1	2.5442	50/50	2.5442
940651	AE2-052	3.4274	50/50	3.4274
940891	AE2-078 C	1.0311	Adder	1.21
940892	AE2-078 E	0.5312	Adder	0.62
940901	AE2-079 C	1.0311	Adder	1.21
940902	AE2-079 E	0.5312	Adder	0.62
941101	AE2-104 C O1	1.1939	Adder	1.4
941102	AE2-104 E O1	1.8982	Adder	2.23
941501	AE2-147 C	4.8333	Adder	5.69
941502	AE2-147 E	3.2222	Adder	3.79
941541	AE2-151 C	0.3818	Adder	0.45
941542	AE2-151 E	0.2056	Adder	0.24
941591	AE2-156 O1	5.3618	Adder	6.31
942001	AE2-212 C	3.1640	50/50	3.1640
942002	AE2-212 E	2.1094	50/50	2.1094
942131	AE2-225 C	0.6519	Adder	0.77
942132	AE2-225 E	0.4346	Adder	0.51
942161	AE2-228 C	3.6515	50/50	3.6515
942162	AE2-228 E	2.4343	50/50	2.4343

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
942171	AE2-229 C	0.6519	Adder	0.77
942172	AE2-229 E	0.4346	Adder	0.51
942341	AE2-247 C	0.8509	50/50	0.8509
942342	AE2-247 E	1.1751	50/50	1.1751
942371	AE2-250 C O1	8.7507	50/50	8.7507
942372	AE2-250 E O1	4.6184	50/50	4.6184
942471	AE2-260 C O1	9.3253	50/50	9.3253
942472	AE2-260 E O1	13.2267	50/50	13.2267
942551	AE2-270	20.1510	50/50	20.1510
942851	AE2-304 C	0.1935	Adder	0.23
942852	AE2-304 E	0.0753	Adder	0.09
943171	AE2-346 C	0.4992	Adder	0.59
943172	AE2-346 E	0.2140	Adder	0.25
943461	AF1-017 C	0.7699	50/50	0.7699
943462	AF1-017 E	1.2561	50/50	1.2561
943611	AF1-032 C	0.5324	Adder	0.63
943612	AF1-032 E	0.2825	Adder	0.33
943621	AF1-033 C	1.0311	Adder	1.21
943622	AF1-033 E	0.5312	Adder	0.62
943911	AF1-059	5.8939	Adder	6.93
944501	AF1-115 C O1	3.1402	Adder	3.69
944502	AF1-115 E O1	1.5467	Adder	1.82
944631	AF1-128 O1	18.9568	Adder	22.3
944871	AF1-152 C	1.6111	Adder	1.9
944872	AF1-152 E	1.0741	Adder	1.26
945711	AF1-236 C O1	25.1538	Adder	29.59
945712	AF1-236 E O1	41.0404	Adder	48.28
946002	AF1-265 BAT	11.4495	Merchant Transmission	11.4495
946011	AF1-266	10.0232	50/50	10.0232
946261	AF1-291 C	3.6802	50/50	3.6802
946262	AF1-291 E	2.4534	50/50	2.4534
946281	AF1-292 C	0.7204	Adder	0.85
946282	AF1-292 E	0.4857	Adder	0.57
957491	AF2-043 C	0.3455	Adder	0.77
957492	AF2-043 E	0.2303	Adder	0.51
957521	AF2-046 C	3.2335	Adder	7.18
957522	AF2-046 E	1.6265	Adder	3.61
957531	AF2-047 C	2.8936	Adder	6.42
957532	AF2-047 E	1.4555	Adder	3.23
957631	AF2-057	0.5708	Adder	1.27
957711	AF2-065 C	10.2770	50/50	10.2770
957712	AF2-065 E	9.8740	50/50	9.8740
957791	AF2-073 C (Withdrawn : 07/02/2020)	1.6084	Adder	3.57
957792	AF2-073 E (Withdrawn : 07/02/2020)	1.0283	Adder	2.28
957801	AF2-074 C (Withdrawn : 07/02/2020)	0.7148	Adder	1.59
957802	AF2-074 E (Withdrawn : 07/02/2020)	0.4570	Adder	1.01
957821	AF2-076 C O2	0.8625	Adder	1.91
957822	AF2-076 E O2	0.5750	Adder	1.28
958141	AF2-108	3.8089	50/50	3.8089

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
958161	AF2-110 C	0.2609	Adder	0.58
958162	AF2-110 E	0.4080	Adder	0.91
959651	AF2-256 C	0.9129	50/50	0.9129
959652	AF2-256 E	0.6086	50/50	0.6086
959661	AF2-257 C	0.9200	50/50	0.9200
959662	AF2-257 E	0.6134	50/50	0.6134
959671	AF2-258 C	0.7910	50/50	0.7910
959672	AF2-258 E	0.5273	50/50	0.5273
959681	AF2-259 C	3.2648	50/50	3.2648
959682	AF2-259 E	2.1765	50/50	2.1765
959731	AF2-264 C	0.4278	Adder	0.95
959732	AF2-264 E	0.2107	Adder	0.47
960081	AF2-299 C	0.6435	Adder	1.43
960082	AF2-299 E	0.4290	Adder	0.95
960101	AF2-301 C	0.5430	Adder	1.21
960102	AF2-301 E	0.3620	Adder	0.8
960131	AF2-304 C O2	11.9892	50/50	11.9892
960132	AF2-304 E O2	8.2173	50/50	8.2173
960361	AF2-327 C (Withdrawn : 07/22/2020)	2.1043	50/50	2.1043
960362	AF2-327 E (Withdrawn : 07/22/2020)	0.5261	50/50	0.5261
960831	AF2-374 C	0.2432	Adder	0.54
960832	AF2-374 E	0.3967	Adder	0.88
961091	AF2-400 C	0.0900	Adder	0.2
961092	AF2-400 E	0.1477	Adder	0.33
961111	AF2-402 C O2	0.7332	50/50	0.7332
961112	AF2-402 E O2	1.1987	50/50	1.1987
WEC	WEC	0.1616	Confirmed LTF	0.1616
LGEE	LGEE	0.3081	Confirmed LTF	0.3081
CPL	CPL	2.3258	Confirmed LTF	2.3258
CBM-W2	CBM-W2	7.4693	Confirmed LTF	7.4693
NY	NY	0.4125	Confirmed LTF	0.4125
CBM-W1	CBM-W1	5.8797	Confirmed LTF	5.8797
TVA	TVA	1.6380	Confirmed LTF	1.6380
O-066	O-066	5.6179	Confirmed LTF	5.6179
CBM-S2	CBM-S2	15.2361	Confirmed LTF	15.2361
CBM-S1	CBM-S1	8.9716	Confirmed LTF	8.9716
G-007	G-007	0.8746	Confirmed LTF	0.8746
MADISON	MADISON	0.5484	Confirmed LTF	0.5484
MEC	MEC	1.0472	Confirmed LTF	1.0472
AA2-074	AA2-074	1.5844	LTF	1.5844

13.5.6 Index 6

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804700	314303	6HOPEWLL	DVP	314287	6CHESTF B	DVP	1	DVP_P4-2: 56372	breaker	549.0	199.61	206.22	DC	36.23

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315060	1CHESTF5 (Deactivation : 31/05/2023)	37.5742	Adder	44.2
315073	1STONECA	13.1251	50/50	13.1251
315076	1HOPPOLC	3.1307	50/50	3.1307
315077	1HOPHCF1	4.8935	50/50	4.8935
315078	1HOPHCF2	4.8935	50/50	4.8935
315079	1HOPHCF3	4.8935	50/50	4.8935
315080	1HOPHCF4	7.4287	50/50	7.4287
315116	1SURRY 1	23.2824	50/50	23.2824
315119	1GRAVEL3	2.3652	50/50	2.3652
315120	1GRAVEL4	2.3955	50/50	2.3955
315121	1GRAVEL5	2.3652	50/50	2.3652
315122	1GRAVEL6	2.3927	50/50	2.3927
916192	Z1-068 E	0.6279	Adder	0.74
919152	AA1-139 E	1.9477	Adder	2.29
924811	AB2-134 C OP	2.9915	50/50	2.9915
924812	AB2-134 E OP	17.0527	50/50	17.0527
925331	AB2-190 C	28.0896	50/50	28.0896
925332	AB2-190 E	12.0384	50/50	12.0384
925522	AC1-027 E	0.3850	Adder	0.45
926661	AC1-147 C	0.8045	Adder	0.95
926662	AC1-147 E	0.4725	Adder	0.56
927221	AC1-216 C O1	2.2840	50/50	2.2840
927222	AC1-216 E O1	10.4104	50/50	10.4104
932041	AC2-012 C	3.6396	Adder	4.28
932042	AC2-012 E	5.9382	Adder	6.99
933731	AC2-196 C	0.5668	Adder	0.67
933732	AC2-196 E	0.3775	Adder	0.44
934011	AD1-025 C	22.7531	50/50	22.7531
934012	AD1-025 E	13.4779	50/50	13.4779
934061	AD1-033 C	2.3976	Adder	2.82
934062	AD1-033 E	1.5984	Adder	1.88
935111	AD1-144 C	0.6248	Adder	0.74
935112	AD1-144 E	0.3414	Adder	0.4
935161	AD1-151 C O1	22.5720	50/50	22.5720
935162	AD1-151 E O1	15.0480	50/50	15.0480
936041	AD2-007 C	1.0869	50/50	1.0869
936042	AD2-007 E	0.7488	50/50	0.7488
936051	AD2-008 C	3.9613	50/50	3.9613
936052	AD2-008 E	8.6230	50/50	8.6230
936762	AD2-097 E	-4.6231	Adder	-5.44
937221	AD2-160 C O1	1.7988	Adder	2.12

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937222	AD2-160 E O1	0.9433	Adder	1.11
937251	AD2-164 (Withdrawn : 06/30/2020)	1.6949	Adder	1.99
937541	AD2-215 C	0.6312	Adder	0.74
937542	AD2-215 E	0.3349	Adder	0.39
938531	AE1-072 C O1	5.2582	Adder	6.19
938532	AE1-072 E O1	2.7411	Adder	3.22
939311	AE1-162 C	1.3014	Adder	1.53
939312	AE1-162 E	0.8676	Adder	1.02
940251	AE2-007 O1	60.7387	Adder	71.46
940542	AE2-040 BAT	1.5771	Merchant Transmission	1.5771
940891	AE2-078 C	1.6591	Adder	1.95
940892	AE2-078 E	0.8547	Adder	1.01
940901	AE2-079 C	1.6591	Adder	1.95
940902	AE2-079 E	0.8547	Adder	1.01
941281	AE2-122 C O1	9.4573	Adder	11.13
941282	AE2-122 E O1	38.1623	Adder	44.9
941291	AE2-123 C O1	9.7191	Adder	11.43
941292	AE2-123 E O1	37.9004	Adder	44.59
941301	AE2-124 C O1	8.7739	Adder	10.32
941302	AE2-124 E O1	38.4988	Adder	45.29
941591	AE2-156 O1	6.3521	Adder	7.47
942151	AE2-227 C	0.7603	Adder	0.89
942152	AE2-227 E	0.5069	Adder	0.6
942401	AE2-253 C	1.8920	Adder	2.23
942402	AE2-253 E	0.8501	Adder	1.0
942551	AE2-270	36.1050	50/50	36.1050
943621	AF1-033 C	1.6591	Adder	1.95
943622	AF1-033 E	0.8547	Adder	1.01
944501	AF1-115 C O1	5.0527	Adder	5.94
944502	AF1-115 E O1	2.4887	Adder	2.93
944581	AF1-123 C O1	14.3997	Adder	16.94
944582	AF1-123 E O1	32.9712	Adder	38.79
944591	AF1-124 C O1	14.3997	Adder	16.94
944592	AF1-124 E O1	32.9712	Adder	38.79
944601	AF1-125 C O1	14.3997	Adder	16.94
944602	AF1-125 E O1	32.9712	Adder	38.79
944631	AF1-128 O1	29.2405	Adder	34.4
945361	AF1-201 C O1	4.6963	Adder	5.53
945362	AF1-201 E O1	3.1309	Adder	3.68
946012	AF1-266 BAT	9.4801	Merchant Transmission	9.4801
957631	AF2-057	0.6768	Adder	1.5
957711	AF2-065 C	18.4136	50/50	18.4136
957712	AF2-065 E	17.6915	50/50	17.6915
957871	AF2-081 C O2	1.6075	Adder	3.57
957872	AF2-081 E O2	0.6889	Adder	1.53
958142	AF2-108 BAT	1.3579	50/50	1.3579
959641	AF2-255 C	0.1007	Adder	0.22
959642	AF2-255 E	0.0672	Adder	0.15
960101	AF2-301 C	0.8591	Adder	1.91
960102	AF2-301 E	0.5727	Adder	1.27
960131	AF2-304 C O2	21.4971	50/50	21.4971
960132	AF2-304 E O2	14.7339	50/50	14.7339

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
LGEE	LGEE	0.0068	Confirmed LTF	0.0068
CPL	CPL	0.7111	Confirmed LTF	0.7111
CBM-W2	CBM-W2	1.3186	Confirmed LTF	1.3186
NY	NY	0.2959	Confirmed LTF	0.2959
TVA	TVA	0.3724	Confirmed LTF	0.3724
O-066	O-066	3.8304	Confirmed LTF	3.8304
CBM-S2	CBM-S2	4.7338	Confirmed LTF	4.7338
CBM-S1	CBM-S1	1.8659	Confirmed LTF	1.8659
TILTON	TILTON	0.0013	Confirmed LTF	0.0013
G-007	G-007	0.5959	Confirmed LTF	0.5959
MADISON	MADISON	0.2197	Confirmed LTF	0.2197
MEC	MEC	0.0953	Confirmed LTF	0.0953

13.5.7 Index 7

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
97804730	314303	6HOPEWLL	DVP	314286	6CHESTF A	DVP	1	DVP_P4-2: 211T2124	breaker	549.0	172.2	183.87	DC	64.01

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
315073	1STONECA	24.1256	50/50	24.1256
315076	1HOPPOLC	5.7546	50/50	5.7546
315077	1HOPHCF1	8.9949	50/50	8.9949
315078	1HOPHCF2	8.9949	50/50	8.9949
315079	1HOPHCF3	8.9949	50/50	8.9949
315080	1HOPHCF4	13.6549	50/50	13.6549
315116	1SURRY 1	38.2286	50/50	38.2286
315119	1GRAVEL3	3.8835	50/50	3.8835
315120	1GRAVEL4	3.9333	50/50	3.9333
315121	1GRAVEL5	3.8835	50/50	3.8835
315122	1GRAVEL6	3.9288	50/50	3.9288
924811	AB2-134 C OP	5.2848	50/50	5.2848
924812	AB2-134 E OP	30.1257	50/50	30.1257
925331	AB2-190 C	49.8770	50/50	49.8770
925332	AB2-190 E	21.3758	50/50	21.3758
925522	AC1-027 E	0.4892	Adder	0.58
926661	AC1-147 C	1.0430	Adder	1.23
926662	AC1-147 E	0.6126	Adder	0.72
927221	AC1-216 C O1	4.0349	50/50	4.0349
927222	AC1-216 E O1	18.3912	50/50	18.3912
932041	AC2-012 C	4.7185	Adder	5.55
932042	AC2-012 E	7.6987	Adder	9.06
934011	AD1-025 C	40.1961	50/50	40.1961
934012	AD1-025 E	23.8104	50/50	23.8104
935111	AD1-144 C	0.8595	Adder	1.01
935112	AD1-144 E	0.4696	Adder	0.55
935161	AD1-151 C O1	40.0797	50/50	40.0797
935162	AD1-151 E O1	26.7198	50/50	26.7198
936041	AD2-007 C	1.9202	50/50	1.9202
936042	AD2-007 E	1.3228	50/50	1.3228
936051	AD2-008 C	6.9980	50/50	6.9980
936052	AD2-008 E	15.2335	50/50	15.2335
937541	AD2-215 C	0.8684	Adder	1.02
937542	AD2-215 E	0.4608	Adder	0.54
939311	AE1-162 C	2.0341	Adder	2.39
939312	AE1-162 E	1.3561	Adder	1.6
940251	AE2-007 O1	77.8376	Adder	91.57
940891	AE2-078 C	2.6455	Adder	3.11
940892	AE2-078 E	1.3628	Adder	1.6
940901	AE2-079 C	2.6455	Adder	3.11
940902	AE2-079 E	1.3628	Adder	1.6

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
941591	AE2-156 O1	8.1966	Adder	9.64
942551	AE2-270	63.7515	50/50	63.7515
943621	AF1-033 C	2.6455	Adder	3.11
943622	AF1-033 E	1.3628	Adder	1.6
944501	AF1-115 C O1	8.0566	Adder	9.48
944502	AF1-115 E O1	3.9682	Adder	4.67
957631	AF2-057	0.8775	Adder	1.95
957711	AF2-065 C	32.5133	50/50	32.5133
957712	AF2-065 E	31.2382	50/50	31.2382
960101	AF2-301 C	1.2807	Adder	2.84
960102	AF2-301 E	0.8538	Adder	1.9
960131	AF2-304 C O2	37.9772	50/50	37.9772
960132	AF2-304 E O2	26.0293	50/50	26.0293
LGEE	LGEE	0.0029	Confirmed LTF	0.0029
CPL	CPL	1.0478	Confirmed LTF	1.0478
CBM-W2	CBM-W2	1.6298	Confirmed LTF	1.6298
NY	NY	0.3650	Confirmed LTF	0.3650
TVA	TVA	0.4676	Confirmed LTF	0.4676
O-066	O-066	4.7242	Confirmed LTF	4.7242
EDWARDS	EDWARDS	0.0007	Confirmed LTF	0.0007
CBM-S2	CBM-S2	6.3869	Confirmed LTF	6.3869
CBM-S1	CBM-S1	2.3260	Confirmed LTF	2.3260
TILTON	TILTON	0.0076	Confirmed LTF	0.0076
G-007	G-007	0.7332	Confirmed LTF	0.7332
MADISON	MADISON	0.2843	Confirmed LTF	0.2843
MEC	MEC	0.1081	Confirmed LTF	0.1081
BLUEG	BLUEG	0.0069	Confirmed LTF	0.0069
TRIMBLE	TRIMBLE	0.0056	Confirmed LTF	0.0056

13.6 Contingency Descriptions - Secondary POI

Contingency Name	Contingency Definition
DVP_P4-2: 211T2124	CONTINGENCY 'DVP_P4-2: 211T2124' /* HOPEWELL 230 KV OPEN BRANCH FROM BUS 314287 TO BUS 314303 CKT 1 /* 6CHESTF B 230.00 - 6HOPEWLL 230.00 OPEN BRANCH FROM BUS 314269 TO BUS 314291 CKT 1 /* 6PRGEORG 230.00 - 3PRGEORG 115.00 OPEN BRANCH FROM BUS 314269 TO BUS 314303 CKT 1 /* 6PRGEORG 230.00 - 6HOPEWLL 230.00 OPEN BUS 314269 /* ISLAND: 6PRGEORG 230.00 END
DVP_P1-2: LN 563	CONTINGENCY 'DVP_P1-2: LN 563' OPEN BRANCH FROM BUS 314902 TO BUS 314914 CKT 1 /* 8CARSON 500.00 - 8MDLTHAN 500.00 END
DVP_P1-2: LN 228	CONTINGENCY 'DVP_P1-2: LN 228' OPEN BRANCH FROM BUS 314286 TO BUS 314303 CKT 1 /* 6CHESTF A 230.00 - 6HOPEWLL 230.00 END
DVP_P1-2: LN 208	CONTINGENCY 'DVP_P1-2: LN 208' OPEN BRANCH FROM BUS 314286 TO BUS 314309 CKT 1 /* 6CHESTF A 230.00 - 6IRON208 230.00 OPEN BRANCH FROM BUS 314309 TO BUS 314338 CKT 1 /* 6IRON208 230.00 - 6SOUWEST 230.00 OPEN BUS 314309 /* ISLAND: 6IRON208 230.00 END
DVP_P1-2: LN 240	CONTINGENCY 'DVP_P1-2: LN 240' OPEN BRANCH FROM BUS 314303 TO BUS 925330 CKT 2 /* 6HOPEWLL 230.00 - AB2- 190 TAP 230.00 END
DVP_P4-2: 562T563	CONTINGENCY 'DVP_P4-2: 562T563' /* CARSON 500 KV OPEN BRANCH FROM BUS 314902 TO BUS 940640 CKT 1 /* 8CARSON 500.00 - AE2- 051 TAP 500.00 OPEN BRANCH FROM BUS 314902 TO BUS 314914 CKT 1 /* 8CARSON 500.00 - 8MDLTHAN 500.00 END

Contingency Name	Contingency Definition
DVP_P4-2: 240T2041	CONTINGENCY 'DVP_P4-2: 240T2041' /* HOPEWELL 230 KV OPEN BRANCH FROM BUS 314303 TO BUS 925330 CKT 2 /* 6HOPEWLL 230.00 - AB2-190 TAP 230.00 OPEN BUS 315077 /* 1HOPHCF1 13.800 KV OPEN BUS 315078 /* 1HOPHCF2 13.800 KV OPEN BUS 315079 /* 1HOPHCF3 13.800 KV OPEN BUS 315080 /* 1HOPHCF4 13.800 KV END
DVP_P1-2: LN 594	CONTINGENCY 'DVP_P1-2: LN 594' OPEN BRANCH FROM BUS 314916 TO BUS 314934 CKT 1 /* 8MORRSVL 500.00 - 8SPOTSYL 500.00 END
DVP_P4-2: 56372	CONTINGENCY 'DVP_P4-2: 56372' /* CARSON 500 KV OPEN BRANCH FROM BUS 314902 TO BUS 314914 CKT 1 /* 8CARSON 500.00 - 8MDLTHAN 500.00 OPEN BRANCH FROM BUS 314282 TO BUS 314902 CKT 1 /* 6CARSON 230.00 - 8CARSON 500.00 END
DVP_P4-2: 531T582	CONTINGENCY 'DVP_P4-2: 531T582' /* SURRY 500 KV OPEN BRANCH FROM BUS 314924 TO BUS 314928 CKT 1 /* 8SURRY 500.00 - 8SUFFOLK 500.00 OPEN BRANCH FROM BUS 314924 TO BUS 314931 CKT 1 /* 8SURRY 500.00 - 8SKIFF CREEK500.00 END
DVP_P4-2: G5T228	CONTINGENCY 'DVP_P4-2: G5T228' /* CHESTERFIELD 230 230 KV OPEN BRANCH FROM BUS 314286 TO BUS 314303 CKT 1 /* 6CHESTF A 230.00 - 6HOPEWLL 230.00 OPEN BRANCH FROM BUS 314286 TO BUS 315060 CKT 1 /* 6CHESTF A 230.00 - 1CHESTF5 22.000 OPEN BUS 315060 /* ISLAND: 1CHESTF5 22.000 END
DVP_P1-2: LN 573	CONTINGENCY 'DVP_P1-2: LN 573' OPEN BRANCH FROM BUS 314918 TO BUS 314934 CKT 1 /* 8NO ANNA 500.00 - 8SPOTSYL 500.00 END
DVP_P1-2: LN 579	CONTINGENCY 'DVP_P1-2: LN 579' OPEN BRANCH FROM BUS 314923 TO BUS 314927 CKT 1 /* 8SEPTA 500.00 - 8YADKIN 500.00 END

Contingency Name	Contingency Definition
DVP_P1-2: LN 211	CONTINGENCY 'DVP_P1-2: LN 211' OPEN BRANCH FROM BUS 314287 TO BUS 314303 CKT 1 /* 6CHESTF B 230.00 - 6HOPEWLL 230.00 END
DVP_P1-2: LN 557	CONTINGENCY 'DVP_P1-2: LN 557' OPEN BRANCH FROM BUS 314214 TO BUS 314903 CKT 1 /* 6CHCKAHM 230.00 - 8CHCKAHM 500.00 OPEN BRANCH FROM BUS 314903 TO BUS 314908 CKT 1 /* 8CHCKAHM 500.00 - 8ELMONT 500.00 END
DVP_P1-2: LN 259	CONTINGENCY 'DVP_P1-2: LN 259' OPEN BRANCH FROM BUS 314276 TO BUS 314287 CKT 1 /* 6BASIN 230.00 - 6CHESTF B 230.00 END
DVP_P1-2: LN 217	CONTINGENCY 'DVP_P1-2: LN 217' OPEN BRANCH FROM BUS 314225 TO BUS 314227 CKT 1 /* 6CHARCTY 230.00 - 6LAKESIDE 230.00 OPEN BRANCH FROM BUS 314225 TO BUS 314287 CKT 1 /* 6CHARCTY 230.00 - 6CHESTF B 230.00 OPEN BUS 314225 /* ISLAND: 6CHARCTY 230.00 END
DVP_P7-1: LN 223-226	CONTINGENCY 'DVP_P7-1: LN 223-226' /* . OPEN BRANCH FROM BUS 314475 TO BUS 314514 CKT 1 /* 6HARBORV 230.00 - 6YADKIN 230.00 OPEN BRANCH FROM BUS 314475 TO BUS 314533 CKT 1 /* 6HARBORV 230.00 - 6SMITFLD 230.00 OPEN BRANCH FROM BUS 314533 TO BUS 314538 CKT 1 /* 6SMITFLD 230.00 - 6SURREY 230.00 OPEN BUS 314475 /* ISLAND: 6HARBORV 230.00 OPEN BUS 314533 /* ISLAND: 6SMITFLD 230.00 OPEN BRANCH FROM BUS 314453 TO BUS 314484 CKT 1 /* 6CHRHLND 230.00 - 6HARBORV226 230.00 OPEN BRANCH FROM BUS 314484 TO BUS 314523 CKT 1 /* 6HARBORV226 230.00 - 6CRITTDN 230.00 OPEN BRANCH FROM BUS 314523 TO BUS 314538 CKT 1 /* 6CRITTDN 230.00 - 6SURREY 230.00 OPEN BUS 314484 /* ISLAND: 6HARBORV226 230.00 OPEN BUS 314523 /* ISLAND: 6CRITTDN 230.00 END
DVP_P1-2: LN 576	CONTINGENCY 'DVP_P1-2: LN 576' OPEN BRANCH FROM BUS 314914 TO BUS 314918 CKT 1 /* 8MDLTHAN 500.00 - 8NO ANNA 500.00 END

Contingency Name	Contingency Definition
DVP_P1-2: LN 531	CONTINGENCY 'DVP_P1-2: LN 531' OPEN BRANCH FROM BUS 314924 TO BUS 314928 CKT 1 /* 8SURRY 500.00 - 8SUFFOLK 500.00 END
Base Case	
DVP_P7-1: LN 208-259	CONTINGENCY 'DVP_P7-1: LN 208-259' /* . OPEN BRANCH FROM BUS 314286 TO BUS 314309 CKT 1 /* 6CHESTF A 230.00 - 6IRON208 230.00 OPEN BRANCH FROM BUS 314309 TO BUS 314338 CKT 1 /* 6IRON208 230.00 - 6SOUWEST 230.00 OPEN BUS 314309 /* ISLAND: 6IRON208 230.00 OPEN BRANCH FROM BUS 314276 TO BUS 314287 CKT 1 /* 6BASIN 230.00 - 6CHESTF B 230.00 END
DVP_P1-2: LN 581	CONTINGENCY 'DVP_P1-2: LN 581' OPEN BRANCH FROM BUS 314135 TO BUS 314905 CKT 2 /* 3CHANCE 115.00 - 8CHANCE 500.00 OPEN BRANCH FROM BUS 314905 TO BUS 314911 CKT 1 /* 8CHANCE 500.00 - 8LADYSMITH 500.00 END
DVP_P1-2: LN 2197	CONTINGENCY 'DVP_P1-2: LN 2197' OPEN BRANCH FROM BUS 313896 TO BUS 314303 CKT 1 /* 6COLONIAL TR230.00 - 6HOPEWELL 230.00 END

14 Affected Systems

14.1 TVA

TVA Impacts to be determined during later study phases (as applicable).

14.2 Duke Energy Progress

Duke Energy Progress Impacts to be determined during later study phases (as applicable).