



**Generation Interconnection
Feasibility Study Report
for
Queue Project AF2-441
“BURNHAM 138 KV”**

July 2020

1 Introduction

This Feasibility Study has been prepared in accordance with the PJM Open Access Transmission Tariff, 36.2, as well as the Feasibility Study Agreement between the Interconnection Customer (IC), and PJM Interconnection, LLC (PJM), Transmission Provider (TP). The Interconnected Transmission Owner (ITO) is ComEd.

2 Preface

The intent of the Feasibility Study is to determine a plan, with ballpark cost and construction time estimates, to connect the subject generation to the PJM network at a location specified by the Interconnection Customer. The Interconnection Customer may request the interconnection of generation as a capacity resource or as an energy-only resource. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: (1) Direct Connections, which are new facilities and/or facilities upgrades needed to connect the generator to the PJM network, and (2) Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system.

In some instances a generator interconnection may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection, may also contribute to the need for the same network reinforcement. Cost allocation rules for network upgrades can be found in PJM Manual 14A, Attachment B. The possibility of sharing the reinforcement costs with other projects may be identified in the feasibility study, but the actual allocation will be deferred until the impact study is performed.

An Interconnection Customer with a proposed new Customer Facility that has a Maximum Facility Output equal to or greater than 100 MW shall install and maintain, at its expense, phasor measurement units (PMUs). See Section 8.5.3 of Appendix 2 to the Interconnection Service Agreement as well as section 4.3 of PJM Manual 14D for additional information.

The Feasibility Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer is responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

3 General

The Interconnection Customer (IC) has proposed a storage generating facility located in Cook County, Illinois. The installed facilities will have a total capability of 200 MW with 80 MW of this output being recognized by PJM as Capacity. The proposed in-service date for this project is May 31, 2024. This study does not imply a TO commitment to this in-service date.

Queue Number	AF2-441
Project Name	BURNHAM 138KV
State	Illinois
County	Cook
Transmission Owner	ComEd
MFO	200
MWE	200
MWC	80
Fuel	Storage
Basecase Study Year	2023

A new service customer with a generating facility that could be commercially operable prior to June 1st of the basecase study year is required to request an interim deliverability analysis from PJM.

4 Point of Interconnection

Queue Position AF2-441, a 200 MW battery storage facility, proposes to interconnect with the ComEd transmission system by tying into the 138kV bus at the Burnham TSS 177 Substation.

5 Cost Summary

The AF2-441 project will be responsible for the following costs:

Description	Total Cost
Total Physical Interconnection Costs	\$9,000,000
Total System Network Upgrade Costs	\$11,000,000
Total Costs	\$20,000,000

This cost excludes a Federal Income Tax Gross Up charges. This tax may or may not be charged based on whether this project meets the eligibility requirements of IRS Notice 88-129. If at a future date it is determined that the Federal Income Tax Gross charge is required, the Transmission Owner shall be reimbursed by the Interconnection Customer for such taxes.

6 Transmission Owner Scope of Work

Attachment Facilities

The AF2-441 generator lead would interconnect to the 138kV bus at the Burnham TSS 177 Substation. The required Attachment Facilities are one 138kV circuit breaker, a dead-end structure and revenue metering. Additionally, the generator lead will have to cross three 138kV overhead transmission lines to enter the 138kV switchgear at Burnham TSS 177, as shown in the one-line diagram.

Scope of Work	Cost Estimate
Installation of one 138kV line circuit breaker, one dead-end structure and one set of revenue metering (see notes below on cost estimate)	\$4,000,000
Generator lead crossing three 138kV overhead lines	\$2,000,000
Total Cost Estimate (see notes below on cost estimate)	\$6,000,000

Direct Connection Network Upgrades

To accommodate interconnection of AF2-441, the existing 138kV Blue bus at Burnham TSS 177 would need to be split to satisfy ComEd's Design Philosophy.

The scope of work includes the installation of one 138kV circuit breaker to split the Blue bus at Burnham TSS 177, as shown in the one-line diagram below.

The Interconnection Customer ("IC") is responsible for constructing all of the facilities on the IC side of the Point of Interconnection ("POI") outside of the substation.

The estimated cost for the Direct Connection Network upgrade is given below.

Scope of Work	Cost Estimate
Installation of one 138kV circuit breakers at Burnham TSS 177 and relay/protection work	\$3,000,000
Total Cost Estimate (see notes below on cost estimate)	\$3,000,000

ComEd would take approximately 24-months to construct the substation and transmission line work after the ISA / ICSA are signed.

Non-Direct Connection Network Upgrades

None

Notes on Cost Estimate:

- 1) These estimates are Order-of-Magnitude estimates of the costs that ComEd would bill to the customer for this interconnection. These estimates are based on a one-line electrical diagram of the project and the information provided by the IC.
- 2) There were no site visits performed for these estimates. There may be costs related to specific site related issues that are not identified in these estimates. The site reviews will be performed during the Facilities Study or during detailed engineering.
- 3) These estimates are not a guarantee of the maximum amount payable by the IC and the actual costs of ComEd's work may differ significantly from these estimates. The IC will be responsible for paying actual costs of ComEd's work in accordance with Sections 212.1 and 217 of the PJM Open Access Transmission Tariff.
- 4) The IC is responsible for all engineering, procurement, testing and construction of all equipment on the IC's side of the POI.
- 5) These cost estimates do not include cost of acquiring right-of-way for the transmission line and purchasing any additional land, if needed, for the line terminations. The need and cost of acquiring property and associated legal costs will be investigated during Facilities Study for this project.

7 Schedule

See Sections 6 and 11.5.

8 Transmission Owner Analysis

See Section 6.

9 Interconnection Customer Requirements

The Interconnection Customer is responsible for all design and construction related activities on the Interconnection Customer's side of the Point of Interconnection.

10 Revenue Metering and SCADA Requirements

10.1 PJM Requirements

The Interconnection Customer will be required to install equipment necessary to provide Revenue Metering (KWH, KVARH) and real time data (KW, KVAR) for IC's generating Resource. See PJM Manuals M-01 and M-14D, and PJM Tariff Section 8 of Attachment O.

10.2 Interconnected Transmission Owner Requirements

The IC will be required to comply with all Interconnected Transmission Owner's revenue metering requirements for generation interconnection customers located at the following link:

ComEd interconnection requirements can be found at <https://www.pjm.com/planning/design-engineering/to-tech-standards/private-comed.aspx>

To the extent that these Applicable Technical Requirements and Standards may conflict with the terms and conditions of the Tariff, the Tariff shall control.

11 Summer Peak - Load Flow Analysis - Primary POI

The Queue Project AF2-441 was evaluated as a 200.0 MW (Capacity 80.0 MW) injection at the Burnham 138 kV substation in the ComEd area. Project AF2-441 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AF2-441 was studied with a commercial probability of 53.0 %. Potential network impacts were as follows:

11.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

11.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

None

11.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJE CT LOADIN G %	POST PROJE CT LOADIN G %	AC D C	MW IMPAC T
95579259	255113	17STILLWELL	345.0	NIPS	243219	05DUMONT	345.0	AEP	1	COMED_P1-2_695_B2	single	1409.0	109.0	110.08	DC	15.11
96795144	270926	WILTON ; B	345.0	CE	275232	WILTON ;3M	345.0	CE	1	COMED_P4_112-65-BT5-6_	breaker	1379.0	122.21	122.27	DC	30.47
96795132	270927	WILTON ; R	345.0	CE	275233	WILTON ;4M	345.0	CE	1	COMED_P4_112-65-BT2-3_	breaker	1379.0	124.77	124.83	DC	31.12
96795143	275232	WILTON ;3M	345.0	CE	270644	WILTON ;	765.0	CE	1	COMED_P4_112-65-BT5-6_	breaker	1379.0	122.21	122.27	DC	30.47
96795131	275233	WILTON ;4M	345.0	CE	270644	WILTON ;	765.0	CE	1	COMED_P4_112-65-BT2-3_	breaker	1379.0	124.77	124.83	DC	31.12

11.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

None

11.5 System Reinforcements - Summer Peak Load Flow - Primary POI

ID	Idx	Facility	Upgrade Description	Cost
96795132	3	WILTON ; R 345.0 kV - WILTON ;4M 345.0 kV Ckt 1	n5145 (887) : PJM Network Upgrade (n5145): Reconfigure Wilton 765kV bus thereby allowing for 765kV L11216 (currently on Bus 6) to be relocated to Bus 8. Along with this line relocation, installation of 2-765kV BT CBs (6-8 & 8-2). Project Type : CON Cost : \$11,000,000 Time Estimate : 36-40 Months	\$11,000,000
96795131	5	WILTON ;4M 345.0 kV - WILTON ; 765.0 kV Ckt 1		
96795143	4	WILTON ;3M 345.0 kV - WILTON ; 765.0 kV Ckt 1		
96795144	2	WILTON ; B 345.0 kV - WILTON ;3M 345.0 kV Ckt 1		

ID	Idx	Facility	Upgrade Description	Cost
95579259	1	17STILLWELL 345.0 kV - 05DUMONT 345.0 kV Ckt 1	<p><u>AEP</u> n4790 (510) : PJM Network Upgrade n4790. Replace Dumont substation 2500A wavetrap. The network project had a projected in-service date of 06/01/2019 and an estimated cost of \$200,000.</p> <p>This Queue Project presently does not receive cost allocation for this upgrade. Note 1: as changes to the interconnection process occur, such as prior queued projects withdrawing from the queue, reducing in size, etc., this Queue Project could receive cost allocation. Note 2: Although this Queue Project may not have cost responsibility for this upgrade, the project may need this upgrade in-service to be deliverable to the PJM system. If this project comes into service prior to completion of the upgrade, this project will need an interim study.</p> <p>Project Type : FAC Cost : \$0 Time Estimate : N/A Months</p> <p>NonPJMArea (1662) : The external (i.e. Non-PJM) Transmission Owner, NIPS, will not evaluate this violation until the impact study phase. Project Type : FAC Cost : \$0 Time Estimate : N/A Months</p>	\$0
			TOTAL COST	\$11,000,000

Cost allocations for any System Upgrades will be provided in the System Impact Study Report.

11.6 Flow Gate Details - Primary POI

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

11.6.1 Index 1

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
----	-----------	----------	---------------	---------	--------	-------------	--------	-----------	------	------------	-----------------------	------------------------	-------	-----------

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
95579259	255113	17STILLWELL	NIPS	243219	05DUMONT	AEP	1	COMED_P1-2_695_B2	single	1409.0	109.0	110.08	DC	15.11

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274723	RIVER EC ;12	5.5486	80/20	5.5486
274724	RIVER EC ;11	5.5078	80/20	5.5078
274788	SE CHICAG;5U (Deactivation : 01/06/2020)	7.5182	80/20	7.5182
274789	SE CHICAG;6U (Deactivation : 01/06/2020)	7.5381	80/20	7.5381
274790	SE CHICAG;7U (Deactivation : 01/06/2020)	7.6372	80/20	7.6372
274791	SE CHICAG;8U (Deactivation : 01/06/2020)	7.6372	80/20	7.6372
274792	SE CHICAG;9U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274793	SE CHICAG;0U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274794	SE CHICAG;1U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274795	SE CHICAG;2U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274798	UNIV PARK;1U	1.5551	80/20	1.5551
274801	UNIV PARK;4U	1.5435	80/20	1.5435
274826	FISK ;BP	2.9034	80/20	2.9034
274827	FISK ;RP	2.0577	80/20	2.0577
274830	U3-021 1	6.0871	Adder	7.16
274831	U3-021 2	6.0871	Adder	7.16
276164	X3-005 C	0.1075	80/20	0.1075
293540	O-012 C	0.6150	80/20	0.6150
915011	Y3-013 1	3.7444	Adder	4.41
915021	Y3-013 2	3.7444	Adder	4.41
915031	Y3-013 3	3.7444	Adder	4.41
919581	AA2-030	17.5313	Adder	20.63
924041	AB2-047 C O1	3.3636	Adder	3.96
924471	AB2-096	42.2718	Adder	49.73
925581	AC1-033 C	1.4016	Adder	1.65
926311	AC1-109 1	1.9040	Adder	2.24
926321	AC1-109 2	1.9040	Adder	2.24
926331	AC1-110 1	1.8980	Adder	2.23
926341	AC1-110 2	1.8980	Adder	2.23
926351	AC1-111 1	0.7620	Adder	0.9
926361	AC1-111 2	0.7620	Adder	0.9

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
926371	AC1-111 3	0.7620	Adder	0.9
926381	AC1-111 4	0.7620	Adder	0.9
926391	AC1-111 5	0.7620	Adder	0.9
926401	AC1-111 6	0.7620	Adder	0.9
926431	AC1-114	2.3739	Adder	2.79
926821	AC1-168 C O1	1.1406	Adder	1.34
926841	AC1-171 C O1	1.0368	Adder	1.22
927201	AC1-214 C O1	2.0483	Adder	2.41
927451	AC1-142A 1	4.2157	Adder	4.96
927461	AC1-142A 2	4.2160	Adder	4.96
927511	AC1-113 1	1.1869	Adder	1.4
927521	AC1-113 2	1.1869	Adder	1.4
930481	AB1-089	65.6043	Adder	77.18
930501	AB1-091 O1	76.9692	Adder	90.55
930741	AB1-122 1O1	71.4553	Adder	84.07
930751	AB1-122 2O1	73.8990	Adder	86.94
932881	AC2-115 1	2.3739	Adder	2.79
932891	AC2-115 2	2.3739	Adder	2.79
932921	AC2-116	0.8309	Adder	0.98
932931	AC2-117	5.1330	Adder	6.04
933411	AC2-154 C	2.6404	Adder	3.11
933431	AC2-156 C O1	0.9541	Adder	1.12
933911	AD1-013 C	1.8539	Adder	2.18
933931	AD1-016 C	0.9273	Adder	1.09
934051	AD1-031 C O1	2.8459	Adder	3.35
934101	AD1-039 1	7.0026	Adder	8.24
934111	AD1-039 2	7.2421	Adder	8.52
934431	AD1-067 C	0.1318	Adder	0.16
934651	AD1-096 C	0.8893	Adder	1.05
934701	AD1-098 C O1	6.9062	Adder	8.12
934721	AD1-100 C	19.5139	Adder	22.96
934871	AD1-116 C	0.9472	Adder	1.11
934971	AD1-129 C	0.9021	Adder	1.06
935001	AD1-133 C O1	20.6718	Adder	24.32
936291	AD2-038 C O1	2.3283	Adder	2.74
936371	AD2-047 C O1	4.7249	Adder	5.56
936461	AD2-060	2.7793	Adder	3.27
936511	AD2-066 C O1	8.3972	Adder	9.88
936791	AD2-102 C	14.1066	Adder	16.6
937001	AD2-134 C	2.7442	Adder	3.23
937311	AD2-172 C	2.4544	Adder	2.89
937401	AD2-194 1	7.7948	Adder	9.17
937411	AD2-194 2	7.7923	Adder	9.17
937531	AD2-214 C	4.3946	Adder	5.17
938511	AE1-070 1	9.1589	Adder	10.78
938521	AE1-070 2	8.3767	Adder	9.85
938851	AE1-113 C	7.9623	Adder	9.37
938861	AE1-114 C O1	3.9206	Adder	4.61
939051	AE1-134 1	1.3623	Adder	1.6
939061	AE1-134 2	1.3623	Adder	1.6
939321	AE1-163 C O1	5.8506	Adder	6.88
939351	AE1-166 C O1	10.2692	Adder	12.08

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
939401	AE1-172 C O1	5.2573	Adder	6.19
939631	AE1-193 C	9.0290	Adder	10.62
939641	AE1-194 C	9.0290	Adder	10.62
939651	AE1-195 C	9.0290	Adder	10.62
939681	AE1-198 C	26.8091	Adder	31.54
939741	AE1-205 C O1	8.6937	Adder	10.23
940101	AE1-252 C O1	10.5616	Adder	12.43
940501	AE2-035 C	2.4544	Adder	2.89
941131	AE2-107 C	7.3063	Adder	8.6
941551	AE2-152 C O1	11.8491	Adder	13.94
941561	AE2-153 C O1	4.7360	Adder	5.57
941731	AE2-173 O1	5.1748	Adder	6.09
942111	AE2-223 C	2.0182	Adder	2.37
942421	AE2-255 C O1	3.0160	Adder	3.55
942651	AE2-281 C O1	0.8358	Adder	0.98
942991	AE2-321 C	8.1632	Adder	9.6
943121	AE2-341 C	12.7367	Adder	14.98
943381	AF1-009 C	0.5974	Adder	0.7
943401	AF1-011 C	1.2399	Adder	1.46
943411	AF1-012 C	11.9631	Adder	14.07
943591	AF1-030 C O1	8.4700	Adder	9.96
943801	AF1-048 C	3.8160	Adder	4.49
943921	AF1-060	1.2085	Adder	1.42
944041	AF1-072	2.1512	Adder	2.53
944911	AF1-156 C	12.1092	Adder	14.25
945351	AF1-200 FTIR	308.5264	Merchant Transmission	308.5264
946151	AF1-280 C O1	15.5391	Adder	18.28
946161	AF1-281 C	0.3403	Adder	0.4
946321	AF1-296 C O1	3.9241	Adder	4.62
946501	AF1-314 C	4.3608	Adder	5.13
946531	AF1-317 C O1	2.2787	Adder	2.68
946541	AF1-318 C O1	5.7512	Adder	6.77
946661	AF1-330 C	2.0011	Adder	2.35
946671	AF1-331	2.4077	Adder	2.83
951721	J643	27.1460	PJM External (MISO)	27.1460
953871	J847	13.8150	PJM External (MISO)	13.8150
954751	J351	446.6739	PJM External (MISO)	446.6739
955741	J1058	38.3400	PJM External (MISO)	38.3400
957021	AF2-003 C O1	3.4823	Adder	7.73
957331	AF2-027 C	1.3230	Adder	2.94
957371	AF2-031 C O1	1.5768	80/20	1.5768
957471	AF2-041 C	11.2861	Adder	25.05
957751	AF2-069 C	0.1257	Adder	0.28
957761	AF2-070 C	0.1771	Adder	0.39
958011	AF2-095 C O1	10.0173	Adder	22.24
958021	AF2-096 C O1	17.7815	Adder	39.47
958341	AF2-128 C O1	0.8096	Adder	1.8
958481	AF2-142 C	5.9447	Adder	13.2
958491	AF2-143 C	5.6954	Adder	12.64
958911	AF2-182	10.8206	Adder	24.02
958921	AF2-183 C	1.9237	Adder	4.27
959081	AF2-199 C	3.7620	Adder	8.35

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
959091	AF2-200 C	7.5241	Adder	16.7
959101	AF2-201 C O1	3.1839	Adder	7.07
959341	AF2-225 C	3.4557	Adder	7.67
959351	AF2-226 C	1.3489	Adder	2.99
959611	AF2-252 C	0.9462	Adder	2.1
959761	AF2-267 C O1	2.2994	Adder	5.1
960281	AF2-319 C	1.3489	Adder	2.99
960381	AF2-329	3.5027	Adder	7.78
960551	AF2-346 C	2.7173	Adder	6.03
960581	AF2-349 C	11.5496	Adder	25.64
960591	AF2-350 C O1	4.4191	Adder	9.81
960601	AF2-351 C O1	0.5892	Adder	1.31
960611	AF2-352 C	0.9462	Adder	2.1
960721	AF2-363 C O1	3.1543	Adder	7.0
960731	AF2-364 C O1	3.2513	Adder	7.22
960751	AF2-366 C O1	3.6866	Adder	8.18
961011	AF2-392 C O1	2.0976	Adder	4.66
961021	AF2-393 O1	3.5755	Adder	7.94
961031	AF2-394 O1	2.3837	Adder	5.29
961501	AF2-441 C O1	15.1056	80/20	15.1056
WEC	WEC	4.4132	Confirmed LTF	4.4132
CBM-W2	CBM-W2	24.9631	Confirmed LTF	24.9631
NY	NY	1.3416	Confirmed LTF	1.3416
CBM-W1	CBM-W1	79.8013	Confirmed LTF	79.8013
TVA	TVA	1.7262	Confirmed LTF	1.7262
CHEOAH	CHEOAH	0.0065	Confirmed LTF	0.0065
CBM-S1	CBM-S1	7.0972	Confirmed LTF	7.0972
MADISON	MADISON	22.9824	Confirmed LTF	22.9824
MEC	MEC	15.3656	Confirmed LTF	15.3656
BLUEG	BLUEG	1.7030	Confirmed LTF	1.7030
TRIMBLE	TRIMBLE	0.5994	Confirmed LTF	0.5994
CATAWBA	CATAWBA	0.3045	Confirmed LTF	0.3045

11.6.2 Index 2

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795144	270926	WILTON ; B	CE	275232	WILTON ;3M	CE	1	COMED_P4_112-65-BT5-6__	breaker	1379.0	122.21	122.27	DC	30.47

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.7664	50/50	3.7664
274772	LINCOLN ;3U	3.7664	50/50	3.7664
274773	LINCOLN ;4U	3.7664	50/50	3.7664
274774	LINCOLN ;5U	3.7664	50/50	3.7664
274775	LINCOLN ;6U	3.7664	50/50	3.7664
274776	LINCOLN ;7U	3.7664	50/50	3.7664
274777	LINCOLN ;8U	3.7664	50/50	3.7664

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274830	U3-021 1	6.3035	Adder	7.42
274831	U3-021 2	6.3035	Adder	7.42
274881	PILOT HIL;1E	19.9396	Adder	23.46
274890	CAYUG;1U E	17.0054	Adder	20.01
274891	CAYUG;2U E	17.0054	Adder	20.01
275149	KELLYCK ;1E	19.9396	Adder	23.46
276167	Z1-106 E2	1.3063	Adder	1.54
276168	Z1-106 E1	1.3062	Adder	1.54
276169	Z1-107 E	2.6738	Adder	3.15
276170	Z1-108 E	2.5704	Adder	3.02
290021	O50 E	20.0260	Adder	23.56
290051	GSG-6; E	10.8913	Adder	12.81
290108	LEEDK;1U E	25.1940	Adder	29.64
293061	N-015 E	16.4434	Adder	19.35
293644	O22 E1	10.5913	Adder	12.46
293645	O22 E2	20.5595	Adder	24.19
294392	P-010 E	20.8831	Adder	24.57
910542	X3-005 E	0.7562	Adder	0.89
915011	Y3-013 1	3.8635	Adder	4.55
915021	Y3-013 2	3.8635	Adder	4.55
915031	Y3-013 3	3.8635	Adder	4.55
918052	AA1-018 E OP	16.9837	Adder	19.98
920272	AA2-123 E	2.5262	Adder	2.97
924471	AB2-096	43.7741	Adder	51.5
926311	AC1-109 1	1.9765	Adder	2.33
926321	AC1-109 2	1.9765	Adder	2.33
926331	AC1-110 1	1.9634	Adder	2.31
926341	AC1-110 2	1.9634	Adder	2.31
926351	AC1-111 1	0.7894	Adder	0.93
926361	AC1-111 2	0.7894	Adder	0.93
926371	AC1-111 3	0.7894	Adder	0.93
926381	AC1-111 4	0.7894	Adder	0.93
926391	AC1-111 5	0.7894	Adder	0.93
926401	AC1-111 6	0.7894	Adder	0.93
927451	AC1-142A 1	4.3256	Adder	5.09
927461	AC1-142A 2	4.3256	Adder	5.09
930501	AB1-091 O1	79.3394	Adder	93.34
930741	AB1-122 1O1	75.3017	Adder	88.59
930751	AB1-122 2O1	76.2303	Adder	89.68
933411	AC2-154 C	2.7061	Adder	3.18
933412	AC2-154 E	4.4152	Adder	5.19
933431	AC2-156 C O1	0.9893	Adder	1.16
933432	AC2-156 E O1	1.6142	Adder	1.9
933911	AD1-013 C	1.9232	Adder	2.26
933912	AD1-013 E	3.0721	Adder	3.61
933931	AD1-016 C	0.9600	Adder	1.13
933932	AD1-016 E	1.5662	Adder	1.84
934101	AD1-039 1	7.3796	Adder	8.68
934111	AD1-039 2	7.4706	Adder	8.79
934431	AD1-067 C	0.1368	Adder	0.16
934432	AD1-067 E	0.5750	Adder	0.68
934701	AD1-098 C O1	7.1661	Adder	8.43

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
934702	AD1-098 E O1	5.2320	Adder	6.16
934721	AD1-100 C	24.8523	Adder	29.24
934722	AD1-100 E	115.9774	Adder	136.44
934871	AD1-116 C	0.9891	Adder	1.16
934872	AD1-116 E	1.6138	Adder	1.9
934971	AD1-129 C	0.9344	Adder	1.1
934972	AD1-129 E	0.6230	Adder	0.73
935001	AD1-133 C O1	23.0234	Adder	27.09
935002	AD1-133 E O1	15.3490	Adder	18.06
936291	AD2-038 C O1	2.4301	Adder	2.86
936292	AD2-038 E O1	16.2627	Adder	19.13
936371	AD2-047 C O1	4.8425	Adder	5.7
936372	AD2-047 E O1	23.6427	Adder	27.81
936461	AD2-060	2.8485	Adder	3.35
936511	AD2-066 C O1	8.7640	Adder	10.31
936512	AD2-066 E O1	5.8426	Adder	6.87
937001	AD2-134 C	2.8471	Adder	3.35
937002	AD2-134 E	11.7616	Adder	13.84
937401	AD2-194 1	8.0697	Adder	9.49
937411	AD2-194 2	8.0692	Adder	9.49
938511	AE1-070 1	9.4819	Adder	11.16
938521	AE1-070 2	8.6744	Adder	10.21
938851	AE1-113 C	8.2607	Adder	9.72
938852	AE1-113 E	29.2880	Adder	34.46
939321	AE1-163 C O1	6.1063	Adder	7.18
939322	AE1-163 E O1	37.5102	Adder	44.13
939351	AE1-166 C O1	12.2622	Adder	14.43
939352	AE1-166 E O1	11.3189	Adder	13.32
939401	AE1-172 C O1	6.7946	Adder	7.99
939402	AE1-172 E O1	31.8801	Adder	37.51
940101	AE1-252 C O1	13.6499	Adder	16.06
940102	AE1-252 E O1	9.0999	Adder	10.71
940752	AE2-062 E	0.1351	Adder	0.16
941131	AE2-107 C	7.5761	Adder	8.91
941132	AE2-107 E	5.0507	Adder	5.94
941551	AE2-152 C O1	14.1487	Adder	16.65
941552	AE2-152 E O1	9.4325	Adder	11.1
941561	AE2-153 C O1	5.1247	Adder	6.03
941562	AE2-153 E O1	23.9929	Adder	28.23
941731	AE2-173 O1	3.2665	Adder	3.84
942111	AE2-223 C	2.4140	Adder	2.84
942112	AE2-223 E	16.1551	Adder	19.01
942421	AE2-255 C O1	3.1291	Adder	3.68
942422	AE2-255 E O1	9.3872	Adder	11.04
942651	AE2-281 C O1	0.8723	Adder	1.03
942652	AE2-281 E O1	5.3586	Adder	6.3
942991	AE2-321 C	8.4508	Adder	9.94
942992	AE2-321 E	4.1623	Adder	4.9
943121	AE2-341 C	13.2079	Adder	15.54
943122	AE2-341 E	6.4858	Adder	7.63
943381	AF1-009 C	0.6199	Adder	0.73
943382	AF1-009 E	2.4796	Adder	2.92

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
943591	AF1-030 C O1	8.7834	Adder	10.33
943592	AF1-030 E O1	4.3457	Adder	5.11
943801	AF1-048 C	3.9504	Adder	4.65
943802	AF1-048 E	2.6336	Adder	3.1
944041	AF1-072	2.2259	Adder	2.62
944911	AF1-156 C	13.1029	Adder	15.42
944912	AF1-156 E	8.7353	Adder	10.28
945351	AF1-200 FTIR	322.6289	Merchant Transmission	322.6289
946661	AF1-330 C	2.0715	Adder	2.44
946662	AF1-330 E	0.4547	Adder	0.53
946671	AF1-331	2.4976	Adder	2.94
957021	AF2-003 C O1	3.5751	Adder	7.94
957022	AF2-003 E O1	16.7377	Adder	37.15
957331	AF2-027 C	1.3651	Adder	3.03
957332	AF2-027 E	2.0477	Adder	4.55
958011	AF2-095 C O1	10.2661	Adder	22.79
958012	AF2-095 E O1	4.8311	Adder	10.72
958021	AF2-096 C O1	19.7578	Adder	43.86
958022	AF2-096 E O1	9.3434	Adder	20.74
958481	AF2-142 C	6.2078	Adder	13.78
958482	AF2-142 E	4.1386	Adder	9.19
958491	AF2-143 C	5.9443	Adder	13.19
958492	AF2-143 E	3.9629	Adder	8.8
959341	AF2-225 C	4.1335	Adder	9.18
959342	AF2-225 E	5.7081	Adder	12.67
959351	AF2-226 C	1.3758	Adder	3.05
959352	AF2-226 E	2.0637	Adder	4.58
960281	AF2-319 C	1.3758	Adder	3.05
960282	AF2-319 E	2.0637	Adder	4.58
960381	AF2-329	3.6323	Adder	8.06
960581	AF2-349 C	11.9583	Adder	26.54
960582	AF2-349 E	7.9722	Adder	17.7
960591	AF2-350 C O1	4.5291	Adder	10.05
960592	AF2-350 E O1	3.0194	Adder	6.7
960601	AF2-351 C O1	0.6039	Adder	1.34
960602	AF2-351 E O1	0.9058	Adder	2.01
960721	AF2-363 C O1	3.2702	Adder	7.26
960722	AF2-363 E O1	2.1801	Adder	4.84
960731	AF2-364 C O1	3.3662	Adder	7.47
960732	AF2-364 E O1	2.2441	Adder	4.98
960751	AF2-366 C O1	3.8221	Adder	8.48
960752	AF2-366 E O1	2.5480	Adder	5.66
961501	AF2-441 C O1	5.4914	Adder	12.19
961502	AF2-441 E O1	8.2371	Adder	18.28
WEC	WEC	4.5603	Confirmed LTF	4.5603
CALDERWOOD	CALDERWOOD	0.0631	Confirmed LTF	0.0631
CBM-W2	CBM-W2	25.0942	Confirmed LTF	25.0942
NY	NY	1.4306	Confirmed LTF	1.4306
CBM-W1	CBM-W1	78.1875	Confirmed LTF	78.1875
TVA	TVA	1.6184	Confirmed LTF	1.6184
O-066	O-066	16.9546	Confirmed LTF	16.9546
CHEOAH	CHEOAH	0.0771	Confirmed LTF	0.0771

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
CBM-S1	CBM-S1	6.0407	Confirmed LTF	6.0407
G-007	G-007	2.6218	Confirmed LTF	2.6218
MADISON	MADISON	24.3210	Confirmed LTF	24.3210
MEC	MEC	16.0171	Confirmed LTF	16.0171
BLUEG	BLUEG	2.3071	Confirmed LTF	2.3071
TRIMBLE	TRIMBLE	0.7969	Confirmed LTF	0.7969
CATAWBA	CATAWBA	0.3619	Confirmed LTF	0.3619

11.6.3 Index 3

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795132	270927	WILTON ; R	CE	275233	WILTON ;4M	CE	1	COMED_P4_112-65-BT2-3__	breaker	1379.0	124.77	124.83	DC	31.12

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.8683	50/50	3.8683
274772	LINCOLN ;3U	3.8683	50/50	3.8683
274773	LINCOLN ;4U	3.8683	50/50	3.8683
274774	LINCOLN ;5U	3.8683	50/50	3.8683
274775	LINCOLN ;6U	3.8683	50/50	3.8683
274776	LINCOLN ;7U	3.8683	50/50	3.8683
274777	LINCOLN ;8U	3.8683	50/50	3.8683
274830	U3-021 1	6.4380	Adder	7.57
274831	U3-021 2	6.4380	Adder	7.57
274881	PILOT HIL;1E	20.3561	Adder	23.95
274890	CAYUG;1U E	17.3451	Adder	20.41
274891	CAYUG;2U E	17.3451	Adder	20.41
275149	KELLYCK ;1E	20.3561	Adder	23.95
276167	Z1-106 E2	1.3342	Adder	1.57
276168	Z1-106 E1	1.3341	Adder	1.57
276169	Z1-107 E	2.7309	Adder	3.21
276170	Z1-108 E	2.6251	Adder	3.09
290021	O50 E	20.4530	Adder	24.06
290051	GSG-6; E	11.1236	Adder	13.09
290108	LEEDK;1U E	25.7295	Adder	30.27
293061	N-015 E	16.7861	Adder	19.75
293644	O22 E1	10.8153	Adder	12.72
293645	O22 E2	20.9944	Adder	24.7
294392	P-010 E	21.3184	Adder	25.08
910542	X3-005 E	0.7727	Adder	0.91
915011	Y3-013 1	3.9461	Adder	4.64
915021	Y3-013 2	3.9461	Adder	4.64
915031	Y3-013 3	3.9461	Adder	4.64
918052	AA1-018 E OP	17.3542	Adder	20.42
920272	AA2-123 E	2.5799	Adder	3.04
924471	AB2-096	44.7083	Adder	52.6
926311	AC1-109 1	2.0186	Adder	2.37

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
926321	AC1-109 2	2.0186	Adder	2.37
926331	AC1-110 1	2.0052	Adder	2.36
926341	AC1-110 2	2.0052	Adder	2.36
926351	AC1-111 1	0.8063	Adder	0.95
926361	AC1-111 2	0.8063	Adder	0.95
926371	AC1-111 3	0.8063	Adder	0.95
926381	AC1-111 4	0.8063	Adder	0.95
926391	AC1-111 5	0.8063	Adder	0.95
926401	AC1-111 6	0.8063	Adder	0.95
927451	AC1-142A 1	4.4186	Adder	5.2
927461	AC1-142A 2	4.4186	Adder	5.2
930501	AB1-091 O1	80.9897	Adder	95.28
930741	AB1-122 1O1	76.8999	Adder	90.47
930751	AB1-122 2O1	77.8579	Adder	91.6
933411	AC2-154 C	2.7626	Adder	3.25
933412	AC2-154 E	4.5074	Adder	5.3
933431	AC2-156 C O1	1.0103	Adder	1.19
933432	AC2-156 E O1	1.6485	Adder	1.94
933911	AD1-013 C	1.9642	Adder	2.31
933912	AD1-013 E	3.1375	Adder	3.69
933931	AD1-016 C	0.9804	Adder	1.15
933932	AD1-016 E	1.5996	Adder	1.88
934101	AD1-039 1	7.5362	Adder	8.87
934111	AD1-039 2	7.6301	Adder	8.98
934431	AD1-067 C	0.1397	Adder	0.16
934432	AD1-067 E	0.5873	Adder	0.69
934701	AD1-098 C O1	7.3184	Adder	8.61
934702	AD1-098 E O1	5.3432	Adder	6.29
934721	AD1-100 C	25.3457	Adder	29.82
934722	AD1-100 E	118.2800	Adder	139.15
934871	AD1-116 C	1.0107	Adder	1.19
934872	AD1-116 E	1.6490	Adder	1.94
934971	AD1-129 C	0.9544	Adder	1.12
934972	AD1-129 E	0.6363	Adder	0.75
935001	AD1-133 C O1	23.5023	Adder	27.65
935002	AD1-133 E O1	15.6682	Adder	18.43
936291	AD2-038 C O1	2.4826	Adder	2.92
936292	AD2-038 E O1	16.6143	Adder	19.55
936371	AD2-047 C O1	4.9436	Adder	5.82
936372	AD2-047 E O1	24.1366	Adder	28.4
936461	AD2-060	2.9080	Adder	3.42
936511	AD2-066 C O1	8.9497	Adder	10.53
936512	AD2-066 E O1	5.9665	Adder	7.02
937001	AD2-134 C	2.9079	Adder	3.42
937002	AD2-134 E	12.0124	Adder	14.13
937401	AD2-194 1	8.2426	Adder	9.7
937411	AD2-194 2	8.2421	Adder	9.7
938511	AE1-070 1	9.6851	Adder	11.39
938521	AE1-070 2	8.8603	Adder	10.42
938851	AE1-113 C	8.4369	Adder	9.93
938852	AE1-113 E	29.9126	Adder	35.19
939321	AE1-163 C O1	6.2383	Adder	7.34

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
939322	AE1-163 E O1	38.3212	Adder	45.08
939351	AE1-166 C O1	12.5095	Adder	14.72
939352	AE1-166 E O1	11.5472	Adder	13.58
939401	AE1-172 C O1	6.9294	Adder	8.15
939402	AE1-172 E O1	32.5126	Adder	38.25
940101	AE1-252 C O1	13.9207	Adder	16.38
940102	AE1-252 E O1	9.2805	Adder	10.92
940752	AE2-062 E	0.1379	Adder	0.16
941131	AE2-107 C	7.7372	Adder	9.1
941132	AE2-107 E	5.1581	Adder	6.07
941551	AE2-152 C O1	14.4340	Adder	16.98
941552	AE2-152 E O1	9.6227	Adder	11.32
941561	AE2-153 C O1	5.2303	Adder	6.15
941562	AE2-153 E O1	24.4874	Adder	28.81
941731	AE2-173 O1	3.3326	Adder	3.92
942111	AE2-223 C	2.4629	Adder	2.9
942112	AE2-223 E	16.4823	Adder	19.39
942421	AE2-255 C O1	3.1958	Adder	3.76
942422	AE2-255 E O1	9.5874	Adder	11.28
942651	AE2-281 C O1	0.8912	Adder	1.05
942652	AE2-281 E O1	5.4745	Adder	6.44
942991	AE2-321 C	8.6313	Adder	10.15
942992	AE2-321 E	4.2513	Adder	5.0
943121	AE2-341 C	13.4892	Adder	15.87
943122	AE2-341 E	6.6239	Adder	7.79
943381	AF1-009 C	0.6331	Adder	0.74
943382	AF1-009 E	2.5323	Adder	2.98
943591	AF1-030 C O1	8.9705	Adder	10.55
943592	AF1-030 E O1	4.4383	Adder	5.22
943801	AF1-048 C	4.0348	Adder	4.75
943802	AF1-048 E	2.6899	Adder	3.16
944041	AF1-072	2.2734	Adder	2.67
944911	AF1-156 C	13.3730	Adder	15.73
944912	AF1-156 E	8.9153	Adder	10.49
945351	AF1-200 FTIR	329.4462	Merchant Transmission	329.4462
946661	AF1-330 C	2.1155	Adder	2.49
946662	AF1-330 E	0.4644	Adder	0.55
946671	AF1-331	2.5508	Adder	3.0
957021	AF2-003 C O1	3.6510	Adder	8.1
957022	AF2-003 E O1	17.0932	Adder	37.94
957331	AF2-027 C	1.3943	Adder	3.1
957332	AF2-027 E	2.0914	Adder	4.64
958011	AF2-095 C O1	10.4805	Adder	23.26
958012	AF2-095 E O1	4.9320	Adder	10.95
958021	AF2-096 C O1	20.1649	Adder	44.76
958022	AF2-096 E O1	9.5360	Adder	21.17
958481	AF2-142 C	6.3433	Adder	14.08
958482	AF2-142 E	4.2288	Adder	9.39
958491	AF2-143 C	6.0728	Adder	13.48
958492	AF2-143 E	4.0486	Adder	8.99
959341	AF2-225 C	4.2172	Adder	9.36
959342	AF2-225 E	5.8238	Adder	12.93

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
959351	AF2-226 C	1.4049	Adder	3.12
959352	AF2-226 E	2.1074	Adder	4.68
960281	AF2-319 C	1.4049	Adder	3.12
960282	AF2-319 E	2.1074	Adder	4.68
960381	AF2-329	3.7097	Adder	8.23
960581	AF2-349 C	12.2138	Adder	27.11
960582	AF2-349 E	8.1425	Adder	18.07
960591	AF2-350 C O1	4.6238	Adder	10.26
960592	AF2-350 E O1	3.0825	Adder	6.84
960601	AF2-351 C O1	0.6165	Adder	1.37
960602	AF2-351 E O1	0.9248	Adder	2.05
960721	AF2-363 C O1	3.3397	Adder	7.41
960722	AF2-363 E O1	2.2265	Adder	4.94
960731	AF2-364 C O1	3.4379	Adder	7.63
960732	AF2-364 E O1	2.2919	Adder	5.09
960751	AF2-366 C O1	3.9034	Adder	8.66
960752	AF2-366 E O1	2.6023	Adder	5.78
961501	AF2-441 C O1	5.6075	Adder	12.45
961502	AF2-441 E O1	8.4112	Adder	18.67
WEC	WEC	4.6573	Confirmed LTF	4.6573
CALDERWOOD	CALDERWOOD	0.0656	Confirmed LTF	0.0656
CBM-W2	CBM-W2	25.6101	Confirmed LTF	25.6101
NY	NY	1.4616	Confirmed LTF	1.4616
CBM-W1	CBM-W1	79.8388	Confirmed LTF	79.8388
TVA	TVA	1.6492	Confirmed LTF	1.6492
O-066	O-066	17.3242	Confirmed LTF	17.3242
CHEOAH	CHEOAH	0.0801	Confirmed LTF	0.0801
CBM-S1	CBM-S1	6.1514	Confirmed LTF	6.1514
G-007	G-007	2.6780	Confirmed LTF	2.6780
MADISON	MADISON	24.8371	Confirmed LTF	24.8371
MEC	MEC	16.3540	Confirmed LTF	16.3540
BLUEG	BLUEG	2.3592	Confirmed LTF	2.3592
TRIMBLE	TRIMBLE	0.8147	Confirmed LTF	0.8147
CATAWBA	CATAWBA	0.3703	Confirmed LTF	0.3703

11.6.4 Index 4

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795143	275232	WILTON ;3M	CE	270644	WILTON ;	CE	1	COMED_P4_112-65-BT5-6_	breaker	1379.0	122.21	122.27	DC	30.47

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.7664	50/50	3.7664
274772	LINCOLN ;3U	3.7664	50/50	3.7664
274773	LINCOLN ;4U	3.7664	50/50	3.7664
274774	LINCOLN ;5U	3.7664	50/50	3.7664
274775	LINCOLN ;6U	3.7664	50/50	3.7664
274776	LINCOLN ;7U	3.7664	50/50	3.7664
274777	LINCOLN ;8U	3.7664	50/50	3.7664
274830	U3-021 1	6.3035	Adder	7.42
274831	U3-021 2	6.3035	Adder	7.42
274881	PILOT HIL;1E	19.9396	Adder	23.46
274890	CAYUG;1U E	17.0054	Adder	20.01
274891	CAYUG;2U E	17.0054	Adder	20.01
275149	KELLYCK ;1E	19.9396	Adder	23.46
276167	Z1-106 E2	1.3063	Adder	1.54
276168	Z1-106 E1	1.3062	Adder	1.54
276169	Z1-107 E	2.6738	Adder	3.15
276170	Z1-108 E	2.5704	Adder	3.02
290021	O50 E	20.0260	Adder	23.56
290051	GSG-6; E	10.8913	Adder	12.81
290108	LEEDK;1U E	25.1940	Adder	29.64
293061	N-015 E	16.4434	Adder	19.35
293644	O22 E1	10.5913	Adder	12.46
293645	O22 E2	20.5595	Adder	24.19
294392	P-010 E	20.8831	Adder	24.57
910542	X3-005 E	0.7562	Adder	0.89
915011	Y3-013 1	3.8635	Adder	4.55
915021	Y3-013 2	3.8635	Adder	4.55
915031	Y3-013 3	3.8635	Adder	4.55
918052	AA1-018 E OP	16.9837	Adder	19.98
920272	AA2-123 E	2.5262	Adder	2.97
924471	AB2-096	43.7741	Adder	51.5
926311	AC1-109 1	1.9765	Adder	2.33
926321	AC1-109 2	1.9765	Adder	2.33
926331	AC1-110 1	1.9634	Adder	2.31
926341	AC1-110 2	1.9634	Adder	2.31
926351	AC1-111 1	0.7894	Adder	0.93
926361	AC1-111 2	0.7894	Adder	0.93
926371	AC1-111 3	0.7894	Adder	0.93
926381	AC1-111 4	0.7894	Adder	0.93
926391	AC1-111 5	0.7894	Adder	0.93
926401	AC1-111 6	0.7894	Adder	0.93
927451	AC1-142A 1	4.3256	Adder	5.09

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
927461	AC1-142A 2	4.3256	Adder	5.09
930501	AB1-091 O1	79.3394	Adder	93.34
930741	AB1-122 1O1	75.3017	Adder	88.59
930751	AB1-122 2O1	76.2303	Adder	89.68
933411	AC2-154 C	2.7061	Adder	3.18
933412	AC2-154 E	4.4152	Adder	5.19
933431	AC2-156 C O1	0.9893	Adder	1.16
933432	AC2-156 E O1	1.6142	Adder	1.9
933911	AD1-013 C	1.9232	Adder	2.26
933912	AD1-013 E	3.0721	Adder	3.61
933931	AD1-016 C	0.9600	Adder	1.13
933932	AD1-016 E	1.5662	Adder	1.84
934101	AD1-039 1	7.3796	Adder	8.68
934111	AD1-039 2	7.4706	Adder	8.79
934431	AD1-067 C	0.1368	Adder	0.16
934432	AD1-067 E	0.5750	Adder	0.68
934701	AD1-098 C O1	7.1661	Adder	8.43
934702	AD1-098 E O1	5.2320	Adder	6.16
934721	AD1-100 C	24.8523	Adder	29.24
934722	AD1-100 E	115.9774	Adder	136.44
934871	AD1-116 C	0.9891	Adder	1.16
934872	AD1-116 E	1.6138	Adder	1.9
934971	AD1-129 C	0.9344	Adder	1.1
934972	AD1-129 E	0.6230	Adder	0.73
935001	AD1-133 C O1	23.0234	Adder	27.09
935002	AD1-133 E O1	15.3490	Adder	18.06
936291	AD2-038 C O1	2.4301	Adder	2.86
936292	AD2-038 E O1	16.2627	Adder	19.13
936371	AD2-047 C O1	4.8425	Adder	5.7
936372	AD2-047 E O1	23.6427	Adder	27.81
936461	AD2-060	2.8485	Adder	3.35
936511	AD2-066 C O1	8.7640	Adder	10.31
936512	AD2-066 E O1	5.8426	Adder	6.87
937001	AD2-134 C	2.8471	Adder	3.35
937002	AD2-134 E	11.7616	Adder	13.84
937401	AD2-194 1	8.0697	Adder	9.49
937411	AD2-194 2	8.0692	Adder	9.49
938511	AE1-070 1	9.4819	Adder	11.16
938521	AE1-070 2	8.6744	Adder	10.21
938851	AE1-113 C	8.2607	Adder	9.72
938852	AE1-113 E	29.2880	Adder	34.46
939321	AE1-163 C O1	6.1063	Adder	7.18
939322	AE1-163 E O1	37.5102	Adder	44.13
939351	AE1-166 C O1	12.2622	Adder	14.43
939352	AE1-166 E O1	11.3189	Adder	13.32
939401	AE1-172 C O1	6.7946	Adder	7.99
939402	AE1-172 E O1	31.8801	Adder	37.51
940101	AE1-252 C O1	13.6499	Adder	16.06
940102	AE1-252 E O1	9.0999	Adder	10.71
940752	AE2-062 E	0.1351	Adder	0.16
941131	AE2-107 C	7.5761	Adder	8.91
941132	AE2-107 E	5.0507	Adder	5.94

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
941551	AE2-152 C O1	14.1487	Adder	16.65
941552	AE2-152 E O1	9.4325	Adder	11.1
941561	AE2-153 C O1	5.1247	Adder	6.03
941562	AE2-153 E O1	23.9929	Adder	28.23
941731	AE2-173 O1	3.2665	Adder	3.84
942111	AE2-223 C	2.4140	Adder	2.84
942112	AE2-223 E	16.1551	Adder	19.01
942421	AE2-255 C O1	3.1291	Adder	3.68
942422	AE2-255 E O1	9.3872	Adder	11.04
942651	AE2-281 C O1	0.8723	Adder	1.03
942652	AE2-281 E O1	5.3586	Adder	6.3
942991	AE2-321 C	8.4508	Adder	9.94
942992	AE2-321 E	4.1623	Adder	4.9
943121	AE2-341 C	13.2079	Adder	15.54
943122	AE2-341 E	6.4858	Adder	7.63
943381	AF1-009 C	0.6199	Adder	0.73
943382	AF1-009 E	2.4796	Adder	2.92
943591	AF1-030 C O1	8.7834	Adder	10.33
943592	AF1-030 E O1	4.3457	Adder	5.11
943801	AF1-048 C	3.9504	Adder	4.65
943802	AF1-048 E	2.6336	Adder	3.1
944041	AF1-072	2.2259	Adder	2.62
944911	AF1-156 C	13.1029	Adder	15.42
944912	AF1-156 E	8.7353	Adder	10.28
945351	AF1-200 FTIR	322.6289	Merchant Transmission	322.6289
946661	AF1-330 C	2.0715	Adder	2.44
946662	AF1-330 E	0.4547	Adder	0.53
946671	AF1-331	2.4976	Adder	2.94
957021	AF2-003 C O1	3.5751	Adder	7.94
957022	AF2-003 E O1	16.7377	Adder	37.15
957331	AF2-027 C	1.3651	Adder	3.03
957332	AF2-027 E	2.0477	Adder	4.55
958011	AF2-095 C O1	10.2661	Adder	22.79
958012	AF2-095 E O1	4.8311	Adder	10.72
958021	AF2-096 C O1	19.7578	Adder	43.86
958022	AF2-096 E O1	9.3434	Adder	20.74
958481	AF2-142 C	6.2078	Adder	13.78
958482	AF2-142 E	4.1386	Adder	9.19
958491	AF2-143 C	5.9443	Adder	13.19
958492	AF2-143 E	3.9629	Adder	8.8
959341	AF2-225 C	4.1335	Adder	9.18
959342	AF2-225 E	5.7081	Adder	12.67
959351	AF2-226 C	1.3758	Adder	3.05
959352	AF2-226 E	2.0637	Adder	4.58
960281	AF2-319 C	1.3758	Adder	3.05
960282	AF2-319 E	2.0637	Adder	4.58
960381	AF2-329	3.6323	Adder	8.06
960581	AF2-349 C	11.9583	Adder	26.54
960582	AF2-349 E	7.9722	Adder	17.7
960591	AF2-350 C O1	4.5291	Adder	10.05
960592	AF2-350 E O1	3.0194	Adder	6.7
960601	AF2-351 C O1	0.6039	Adder	1.34

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
960602	AF2-351 E O1	0.9058	Adder	2.01
960721	AF2-363 C O1	3.2702	Adder	7.26
960722	AF2-363 E O1	2.1801	Adder	4.84
960731	AF2-364 C O1	3.3662	Adder	7.47
960732	AF2-364 E O1	2.2441	Adder	4.98
960751	AF2-366 C O1	3.8221	Adder	8.48
960752	AF2-366 E O1	2.5480	Adder	5.66
961501	AF2-441 C O1	5.4914	Adder	12.19
961502	AF2-441 E O1	8.2371	Adder	18.28
WEC	WEC	4.5603	Confirmed LTF	4.5603
CALDERWOOD	CALDERWOOD	0.0631	Confirmed LTF	0.0631
CBM-W2	CBM-W2	25.0942	Confirmed LTF	25.0942
NY	NY	1.4306	Confirmed LTF	1.4306
CBM-W1	CBM-W1	78.1875	Confirmed LTF	78.1875
TVA	TVA	1.6184	Confirmed LTF	1.6184
O-066	O-066	16.9546	Confirmed LTF	16.9546
CHEOAH	CHEOAH	0.0771	Confirmed LTF	0.0771
CBM-S1	CBM-S1	6.0407	Confirmed LTF	6.0407
G-007	G-007	2.6218	Confirmed LTF	2.6218
MADISON	MADISON	24.3210	Confirmed LTF	24.3210
MEC	MEC	16.0171	Confirmed LTF	16.0171
BLUEG	BLUEG	2.3071	Confirmed LTF	2.3071
TRIMBLE	TRIMBLE	0.7969	Confirmed LTF	0.7969
CATAWBA	CATAWBA	0.3619	Confirmed LTF	0.3619

11.6.5 Index 5

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795131	275233	WILTON ;4M	CE	270644	WILTON ;	CE	1	COMED_P4_112-65-BT2-3__	breaker	1379.0	124.77	124.83	DC	31.12

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.8683	50/50	3.8683
274772	LINCOLN ;3U	3.8683	50/50	3.8683
274773	LINCOLN ;4U	3.8683	50/50	3.8683
274774	LINCOLN ;5U	3.8683	50/50	3.8683
274775	LINCOLN ;6U	3.8683	50/50	3.8683
274776	LINCOLN ;7U	3.8683	50/50	3.8683
274777	LINCOLN ;8U	3.8683	50/50	3.8683
274830	U3-021 1	6.4380	Adder	7.57
274831	U3-021 2	6.4380	Adder	7.57
274881	PILOT HIL;1E	20.3561	Adder	23.95
274890	CAYUG;1U E	17.3451	Adder	20.41
274891	CAYUG;2U E	17.3451	Adder	20.41
275149	KELLYCK ;1E	20.3561	Adder	23.95
276167	Z1-106 E2	1.3342	Adder	1.57
276168	Z1-106 E1	1.3341	Adder	1.57

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
276169	Z1-107 E	2.7309	Adder	3.21
276170	Z1-108 E	2.6251	Adder	3.09
290021	O50 E	20.4530	Adder	24.06
290051	GSG-6; E	11.1236	Adder	13.09
290108	LEEDK;1U E	25.7295	Adder	30.27
293061	N-015 E	16.7861	Adder	19.75
293644	O22 E1	10.8153	Adder	12.72
293645	O22 E2	20.9944	Adder	24.7
294392	P-010 E	21.3184	Adder	25.08
910542	X3-005 E	0.7727	Adder	0.91
915011	Y3-013 1	3.9461	Adder	4.64
915021	Y3-013 2	3.9461	Adder	4.64
915031	Y3-013 3	3.9461	Adder	4.64
918052	AA1-018 E OP	17.3542	Adder	20.42
920272	AA2-123 E	2.5799	Adder	3.04
924471	AB2-096	44.7083	Adder	52.6
926311	AC1-109 1	2.0186	Adder	2.37
926321	AC1-109 2	2.0186	Adder	2.37
926331	AC1-110 1	2.0052	Adder	2.36
926341	AC1-110 2	2.0052	Adder	2.36
926351	AC1-111 1	0.8063	Adder	0.95
926361	AC1-111 2	0.8063	Adder	0.95
926371	AC1-111 3	0.8063	Adder	0.95
926381	AC1-111 4	0.8063	Adder	0.95
926391	AC1-111 5	0.8063	Adder	0.95
926401	AC1-111 6	0.8063	Adder	0.95
927451	AC1-142A 1	4.4186	Adder	5.2
927461	AC1-142A 2	4.4186	Adder	5.2
930501	AB1-091 O1	80.9897	Adder	95.28
930741	AB1-122 1O1	76.8999	Adder	90.47
930751	AB1-122 2O1	77.8579	Adder	91.6
933411	AC2-154 C	2.7626	Adder	3.25
933412	AC2-154 E	4.5074	Adder	5.3
933431	AC2-156 C O1	1.0103	Adder	1.19
933432	AC2-156 E O1	1.6485	Adder	1.94
933911	AD1-013 C	1.9642	Adder	2.31
933912	AD1-013 E	3.1375	Adder	3.69
933931	AD1-016 C	0.9804	Adder	1.15
933932	AD1-016 E	1.5996	Adder	1.88
934101	AD1-039 1	7.5362	Adder	8.87
934111	AD1-039 2	7.6301	Adder	8.98
934431	AD1-067 C	0.1397	Adder	0.16
934432	AD1-067 E	0.5873	Adder	0.69
934701	AD1-098 C O1	7.3184	Adder	8.61
934702	AD1-098 E O1	5.3432	Adder	6.29
934721	AD1-100 C	25.3457	Adder	29.82
934722	AD1-100 E	118.2800	Adder	139.15
934871	AD1-116 C	1.0107	Adder	1.19
934872	AD1-116 E	1.6490	Adder	1.94
934971	AD1-129 C	0.9544	Adder	1.12
934972	AD1-129 E	0.6363	Adder	0.75
935001	AD1-133 C O1	23.5023	Adder	27.65

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
935002	AD1-133 E O1	15.6682	Adder	18.43
936291	AD2-038 C O1	2.4826	Adder	2.92
936292	AD2-038 E O1	16.6143	Adder	19.55
936371	AD2-047 C O1	4.9436	Adder	5.82
936372	AD2-047 E O1	24.1366	Adder	28.4
936461	AD2-060	2.9080	Adder	3.42
936511	AD2-066 C O1	8.9497	Adder	10.53
936512	AD2-066 E O1	5.9665	Adder	7.02
937001	AD2-134 C	2.9079	Adder	3.42
937002	AD2-134 E	12.0124	Adder	14.13
937401	AD2-194 1	8.2426	Adder	9.7
937411	AD2-194 2	8.2421	Adder	9.7
938511	AE1-070 1	9.6851	Adder	11.39
938521	AE1-070 2	8.8603	Adder	10.42
938851	AE1-113 C	8.4369	Adder	9.93
938852	AE1-113 E	29.9126	Adder	35.19
939321	AE1-163 C O1	6.2383	Adder	7.34
939322	AE1-163 E O1	38.3212	Adder	45.08
939351	AE1-166 C O1	12.5095	Adder	14.72
939352	AE1-166 E O1	11.5472	Adder	13.58
939401	AE1-172 C O1	6.9294	Adder	8.15
939402	AE1-172 E O1	32.5126	Adder	38.25
940101	AE1-252 C O1	13.9207	Adder	16.38
940102	AE1-252 E O1	9.2805	Adder	10.92
940752	AE2-062 E	0.1379	Adder	0.16
941131	AE2-107 C	7.7372	Adder	9.1
941132	AE2-107 E	5.1581	Adder	6.07
941551	AE2-152 C O1	14.4340	Adder	16.98
941552	AE2-152 E O1	9.6227	Adder	11.32
941561	AE2-153 C O1	5.2303	Adder	6.15
941562	AE2-153 E O1	24.4874	Adder	28.81
941731	AE2-173 O1	3.3326	Adder	3.92
942111	AE2-223 C	2.4629	Adder	2.9
942112	AE2-223 E	16.4823	Adder	19.39
942421	AE2-255 C O1	3.1958	Adder	3.76
942422	AE2-255 E O1	9.5874	Adder	11.28
942651	AE2-281 C O1	0.8912	Adder	1.05
942652	AE2-281 E O1	5.4745	Adder	6.44
942991	AE2-321 C	8.6313	Adder	10.15
942992	AE2-321 E	4.2513	Adder	5.0
943121	AE2-341 C	13.4892	Adder	15.87
943122	AE2-341 E	6.6239	Adder	7.79
943381	AF1-009 C	0.6331	Adder	0.74
943382	AF1-009 E	2.5323	Adder	2.98
943591	AF1-030 C O1	8.9705	Adder	10.55
943592	AF1-030 E O1	4.4383	Adder	5.22
943801	AF1-048 C	4.0348	Adder	4.75
943802	AF1-048 E	2.6899	Adder	3.16
944041	AF1-072	2.2734	Adder	2.67
944911	AF1-156 C	13.3730	Adder	15.73
944912	AF1-156 E	8.9153	Adder	10.49
945351	AF1-200 FTIR	329.4462	Merchant Transmission	329.4462

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
946661	AF1-330 C	2.1155	Adder	2.49
946662	AF1-330 E	0.4644	Adder	0.55
946671	AF1-331	2.5508	Adder	3.0
957021	AF2-003 C O1	3.6510	Adder	8.1
957022	AF2-003 E O1	17.0932	Adder	37.94
957331	AF2-027 C	1.3943	Adder	3.1
957332	AF2-027 E	2.0914	Adder	4.64
958011	AF2-095 C O1	10.4805	Adder	23.26
958012	AF2-095 E O1	4.9320	Adder	10.95
958021	AF2-096 C O1	20.1649	Adder	44.76
958022	AF2-096 E O1	9.5360	Adder	21.17
958481	AF2-142 C	6.3433	Adder	14.08
958482	AF2-142 E	4.2288	Adder	9.39
958491	AF2-143 C	6.0728	Adder	13.48
958492	AF2-143 E	4.0486	Adder	8.99
959341	AF2-225 C	4.2172	Adder	9.36
959342	AF2-225 E	5.8238	Adder	12.93
959351	AF2-226 C	1.4049	Adder	3.12
959352	AF2-226 E	2.1074	Adder	4.68
960281	AF2-319 C	1.4049	Adder	3.12
960282	AF2-319 E	2.1074	Adder	4.68
960381	AF2-329	3.7097	Adder	8.23
960581	AF2-349 C	12.2138	Adder	27.11
960582	AF2-349 E	8.1425	Adder	18.07
960591	AF2-350 C O1	4.6238	Adder	10.26
960592	AF2-350 E O1	3.0825	Adder	6.84
960601	AF2-351 C O1	0.6165	Adder	1.37
960602	AF2-351 E O1	0.9248	Adder	2.05
960721	AF2-363 C O1	3.3397	Adder	7.41
960722	AF2-363 E O1	2.2265	Adder	4.94
960731	AF2-364 C O1	3.4379	Adder	7.63
960732	AF2-364 E O1	2.2919	Adder	5.09
960751	AF2-366 C O1	3.9034	Adder	8.66
960752	AF2-366 E O1	2.6023	Adder	5.78
961501	AF2-441 C O1	5.6075	Adder	12.45
961502	AF2-441 E O1	8.4112	Adder	18.67
WEC	WEC	4.6573	Confirmed LTF	4.6573
CALDERWOOD	CALDERWOOD	0.0656	Confirmed LTF	0.0656
CBM-W2	CBM-W2	25.6101	Confirmed LTF	25.6101
NY	NY	1.4616	Confirmed LTF	1.4616
CBM-W1	CBM-W1	79.8388	Confirmed LTF	79.8388
TVA	TVA	1.6492	Confirmed LTF	1.6492
O-066	O-066	17.3242	Confirmed LTF	17.3242
CHEOAH	CHEOAH	0.0801	Confirmed LTF	0.0801
CBM-S1	CBM-S1	6.1514	Confirmed LTF	6.1514
G-007	G-007	2.6780	Confirmed LTF	2.6780
MADISON	MADISON	24.8371	Confirmed LTF	24.8371
MEC	MEC	16.3540	Confirmed LTF	16.3540
BLUEG	BLUEG	2.3592	Confirmed LTF	2.3592
TRIMBLE	TRIMBLE	0.8147	Confirmed LTF	0.8147
CATAWBA	CATAWBA	0.3703	Confirmed LTF	0.3703

11.7 Queue Dependencies

The Queue Projects below are listed in one or more indices for the overloads identified in your report. These projects contribute to the loading of the overloaded facilities identified in your report. The percent overload of a facility and cost allocation you may have towards a particular reinforcement could vary depending on the action of these earlier projects. The status of each project at the time of the analysis is presented in the table. This list may change as earlier projects withdraw or modify their requests.

Queue Number	Project Name	Status
AA1-018	Powerton-Goodings Grove	In Service
AA2-030	Nelson	Active
AA2-123	Marengo 34kV	In Service
AB1-089	Byron-Wayne 345kV #1	Active
AB1-091	Davis Creek 345kV	Active
AB1-122	Kendall-Tazewell & Dresden-Mole Creek	Active
AB2-047	Brokaw-Pontiac Midpoint	Engineering and Procurement
AB2-096	Silver Lake-Cherry Valley	Active
AC1-033	Kewanee	Active
AC1-109	Aurora 345kV	Active
AC1-110	Aurora 138kV	Active
AC1-111	Aurora 138kV	Active
AC1-113	Rockford	Active
AC1-114	Rockford II	Active
AC1-142A	Joliet	Active
AC1-168	Kewanee-Streator	Active
AC1-171	Powerton	Active
AC1-214	Crescent Ridge	Engineering and Procurement
AC2-115	Rockford	Active
AC2-116	Rockford II	Active
AC2-117	University Park North	Engineering and Procurement
AC2-154	Davis Creek 138kV	Active
AC2-156	Sandwich 34.5kV	Active
AD1-013	Twombly Road 138kV	Active
AD1-016	Marengo	Active
AD1-031	Kewanee 138 kV	Active
AD1-039	Kendall-Tazewell & Dresden-Mole Creek	Active
AD1-067	Mendota Hills	Active
AD1-096	Stillman Valley 34 kV	Active
AD1-098	Dixon-McGirr	Active
AD1-100	Loretto-Wilton & Braidwood-Davis Creek	Active
AD1-116	Nevada 345 kV	Active
AD1-129	Belvidere 34 kV	Active
AD1-133	Pontiac MidPoint-Dresden	Active
AD2-038	Powerton	Active
AD2-047	Davis Creek 138 kV	Active
AD2-060	Davis Creek 138kV	Active
AD2-066	Mazon-Crescent Ridge	Active
AD2-102	Wempletown 345 kV	Active

Queue Number	Project Name	Status
AD2-134	Shady Oaks	Active
AD2-172	Lena 138kV	Active
AD2-194	Elwood	Active
AD2-214	Rock Falls-Garden Plains	Active
AE1-070	Elwood 345 kV	Active
AE1-113	Mole Creek 345 kV	Active
AE1-114	Maryland-Lancaster 138 kV	Active
AE1-134	Nelson 345 kV	Active
AE1-163	Powerton-Nevada 345 kV	Active
AE1-166	Loretto-Wilton & Braidwood-Davis Creek	Active
AE1-172	Loretto-Wilton Center	Active
AE1-193	Crete 345 kV	Active
AE1-194	Crete 345 kV	Active
AE1-195	Crete 345 kV	Active
AE1-198	Crete 345 kV	Active
AE1-205	McLean 345 kV	Active
AE1-252	Loretto-Wilton Center	Active
AE2-035	Lena 138 kV	Active
AE2-062	Normantown	Active
AE2-107	Haumesser Road 138 kV	Active
AE2-152	Loretto-Wilton & Braidwood-Davis Creek	Active
AE2-153	Braidwood-Davis Creek	Active
AE2-173	McLean 345 kV	Active
AE2-223	McLean 345 kV	Active
AE2-255	Molecreek 345 kV	Active
AE2-281	Powerton-Nevada 345 kV	Active
AE2-321	Belvidere-Marengo 138 kV	Active
AE2-341	Sandwich-Plano	Active
AF1-009	Dixon-McGirr	Active
AF1-011	Schauff Road	Active
AF1-012	Electric Junc-Nelson	Active
AF1-030	Plano-R 138 kV	Active
AF1-048	Belvidere-Marengo	Active
AF1-060	Lena 138 kV	Active
AF1-072	Rocky Road	Active
AF1-156	Braidwood-Davis Creek	Active
AF1-200	Plano 345 kV	Active
AF1-280	Nelson-Lee County	Active
AF1-281	Nelson-Lee County	Active
AF1-296	Garden Plain 138 kV	Active
AF1-314	Lena 138 kV	Active
AF1-317	Electric Jct-Nelson	Active
AF1-318	Crescent Ridge-Corbin	Active
AF1-330	Marengo	Active
AF1-331	Twombly Road	Active
AF2-003	Powerton-Mole Creek	Active
AF2-027	Zion Energy Center 345 kV	Active
AF2-031	River E.C.	Active
AF2-041	Nelson-Electric Junction 345 kV	Active
AF2-069	Crescent Ridge 138 kV	Active
AF2-070	Crescent Ridge 138 kV	Active
AF2-095	Wilmington-Davis Creek	Active

Queue Number	Project Name	Status
AF2-096	Braidwood-East Frankfort 345 kV	Active
AF2-128	Crescent Ridge-Corbin 138 kV	Active
AF2-142	Nevada 345 kV	Active
AF2-143	Powerton-Nevada 345 kV	Active
AF2-182	Nelson-Lee County 345 kV II	Active
AF2-183	Nelson-Lee County 345 kV	Active
AF2-199	Nelson-Electric Junction 345 kV	Active
AF2-200	Nelson-Electric Junction 345 kV	Active
AF2-201	Lena-Ecogrove 138 kV	Active
AF2-225	McLean 345 kV	Active
AF2-226	Katydid Road 345 kV	Active
AF2-252	Blue Mound 345 kV	Active
AF2-267	Lancaster 138 kV	Active
AF2-319	Katydid Road 345 kV	Active
AF2-329	Sandwich-Plano 138 kV	Active
AF2-346	Electric Junction-Nelson 345 kV	Active
AF2-349	Garden Prairie-Silver Lake 345 kV	Active
AF2-350	Kensington 138 kV	Active
AF2-351	Kensington 138 kV	Active
AF2-352	Blue Mound 34.5 kV	Active
AF2-363	Glidden 138 kV	Active
AF2-364	Wayne Red 138 kV	Active
AF2-366	Glidden-Waterman 345 kV	Active
AF2-392	Nelson-Dixon 138 kV	Active
AF2-393	Nelson-Dixon 138 kV	Active
AF2-394	Nelson-Dixon 138 kV	Active
AF2-441	Burnham 138kV	Active
U3-021	Silver Lake-Cherry Valley	Active
X3-005	Wildwood 12kV	In Service
Y3-013	Zion Energy Center	Active
Z1-106	West Chicago 34kV	In Service
Z1-107	Joliet 34kV	In Service
Z1-108	McHenry 34kV	In Service
J1058	MISO	MISO
J351	MISO	MISO
J643	MISO	MISO
J847	MISO	MISO

11.8 Contingency Descriptions - Primary POI

Contingency Name	Contingency Definition
COMED_P1-2_695_B2	CONTINGENCY 'COMED_P1-2_695_B2' OPEN BRANCH FROM BUS 243206 TO BUS 270644 CKT 1 / 243206 05DUMONT 765 270644 WILTO; 765 1 END
COMED_P4_112-65-BT2-3__	CONTINGENCY 'COMED_P4_112-65-BT2-3__' TRIP BRANCH FROM BUS 270644 TO BUS 270607 CKT 1 / WILTO; 765 COLLI; 765 TRIP BRANCH FROM BUS 275232 TO BUS 270644 CKT 1 / WILTO;3M 345 WILTO; 765 TRIP BRANCH FROM BUS 275232 TO BUS 270926 CKT 1 / WILTO;3M 345 WILTO; B 345 TRIP BRANCH FROM BUS 275232 TO BUS 275332 CKT 1 / WILTO;3M 345 WILTO;3C 33 END
COMED_P4_112-65-BT5-6__	CONTINGENCY 'COMED_P4_112-65-BT5-6__' TRIP BRANCH FROM BUS 270644 TO BUS 270607 CKT 1 / WILTO; 765 COLLI; 765 TRIP BRANCH FROM BUS 275233 TO BUS 270644 CKT 1 / WILTO;4M 345 WILTO; 765 TRIP BRANCH FROM BUS 275233 TO BUS 270927 CKT 1 / WILTO;4M 345 WILTO; R 345 TRIP BRANCH FROM BUS 275233 TO BUS 275333 CKT 1 / WILTO;4M 345 WILTO;4C 33 END

12 Short Circuit Analysis - Primary POI

The following breakers are overdutied:

None

12.1 System Reinforcements - Short Circuit

None

13 Summer Peak - Load Flow Analysis - Secondary POI

The Queue Project AF2-441 was evaluated as a 200.0 MW (Capacity 80.0 MW) injection at the Burnham 345 kV substation in the ComEd area. Project AF2-441 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AF2-441 was studied with a commercial probability of 53.0 %. Potential network impacts were as follows:

13.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

13.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

None

13.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

ID	FROM BUS#	FROM BUS	kV	FROM BUS AREA	TO BUS#	TO BUS	kV	TO BUS AREA	CK T ID	CONT NAME	Type	Rating MVA	PRE PROJE CT LOADIN G %	POST PROJE CT LOADIN G %	AC/D C	MW IMPAC T
95579259	255113	17STILLWELL	345.0	NIPS	243219	05DUMONT	345.0	AEP	1	COMED_P1-2_695_B2	single	1409.0	108.98	110.06	DC	15.22
96795144	270926	WILTON ; B	345.0	CE	275232	WILTON ;3M	345.0	CE	1	COMED_P4_11 2-65-BT5-6_	breaker	1379.0	122.17	122.24	DC	30.86
96795132	270927	WILTON ; R	345.0	CE	275233	WILTON ;4M	345.0	CE	1	COMED_P4_11 2-65-BT2-3_	breaker	1379.0	124.73	124.79	DC	31.51
96795143	275232	WILTON ;3M	345.0	CE	270644	WILTON ;	765.0	CE	1	COMED_P4_11 2-65-BT5-6_	breaker	1379.0	122.17	122.24	DC	30.86
96795131	275233	WILTON ;4M	345.0	CE	270644	WILTON ;	765.0	CE	1	COMED_P4_11 2-65-BT2-3_	breaker	1379.0	124.73	124.79	DC	31.51

13.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed

with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

None

13.5 Flow Gate Details - Secondary POI

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

13.5.1 Index 1

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
95579259	255113	17STILLWELL	NIPS	243219	05DUMONT	AEP	1	COMED_P1-2_695_B2	single	1409.0	108.98	110.06	DC	15.22

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274723	RIVER EC ;12	5.5486	80/20	5.5486
274724	RIVER EC ;11	5.5078	80/20	5.5078
274788	SE CHICAG;5U (Deactivation : 01/06/2020)	7.5182	80/20	7.5182
274789	SE CHICAG;6U (Deactivation : 01/06/2020)	7.5381	80/20	7.5381
274790	SE CHICAG;7U (Deactivation : 01/06/2020)	7.6372	80/20	7.6372

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274791	SE CHICAG;8U (Deactivation : 01/06/2020)	7.6372	80/20	7.6372
274792	SE CHICAG;9U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274793	SE CHICAG;0U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274794	SE CHICAG;1U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274795	SE CHICAG;2U (Deactivation : 01/06/2020)	7.5475	80/20	7.5475
274798	UNIV PARK;1U	1.5551	80/20	1.5551
274801	UNIV PARK;4U	1.5435	80/20	1.5435
274826	FISK ;BP	2.9034	80/20	2.9034
274827	FISK ;RP	2.0577	80/20	2.0577
274830	U3-021 1	6.0871	Adder	7.16
274831	U3-021 2	6.0871	Adder	7.16
276164	X3-005 C	0.1075	80/20	0.1075
293540	O-012 C	0.6150	80/20	0.6150
915011	Y3-013 1	3.7444	Adder	4.41
915021	Y3-013 2	3.7444	Adder	4.41
915031	Y3-013 3	3.7444	Adder	4.41
919581	AA2-030	17.5313	Adder	20.63
924041	AB2-047 C O1	3.3636	Adder	3.96
924471	AB2-096	42.2718	Adder	49.73
925581	AC1-033 C	1.4016	Adder	1.65
926311	AC1-109 1	1.9040	Adder	2.24
926321	AC1-109 2	1.9040	Adder	2.24
926331	AC1-110 1	1.8980	Adder	2.23
926341	AC1-110 2	1.8980	Adder	2.23
926351	AC1-111 1	0.7620	Adder	0.9
926361	AC1-111 2	0.7620	Adder	0.9
926371	AC1-111 3	0.7620	Adder	0.9
926381	AC1-111 4	0.7620	Adder	0.9
926391	AC1-111 5	0.7620	Adder	0.9
926401	AC1-111 6	0.7620	Adder	0.9
926431	AC1-114	2.3739	Adder	2.79
926821	AC1-168 C O1	1.1406	Adder	1.34
926841	AC1-171 C O1	1.0368	Adder	1.22
927201	AC1-214 C O1	2.0483	Adder	2.41
927451	AC1-142A 1	4.2157	Adder	4.96
927461	AC1-142A 2	4.2160	Adder	4.96
927511	AC1-113 1	1.1869	Adder	1.4
927521	AC1-113 2	1.1869	Adder	1.4
930481	AB1-089	65.6043	Adder	77.18
930501	AB1-091 O1	76.9692	Adder	90.55
930741	AB1-122 1O1	71.4553	Adder	84.07
930751	AB1-122 2O1	73.8990	Adder	86.94
932881	AC2-115 1	2.3739	Adder	2.79

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
932891	AC2-115 2	2.3739	Adder	2.79
932921	AC2-116	0.8309	Adder	0.98
932931	AC2-117	5.1330	Adder	6.04
933411	AC2-154 C	2.6404	Adder	3.11
933431	AC2-156 C O1	0.9541	Adder	1.12
933911	AD1-013 C	1.8539	Adder	2.18
933931	AD1-016 C	0.9273	Adder	1.09
934051	AD1-031 C O1	2.8459	Adder	3.35
934101	AD1-039 1	7.0026	Adder	8.24
934111	AD1-039 2	7.2421	Adder	8.52
934431	AD1-067 C	0.1318	Adder	0.16
934651	AD1-096 C	0.8893	Adder	1.05
934701	AD1-098 C O1	6.9062	Adder	8.12
934721	AD1-100 C	19.5139	Adder	22.96
934871	AD1-116 C	0.9472	Adder	1.11
934971	AD1-129 C	0.9021	Adder	1.06
935001	AD1-133 C O1	20.6718	Adder	24.32
936291	AD2-038 C O1	2.3283	Adder	2.74
936371	AD2-047 C O1	4.7249	Adder	5.56
936461	AD2-060	2.7793	Adder	3.27
936511	AD2-066 C O1	8.3972	Adder	9.88
936791	AD2-102 C	14.1066	Adder	16.6
937001	AD2-134 C	2.7442	Adder	3.23
937311	AD2-172 C	2.4544	Adder	2.89
937401	AD2-194 1	7.7948	Adder	9.17
937411	AD2-194 2	7.7923	Adder	9.17
937531	AD2-214 C	4.3946	Adder	5.17
938511	AE1-070 1	9.1589	Adder	10.78
938521	AE1-070 2	8.3767	Adder	9.85
938851	AE1-113 C	7.9623	Adder	9.37
938861	AE1-114 C O1	3.9206	Adder	4.61
939051	AE1-134 1	1.3623	Adder	1.6
939061	AE1-134 2	1.3623	Adder	1.6
939321	AE1-163 C O1	5.8506	Adder	6.88
939351	AE1-166 C O1	10.2692	Adder	12.08
939401	AE1-172 C O1	5.2573	Adder	6.19
939631	AE1-193 C	9.0290	Adder	10.62
939641	AE1-194 C	9.0290	Adder	10.62
939651	AE1-195 C	9.0290	Adder	10.62
939681	AE1-198 C	26.8091	Adder	31.54
939741	AE1-205 C O1	8.6937	Adder	10.23
940101	AE1-252 C O1	10.5616	Adder	12.43
940501	AE2-035 C	2.4544	Adder	2.89
941131	AE2-107 C	7.3063	Adder	8.6
941551	AE2-152 C O1	11.8491	Adder	13.94
941561	AE2-153 C O1	4.7360	Adder	5.57
941731	AE2-173 O1	5.1748	Adder	6.09
942111	AE2-223 C	2.0182	Adder	2.37
942421	AE2-255 C O1	3.0160	Adder	3.55
942651	AE2-281 C O1	0.8358	Adder	0.98
942991	AE2-321 C	8.1632	Adder	9.6
943121	AE2-341 C	12.7367	Adder	14.98

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
943381	AF1-009 C	0.5974	Adder	0.7
943401	AF1-011 C	1.2399	Adder	1.46
943411	AF1-012 C	11.9631	Adder	14.07
943591	AF1-030 C O1	8.4700	Adder	9.96
943801	AF1-048 C	3.8160	Adder	4.49
943921	AF1-060	1.2085	Adder	1.42
944041	AF1-072	2.1512	Adder	2.53
944911	AF1-156 C	12.1092	Adder	14.25
945351	AF1-200 FTIR	308.5264	Merchant Transmission	308.5264
946151	AF1-280 C O1	15.5391	Adder	18.28
946161	AF1-281 C	0.3403	Adder	0.4
946321	AF1-296 C O1	3.9241	Adder	4.62
946501	AF1-314 C	4.3608	Adder	5.13
946531	AF1-317 C O1	2.2787	Adder	2.68
946541	AF1-318 C O1	5.7512	Adder	6.77
946661	AF1-330 C	2.0011	Adder	2.35
946671	AF1-331	2.4077	Adder	2.83
951721	J643	27.1460	PJM External (MISO)	27.1460
953871	J847	13.8150	PJM External (MISO)	13.8150
954751	J351	446.6739	PJM External (MISO)	446.6739
955741	J1058	38.3400	PJM External (MISO)	38.3400
957021	AF2-003 C O2	3.3475	Adder	7.43
957331	AF2-027 C	1.3230	Adder	2.94
957371	AF2-031 C O2	1.5596	80/20	1.5596
957471	AF2-041 C	11.2861	Adder	25.05
957751	AF2-069 C	0.1257	Adder	0.28
957761	AF2-070 C	0.1771	Adder	0.39
958011	AF2-095 C O2	9.8782	Adder	21.93
958021	AF2-096 C O2	17.8412	Adder	39.6
958341	AF2-128 C O2	0.8102	Adder	1.8
958481	AF2-142 C	5.9447	Adder	13.2
958491	AF2-143 C	5.6954	Adder	12.64
958911	AF2-182	10.8206	Adder	24.02
958921	AF2-183 C	1.9237	Adder	4.27
959081	AF2-199 C O2	3.7620	Adder	8.35
959091	AF2-200 C O2	7.5241	Adder	16.7
959101	AF2-201 C O2	3.1839	Adder	7.07
959341	AF2-225 C	3.4557	Adder	7.67
959351	AF2-226 C	1.3489	Adder	2.99
959611	AF2-252 C	0.9462	Adder	2.1
959761	AF2-267 C O2	2.2994	Adder	5.1
960281	AF2-319 C	1.3489	Adder	2.99
960381	AF2-329	3.5027	Adder	7.78
960551	AF2-346 C	2.7173	Adder	6.03
960581	AF2-349 C	11.5496	Adder	25.64
960591	AF2-350 C O2	4.4191	Adder	9.81
960601	AF2-351 C O2	0.5892	Adder	1.31
960611	AF2-352 C	0.9462	Adder	2.1
960721	AF2-363 C O2	3.1287	Adder	6.94
960731	AF2-364 C O2	3.2498	Adder	7.21
960751	AF2-366 C O2	3.6877	Adder	8.19
961011	AF2-392 C O2	2.0929	Adder	4.65

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
961021	AF2-393 O2	3.5674	Adder	7.92
961031	AF2-394 O2	2.3783	Adder	5.28
961501	AF2-441 C O2	15.2240	80/20	15.2240
WEC	WEC	4.4132	Confirmed LTF	4.4132
CBM-W2	CBM-W2	24.9631	Confirmed LTF	24.9631
NY	NY	1.3416	Confirmed LTF	1.3416
CBM-W1	CBM-W1	79.8013	Confirmed LTF	79.8013
TVA	TVA	1.7262	Confirmed LTF	1.7262
CHEOAH	CHEOAH	0.0065	Confirmed LTF	0.0065
CBM-S1	CBM-S1	7.0972	Confirmed LTF	7.0972
MADISON	MADISON	22.9824	Confirmed LTF	22.9824
MEC	MEC	15.3656	Confirmed LTF	15.3656
BLUEG	BLUEG	1.7030	Confirmed LTF	1.7030
TRIMBLE	TRIMBLE	0.5994	Confirmed LTF	0.5994
CATAWBA	CATAWBA	0.3045	Confirmed LTF	0.3045

13.5.2 Index 2

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795144	270926	WILTON ; B	CE	275232	WILTON ;3M	CE	1	COMED_P4_112-65-BT5-6__	breaker	1379.0	122.17	122.24	DC	30.86

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.7664	50/50	3.7664
274772	LINCOLN ;3U	3.7664	50/50	3.7664
274773	LINCOLN ;4U	3.7664	50/50	3.7664
274774	LINCOLN ;5U	3.7664	50/50	3.7664
274775	LINCOLN ;6U	3.7664	50/50	3.7664
274776	LINCOLN ;7U	3.7664	50/50	3.7664
274777	LINCOLN ;8U	3.7664	50/50	3.7664
274830	U3-021 1	6.3035	Adder	7.42
274831	U3-021 2	6.3035	Adder	7.42
274881	PILOT HIL;1E	19.9396	Adder	23.46
274890	CAYUG;1U E	17.0054	Adder	20.01
274891	CAYUG;2U E	17.0054	Adder	20.01
275149	KELLYCK ;1E	19.9396	Adder	23.46
276167	Z1-106 E2	1.3063	Adder	1.54
276168	Z1-106 E1	1.3062	Adder	1.54
276169	Z1-107 E	2.6738	Adder	3.15
276170	Z1-108 E	2.5704	Adder	3.02
290021	O50 E	20.0260	Adder	23.56
290051	GSG-6; E	10.8913	Adder	12.81
290108	LEEDK;1U E	25.1940	Adder	29.64
293061	N-015 E	16.4434	Adder	19.35
293644	O22 E1	10.5913	Adder	12.46
293645	O22 E2	20.5595	Adder	24.19
294392	P-010 E	20.8831	Adder	24.57

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
910542	X3-005 E	0.7562	Adder	0.89
915011	Y3-013 1	3.8635	Adder	4.55
915021	Y3-013 2	3.8635	Adder	4.55
915031	Y3-013 3	3.8635	Adder	4.55
918052	AA1-018 E OP	16.9837	Adder	19.98
920272	AA2-123 E	2.5262	Adder	2.97
924471	AB2-096	43.7741	Adder	51.5
926311	AC1-109 1	1.9765	Adder	2.33
926321	AC1-109 2	1.9765	Adder	2.33
926331	AC1-110 1	1.9634	Adder	2.31
926341	AC1-110 2	1.9634	Adder	2.31
926351	AC1-111 1	0.7894	Adder	0.93
926361	AC1-111 2	0.7894	Adder	0.93
926371	AC1-111 3	0.7894	Adder	0.93
926381	AC1-111 4	0.7894	Adder	0.93
926391	AC1-111 5	0.7894	Adder	0.93
926401	AC1-111 6	0.7894	Adder	0.93
927451	AC1-142A 1	4.3256	Adder	5.09
927461	AC1-142A 2	4.3256	Adder	5.09
930501	AB1-091 O1	79.3394	Adder	93.34
930741	AB1-122 1O1	75.3017	Adder	88.59
930751	AB1-122 2O1	76.2303	Adder	89.68
933411	AC2-154 C	2.7061	Adder	3.18
933412	AC2-154 E	4.4152	Adder	5.19
933431	AC2-156 C O1	0.9893	Adder	1.16
933432	AC2-156 E O1	1.6142	Adder	1.9
933911	AD1-013 C	1.9232	Adder	2.26
933912	AD1-013 E	3.0721	Adder	3.61
933931	AD1-016 C	0.9600	Adder	1.13
933932	AD1-016 E	1.5662	Adder	1.84
934101	AD1-039 1	7.3796	Adder	8.68
934111	AD1-039 2	7.4706	Adder	8.79
934431	AD1-067 C	0.1368	Adder	0.16
934432	AD1-067 E	0.5750	Adder	0.68
934701	AD1-098 C O1	7.1661	Adder	8.43
934702	AD1-098 E O1	5.2320	Adder	6.16
934721	AD1-100 C	24.8523	Adder	29.24
934722	AD1-100 E	115.9774	Adder	136.44
934871	AD1-116 C	0.9891	Adder	1.16
934872	AD1-116 E	1.6138	Adder	1.9
934971	AD1-129 C	0.9344	Adder	1.1
934972	AD1-129 E	0.6230	Adder	0.73
935001	AD1-133 C O1	23.0234	Adder	27.09
935002	AD1-133 E O1	15.3490	Adder	18.06
936291	AD2-038 C O1	2.4301	Adder	2.86
936292	AD2-038 E O1	16.2627	Adder	19.13
936371	AD2-047 C O1	4.8425	Adder	5.7
936372	AD2-047 E O1	23.6427	Adder	27.81
936461	AD2-060	2.8485	Adder	3.35
936511	AD2-066 C O1	8.7640	Adder	10.31
936512	AD2-066 E O1	5.8426	Adder	6.87
937001	AD2-134 C	2.8471	Adder	3.35

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937002	AD2-134 E	11.7616	Adder	13.84
937401	AD2-194 1	8.0697	Adder	9.49
937411	AD2-194 2	8.0692	Adder	9.49
938511	AE1-070 1	9.4819	Adder	11.16
938521	AE1-070 2	8.6744	Adder	10.21
938851	AE1-113 C	8.2607	Adder	9.72
938852	AE1-113 E	29.2880	Adder	34.46
939321	AE1-163 C O1	6.1063	Adder	7.18
939322	AE1-163 E O1	37.5102	Adder	44.13
939351	AE1-166 C O1	12.2622	Adder	14.43
939352	AE1-166 E O1	11.3189	Adder	13.32
939401	AE1-172 C O1	6.7946	Adder	7.99
939402	AE1-172 E O1	31.8801	Adder	37.51
940101	AE1-252 C O1	13.6499	Adder	16.06
940102	AE1-252 E O1	9.0999	Adder	10.71
940752	AE2-062 E	0.1351	Adder	0.16
941131	AE2-107 C	7.5761	Adder	8.91
941132	AE2-107 E	5.0507	Adder	5.94
941551	AE2-152 C O1	14.1487	Adder	16.65
941552	AE2-152 E O1	9.4325	Adder	11.1
941561	AE2-153 C O1	5.1247	Adder	6.03
941562	AE2-153 E O1	23.9929	Adder	28.23
941731	AE2-173 O1	3.2665	Adder	3.84
942111	AE2-223 C	2.4140	Adder	2.84
942112	AE2-223 E	16.1551	Adder	19.01
942421	AE2-255 C O1	3.1291	Adder	3.68
942422	AE2-255 E O1	9.3872	Adder	11.04
942651	AE2-281 C O1	0.8723	Adder	1.03
942652	AE2-281 E O1	5.3586	Adder	6.3
942991	AE2-321 C	8.4508	Adder	9.94
942992	AE2-321 E	4.1623	Adder	4.9
943121	AE2-341 C	13.2079	Adder	15.54
943122	AE2-341 E	6.4858	Adder	7.63
943381	AF1-009 C	0.6199	Adder	0.73
943382	AF1-009 E	2.4796	Adder	2.92
943591	AF1-030 C O1	8.7834	Adder	10.33
943592	AF1-030 E O1	4.3457	Adder	5.11
943801	AF1-048 C	3.9504	Adder	4.65
943802	AF1-048 E	2.6336	Adder	3.1
944041	AF1-072	2.2259	Adder	2.62
944911	AF1-156 C	13.1029	Adder	15.42
944912	AF1-156 E	8.7353	Adder	10.28
945351	AF1-200 FTIR	322.6289	Merchant Transmission	322.6289
946661	AF1-330 C	2.0715	Adder	2.44
946662	AF1-330 E	0.4547	Adder	0.53
946671	AF1-331	2.4976	Adder	2.94
957021	AF2-003 C O2	3.5767	Adder	7.94
957022	AF2-003 E O2	16.7456	Adder	37.17
957331	AF2-027 C	1.3651	Adder	3.03
957332	AF2-027 E	2.0477	Adder	4.55
958011	AF2-095 C O2	10.1350	Adder	22.5
958012	AF2-095 E O2	4.7694	Adder	10.59

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
958021	AF2-096 C O2	19.5077	Adder	43.3
958022	AF2-096 E O2	9.2252	Adder	20.48
958481	AF2-142 C	6.2078	Adder	13.78
958482	AF2-142 E	4.1386	Adder	9.19
958491	AF2-143 C	5.9443	Adder	13.19
958492	AF2-143 E	3.9629	Adder	8.8
959341	AF2-225 C	4.1335	Adder	9.18
959342	AF2-225 E	5.7081	Adder	12.67
959351	AF2-226 C	1.3758	Adder	3.05
959352	AF2-226 E	2.0637	Adder	4.58
960281	AF2-319 C	1.3758	Adder	3.05
960282	AF2-319 E	2.0637	Adder	4.58
960381	AF2-329	3.6323	Adder	8.06
960581	AF2-349 C	11.9583	Adder	26.54
960582	AF2-349 E	7.9722	Adder	17.7
960591	AF2-350 C O2	4.5291	Adder	10.05
960592	AF2-350 E O2	3.0194	Adder	6.7
960601	AF2-351 C O2	0.6039	Adder	1.34
960602	AF2-351 E O2	0.9058	Adder	2.01
960721	AF2-363 C O2	3.2432	Adder	7.2
960722	AF2-363 E O2	2.1621	Adder	4.8
960731	AF2-364 C O2	3.3639	Adder	7.47
960732	AF2-364 E O2	2.2426	Adder	4.98
960751	AF2-366 C O2	3.8234	Adder	8.49
960752	AF2-366 E O2	2.5489	Adder	5.66
961501	AF2-441 C O2	5.5606	Adder	12.34
961502	AF2-441 E O2	8.3409	Adder	18.51
WEC	WEC	4.5603	Confirmed LTF	4.5603
CALDERWOOD	CALDERWOOD	0.0631	Confirmed LTF	0.0631
CBM-W2	CBM-W2	25.0942	Confirmed LTF	25.0942
NY	NY	1.4306	Confirmed LTF	1.4306
CBM-W1	CBM-W1	78.1875	Confirmed LTF	78.1875
TVA	TVA	1.6184	Confirmed LTF	1.6184
O-066	O-066	16.9546	Confirmed LTF	16.9546
CHEOAH	CHEOAH	0.0771	Confirmed LTF	0.0771
CBM-S1	CBM-S1	6.0407	Confirmed LTF	6.0407
G-007	G-007	2.6218	Confirmed LTF	2.6218
MADISON	MADISON	24.3210	Confirmed LTF	24.3210
MEC	MEC	16.0171	Confirmed LTF	16.0171
BLUEG	BLUEG	2.3071	Confirmed LTF	2.3071
TRIMBLE	TRIMBLE	0.7969	Confirmed LTF	0.7969
CATAWBA	CATAWBA	0.3619	Confirmed LTF	0.3619

13.5.3 Index 3

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795132	270927	WILTON	CE	275233	WILTON	CE	1	COMED_P4_112-65-BT2-3__	breaker	1379.0	124.73	124.79	DC	31.51

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.8683	50/50	3.8683
274772	LINCOLN ;3U	3.8683	50/50	3.8683
274773	LINCOLN ;4U	3.8683	50/50	3.8683
274774	LINCOLN ;5U	3.8683	50/50	3.8683
274775	LINCOLN ;6U	3.8683	50/50	3.8683
274776	LINCOLN ;7U	3.8683	50/50	3.8683
274777	LINCOLN ;8U	3.8683	50/50	3.8683
274830	U3-021 1	6.4380	Adder	7.57
274831	U3-021 2	6.4380	Adder	7.57
274881	PILOT HIL;1E	20.3561	Adder	23.95
274890	CAYUG;1U E	17.3451	Adder	20.41
274891	CAYUG;2U E	17.3451	Adder	20.41
275149	KELLYCK ;1E	20.3561	Adder	23.95
276167	Z1-106 E2	1.3342	Adder	1.57
276168	Z1-106 E1	1.3341	Adder	1.57
276169	Z1-107 E	2.7309	Adder	3.21
276170	Z1-108 E	2.6251	Adder	3.09
290021	O50 E	20.4530	Adder	24.06
290051	GSG-6; E	11.1236	Adder	13.09
290108	LEEDK;1U E	25.7295	Adder	30.27
293061	N-015 E	16.7861	Adder	19.75
293644	O22 E1	10.8153	Adder	12.72
293645	O22 E2	20.9944	Adder	24.7
294392	P-010 E	21.3184	Adder	25.08
910542	X3-005 E	0.7727	Adder	0.91
915011	Y3-013 1	3.9461	Adder	4.64
915021	Y3-013 2	3.9461	Adder	4.64
915031	Y3-013 3	3.9461	Adder	4.64
918052	AA1-018 E OP	17.3542	Adder	20.42
920272	AA2-123 E	2.5799	Adder	3.04
924471	AB2-096	44.7083	Adder	52.6
926311	AC1-109 1	2.0186	Adder	2.37
926321	AC1-109 2	2.0186	Adder	2.37
926331	AC1-110 1	2.0052	Adder	2.36
926341	AC1-110 2	2.0052	Adder	2.36
926351	AC1-111 1	0.8063	Adder	0.95
926361	AC1-111 2	0.8063	Adder	0.95
926371	AC1-111 3	0.8063	Adder	0.95
926381	AC1-111 4	0.8063	Adder	0.95
926391	AC1-111 5	0.8063	Adder	0.95
926401	AC1-111 6	0.8063	Adder	0.95
927451	AC1-142A 1	4.4186	Adder	5.2
927461	AC1-142A 2	4.4186	Adder	5.2
930501	AB1-091 O1	80.9897	Adder	95.28
930741	AB1-122 1O1	76.8999	Adder	90.47
930751	AB1-122 2O1	77.8579	Adder	91.6
933411	AC2-154 C	2.7626	Adder	3.25
933412	AC2-154 E	4.5074	Adder	5.3
933431	AC2-156 C O1	1.0103	Adder	1.19
933432	AC2-156 E O1	1.6485	Adder	1.94

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
933911	AD1-013 C	1.9642	Adder	2.31
933912	AD1-013 E	3.1375	Adder	3.69
933931	AD1-016 C	0.9804	Adder	1.15
933932	AD1-016 E	1.5996	Adder	1.88
934101	AD1-039 1	7.5362	Adder	8.87
934111	AD1-039 2	7.6301	Adder	8.98
934431	AD1-067 C	0.1397	Adder	0.16
934432	AD1-067 E	0.5873	Adder	0.69
934701	AD1-098 C O1	7.3184	Adder	8.61
934702	AD1-098 E O1	5.3432	Adder	6.29
934721	AD1-100 C	25.3457	Adder	29.82
934722	AD1-100 E	118.2800	Adder	139.15
934871	AD1-116 C	1.0107	Adder	1.19
934872	AD1-116 E	1.6490	Adder	1.94
934971	AD1-129 C	0.9544	Adder	1.12
934972	AD1-129 E	0.6363	Adder	0.75
935001	AD1-133 C O1	23.5023	Adder	27.65
935002	AD1-133 E O1	15.6682	Adder	18.43
936291	AD2-038 C O1	2.4826	Adder	2.92
936292	AD2-038 E O1	16.6143	Adder	19.55
936371	AD2-047 C O1	4.9436	Adder	5.82
936372	AD2-047 E O1	24.1366	Adder	28.4
936461	AD2-060	2.9080	Adder	3.42
936511	AD2-066 C O1	8.9497	Adder	10.53
936512	AD2-066 E O1	5.9665	Adder	7.02
937001	AD2-134 C	2.9079	Adder	3.42
937002	AD2-134 E	12.0124	Adder	14.13
937401	AD2-194 1	8.2426	Adder	9.7
937411	AD2-194 2	8.2421	Adder	9.7
938511	AE1-070 1	9.6851	Adder	11.39
938521	AE1-070 2	8.8603	Adder	10.42
938851	AE1-113 C	8.4369	Adder	9.93
938852	AE1-113 E	29.9126	Adder	35.19
939321	AE1-163 C O1	6.2383	Adder	7.34
939322	AE1-163 E O1	38.3212	Adder	45.08
939351	AE1-166 C O1	12.5095	Adder	14.72
939352	AE1-166 E O1	11.5472	Adder	13.58
939401	AE1-172 C O1	6.9294	Adder	8.15
939402	AE1-172 E O1	32.5126	Adder	38.25
940101	AE1-252 C O1	13.9207	Adder	16.38
940102	AE1-252 E O1	9.2805	Adder	10.92
940752	AE2-062 E	0.1379	Adder	0.16
941131	AE2-107 C	7.7372	Adder	9.1
941132	AE2-107 E	5.1581	Adder	6.07
941551	AE2-152 C O1	14.4340	Adder	16.98
941552	AE2-152 E O1	9.6227	Adder	11.32
941561	AE2-153 C O1	5.2303	Adder	6.15
941562	AE2-153 E O1	24.4874	Adder	28.81
941731	AE2-173 O1	3.3326	Adder	3.92
942111	AE2-223 C	2.4629	Adder	2.9
942112	AE2-223 E	16.4823	Adder	19.39
942421	AE2-255 C O1	3.1958	Adder	3.76

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
942422	AE2-255 E O1	9.5874	Adder	11.28
942651	AE2-281 C O1	0.8912	Adder	1.05
942652	AE2-281 E O1	5.4745	Adder	6.44
942991	AE2-321 C	8.6313	Adder	10.15
942992	AE2-321 E	4.2513	Adder	5.0
943121	AE2-341 C	13.4892	Adder	15.87
943122	AE2-341 E	6.6239	Adder	7.79
943381	AF1-009 C	0.6331	Adder	0.74
943382	AF1-009 E	2.5323	Adder	2.98
943591	AF1-030 C O1	8.9705	Adder	10.55
943592	AF1-030 E O1	4.4383	Adder	5.22
943801	AF1-048 C	4.0348	Adder	4.75
943802	AF1-048 E	2.6899	Adder	3.16
944041	AF1-072	2.2734	Adder	2.67
944911	AF1-156 C	13.3730	Adder	15.73
944912	AF1-156 E	8.9153	Adder	10.49
945351	AF1-200 FTIR	329.4462	Merchant Transmission	329.4462
946661	AF1-330 C	2.1155	Adder	2.49
946662	AF1-330 E	0.4644	Adder	0.55
946671	AF1-331	2.5508	Adder	3.0
957021	AF2-003 C O2	3.6517	Adder	8.11
957022	AF2-003 E O2	17.0965	Adder	37.95
957331	AF2-027 C	1.3943	Adder	3.1
957332	AF2-027 E	2.0914	Adder	4.64
958011	AF2-095 C O2	10.3469	Adder	22.97
958012	AF2-095 E O2	4.8691	Adder	10.81
958021	AF2-096 C O2	19.9092	Adder	44.19
958022	AF2-096 E O2	9.4150	Adder	20.9
958481	AF2-142 C	6.3433	Adder	14.08
958482	AF2-142 E	4.2288	Adder	9.39
958491	AF2-143 C	6.0728	Adder	13.48
958492	AF2-143 E	4.0486	Adder	8.99
959341	AF2-225 C	4.2172	Adder	9.36
959342	AF2-225 E	5.8238	Adder	12.93
959351	AF2-226 C	1.4049	Adder	3.12
959352	AF2-226 E	2.1074	Adder	4.68
960281	AF2-319 C	1.4049	Adder	3.12
960282	AF2-319 E	2.1074	Adder	4.68
960381	AF2-329	3.7097	Adder	8.23
960581	AF2-349 C	12.2138	Adder	27.11
960582	AF2-349 E	8.1425	Adder	18.07
960591	AF2-350 C O2	4.6238	Adder	10.26
960592	AF2-350 E O2	3.0825	Adder	6.84
960601	AF2-351 C O2	0.6165	Adder	1.37
960602	AF2-351 E O2	0.9248	Adder	2.05
960721	AF2-363 C O2	3.3122	Adder	7.35
960722	AF2-363 E O2	2.2082	Adder	4.9
960731	AF2-364 C O2	3.4357	Adder	7.63
960732	AF2-364 E O2	2.2905	Adder	5.08
960751	AF2-366 C O2	3.9047	Adder	8.67
960752	AF2-366 E O2	2.6031	Adder	5.78
961501	AF2-441 C O2	5.6774	Adder	12.6

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
961502	AF2-441 E O2	8.5161	Adder	18.9
WEC	WEC	4.6573	Confirmed LTF	4.6573
CALDERWOOD	CALDERWOOD	0.0656	Confirmed LTF	0.0656
CBM-W2	CBM-W2	25.6101	Confirmed LTF	25.6101
NY	NY	1.4616	Confirmed LTF	1.4616
CBM-W1	CBM-W1	79.8388	Confirmed LTF	79.8388
TVA	TVA	1.6492	Confirmed LTF	1.6492
O-066	O-066	17.3242	Confirmed LTF	17.3242
CHEOAH	CHEOAH	0.0801	Confirmed LTF	0.0801
CBM-S1	CBM-S1	6.1514	Confirmed LTF	6.1514
G-007	G-007	2.6780	Confirmed LTF	2.6780
MADISON	MADISON	24.8371	Confirmed LTF	24.8371
MEC	MEC	16.3540	Confirmed LTF	16.3540
BLUEG	BLUEG	2.3592	Confirmed LTF	2.3592
TRIMBLE	TRIMBLE	0.8147	Confirmed LTF	0.8147
CATAWBA	CATAWBA	0.3703	Confirmed LTF	0.3703

13.5.4 Index 4

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795143	275232	WILTON ;3M	CE	270644	WILTON ;	CE	1	COMED_P4_112-65-BT5-6__	breaker	1379.0	122.17	122.24	DC	30.86

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.7664	50/50	3.7664
274772	LINCOLN ;3U	3.7664	50/50	3.7664
274773	LINCOLN ;4U	3.7664	50/50	3.7664
274774	LINCOLN ;5U	3.7664	50/50	3.7664
274775	LINCOLN ;6U	3.7664	50/50	3.7664
274776	LINCOLN ;7U	3.7664	50/50	3.7664
274777	LINCOLN ;8U	3.7664	50/50	3.7664
274830	U3-021 1	6.3035	Adder	7.42
274831	U3-021 2	6.3035	Adder	7.42
274881	PILOT HIL;1E	19.9396	Adder	23.46
274890	CAYUG;1U E	17.0054	Adder	20.01
274891	CAYUG;2U E	17.0054	Adder	20.01
275149	KELLYCK ;1E	19.9396	Adder	23.46
276167	Z1-106 E2	1.3063	Adder	1.54
276168	Z1-106 E1	1.3062	Adder	1.54
276169	Z1-107 E	2.6738	Adder	3.15
276170	Z1-108 E	2.5704	Adder	3.02
290021	O50 E	20.0260	Adder	23.56
290051	GSG-6; E	10.8913	Adder	12.81
290108	LEEDK;1U E	25.1940	Adder	29.64
293061	N-015 E	16.4434	Adder	19.35
293644	O22 E1	10.5913	Adder	12.46
293645	O22 E2	20.5595	Adder	24.19

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
294392	P-010 E	20.8831	Adder	24.57
910542	X3-005 E	0.7562	Adder	0.89
915011	Y3-013 1	3.8635	Adder	4.55
915021	Y3-013 2	3.8635	Adder	4.55
915031	Y3-013 3	3.8635	Adder	4.55
918052	AA1-018 E OP	16.9837	Adder	19.98
920272	AA2-123 E	2.5262	Adder	2.97
924471	AB2-096	43.7741	Adder	51.5
926311	AC1-109 1	1.9765	Adder	2.33
926321	AC1-109 2	1.9765	Adder	2.33
926331	AC1-110 1	1.9634	Adder	2.31
926341	AC1-110 2	1.9634	Adder	2.31
926351	AC1-111 1	0.7894	Adder	0.93
926361	AC1-111 2	0.7894	Adder	0.93
926371	AC1-111 3	0.7894	Adder	0.93
926381	AC1-111 4	0.7894	Adder	0.93
926391	AC1-111 5	0.7894	Adder	0.93
926401	AC1-111 6	0.7894	Adder	0.93
927451	AC1-142A 1	4.3256	Adder	5.09
927461	AC1-142A 2	4.3256	Adder	5.09
930501	AB1-091 O1	79.3394	Adder	93.34
930741	AB1-122 1O1	75.3017	Adder	88.59
930751	AB1-122 2O1	76.2303	Adder	89.68
933411	AC2-154 C	2.7061	Adder	3.18
933412	AC2-154 E	4.4152	Adder	5.19
933431	AC2-156 C O1	0.9893	Adder	1.16
933432	AC2-156 E O1	1.6142	Adder	1.9
933911	AD1-013 C	1.9232	Adder	2.26
933912	AD1-013 E	3.0721	Adder	3.61
933931	AD1-016 C	0.9600	Adder	1.13
933932	AD1-016 E	1.5662	Adder	1.84
934101	AD1-039 1	7.3796	Adder	8.68
934111	AD1-039 2	7.4706	Adder	8.79
934431	AD1-067 C	0.1368	Adder	0.16
934432	AD1-067 E	0.5750	Adder	0.68
934701	AD1-098 C O1	7.1661	Adder	8.43
934702	AD1-098 E O1	5.2320	Adder	6.16
934721	AD1-100 C	24.8523	Adder	29.24
934722	AD1-100 E	115.9774	Adder	136.44
934871	AD1-116 C	0.9891	Adder	1.16
934872	AD1-116 E	1.6138	Adder	1.9
934971	AD1-129 C	0.9344	Adder	1.1
934972	AD1-129 E	0.6230	Adder	0.73
935001	AD1-133 C O1	23.0234	Adder	27.09
935002	AD1-133 E O1	15.3490	Adder	18.06
936291	AD2-038 C O1	2.4301	Adder	2.86
936292	AD2-038 E O1	16.2627	Adder	19.13
936371	AD2-047 C O1	4.8425	Adder	5.7
936372	AD2-047 E O1	23.6427	Adder	27.81
936461	AD2-060	2.8485	Adder	3.35
936511	AD2-066 C O1	8.7640	Adder	10.31
936512	AD2-066 E O1	5.8426	Adder	6.87

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
937001	AD2-134 C	2.8471	Adder	3.35
937002	AD2-134 E	11.7616	Adder	13.84
937401	AD2-194 1	8.0697	Adder	9.49
937411	AD2-194 2	8.0692	Adder	9.49
938511	AE1-070 1	9.4819	Adder	11.16
938521	AE1-070 2	8.6744	Adder	10.21
938851	AE1-113 C	8.2607	Adder	9.72
938852	AE1-113 E	29.2880	Adder	34.46
939321	AE1-163 C O1	6.1063	Adder	7.18
939322	AE1-163 E O1	37.5102	Adder	44.13
939351	AE1-166 C O1	12.2622	Adder	14.43
939352	AE1-166 E O1	11.3189	Adder	13.32
939401	AE1-172 C O1	6.7946	Adder	7.99
939402	AE1-172 E O1	31.8801	Adder	37.51
940101	AE1-252 C O1	13.6499	Adder	16.06
940102	AE1-252 E O1	9.0999	Adder	10.71
940752	AE2-062 E	0.1351	Adder	0.16
941131	AE2-107 C	7.5761	Adder	8.91
941132	AE2-107 E	5.0507	Adder	5.94
941551	AE2-152 C O1	14.1487	Adder	16.65
941552	AE2-152 E O1	9.4325	Adder	11.1
941561	AE2-153 C O1	5.1247	Adder	6.03
941562	AE2-153 E O1	23.9929	Adder	28.23
941731	AE2-173 O1	3.2665	Adder	3.84
942111	AE2-223 C	2.4140	Adder	2.84
942112	AE2-223 E	16.1551	Adder	19.01
942421	AE2-255 C O1	3.1291	Adder	3.68
942422	AE2-255 E O1	9.3872	Adder	11.04
942651	AE2-281 C O1	0.8723	Adder	1.03
942652	AE2-281 E O1	5.3586	Adder	6.3
942991	AE2-321 C	8.4508	Adder	9.94
942992	AE2-321 E	4.1623	Adder	4.9
943121	AE2-341 C	13.2079	Adder	15.54
943122	AE2-341 E	6.4858	Adder	7.63
943381	AF1-009 C	0.6199	Adder	0.73
943382	AF1-009 E	2.4796	Adder	2.92
943591	AF1-030 C O1	8.7834	Adder	10.33
943592	AF1-030 E O1	4.3457	Adder	5.11
943801	AF1-048 C	3.9504	Adder	4.65
943802	AF1-048 E	2.6336	Adder	3.1
944041	AF1-072	2.2259	Adder	2.62
944911	AF1-156 C	13.1029	Adder	15.42
944912	AF1-156 E	8.7353	Adder	10.28
945351	AF1-200 FTIR	322.6289	Merchant Transmission	322.6289
946661	AF1-330 C	2.0715	Adder	2.44
946662	AF1-330 E	0.4547	Adder	0.53
946671	AF1-331	2.4976	Adder	2.94
957021	AF2-003 C O2	3.5767	Adder	7.94
957022	AF2-003 E O2	16.7456	Adder	37.17
957331	AF2-027 C	1.3651	Adder	3.03
957332	AF2-027 E	2.0477	Adder	4.55
958011	AF2-095 C O2	10.1350	Adder	22.5

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
958012	AF2-095 E O2	4.7694	Adder	10.59
958021	AF2-096 C O2	19.5077	Adder	43.3
958022	AF2-096 E O2	9.2252	Adder	20.48
958481	AF2-142 C	6.2078	Adder	13.78
958482	AF2-142 E	4.1386	Adder	9.19
958491	AF2-143 C	5.9443	Adder	13.19
958492	AF2-143 E	3.9629	Adder	8.8
959341	AF2-225 C	4.1335	Adder	9.18
959342	AF2-225 E	5.7081	Adder	12.67
959351	AF2-226 C	1.3758	Adder	3.05
959352	AF2-226 E	2.0637	Adder	4.58
960281	AF2-319 C	1.3758	Adder	3.05
960282	AF2-319 E	2.0637	Adder	4.58
960381	AF2-329	3.6323	Adder	8.06
960581	AF2-349 C	11.9583	Adder	26.54
960582	AF2-349 E	7.9722	Adder	17.7
960591	AF2-350 C O2	4.5291	Adder	10.05
960592	AF2-350 E O2	3.0194	Adder	6.7
960601	AF2-351 C O2	0.6039	Adder	1.34
960602	AF2-351 E O2	0.9058	Adder	2.01
960721	AF2-363 C O2	3.2432	Adder	7.2
960722	AF2-363 E O2	2.1621	Adder	4.8
960731	AF2-364 C O2	3.3639	Adder	7.47
960732	AF2-364 E O2	2.2426	Adder	4.98
960751	AF2-366 C O2	3.8234	Adder	8.49
960752	AF2-366 E O2	2.5489	Adder	5.66
961501	AF2-441 C O2	5.5606	Adder	12.34
961502	AF2-441 E O2	8.3409	Adder	18.51
WEC	WEC	4.5603	Confirmed LTF	4.5603
CALDERWOOD	CALDERWOOD	0.0631	Confirmed LTF	0.0631
CBM-W2	CBM-W2	25.0942	Confirmed LTF	25.0942
NY	NY	1.4306	Confirmed LTF	1.4306
CBM-W1	CBM-W1	78.1875	Confirmed LTF	78.1875
TVA	TVA	1.6184	Confirmed LTF	1.6184
O-066	O-066	16.9546	Confirmed LTF	16.9546
CHEOAH	CHEOAH	0.0771	Confirmed LTF	0.0771
CBM-S1	CBM-S1	6.0407	Confirmed LTF	6.0407
G-007	G-007	2.6218	Confirmed LTF	2.6218
MADISON	MADISON	24.3210	Confirmed LTF	24.3210
MEC	MEC	16.0171	Confirmed LTF	16.0171
BLUEG	BLUEG	2.3071	Confirmed LTF	2.3071
TRIMBLE	TRIMBLE	0.7969	Confirmed LTF	0.7969
CATAWBA	CATAWBA	0.3619	Confirmed LTF	0.3619

13.5.5 Index 5

ID	FROM BUS#	FROM BUS	FROM BUS AREA	TO BUS#	TO BUS	TO BUS AREA	CKT ID	CONT NAME	Type	Rating MVA	PRE PROJECT LOADING %	POST PROJECT LOADING %	AC DC	MW IMPACT
96795131	275233	WILTON ;4M	CE	270644	WILTON ;	CE	1	COMED_P4_112-65-BT2-3_	breaker	1379.0	124.73	124.79	DC	31.51

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
274771	LINCOLN ;2U	3.8683	50/50	3.8683
274772	LINCOLN ;3U	3.8683	50/50	3.8683
274773	LINCOLN ;4U	3.8683	50/50	3.8683
274774	LINCOLN ;5U	3.8683	50/50	3.8683
274775	LINCOLN ;6U	3.8683	50/50	3.8683
274776	LINCOLN ;7U	3.8683	50/50	3.8683
274777	LINCOLN ;8U	3.8683	50/50	3.8683
274830	U3-021 1	6.4380	Adder	7.57
274831	U3-021 2	6.4380	Adder	7.57
274881	PILOT HIL;1E	20.3561	Adder	23.95
274890	CAYUG;1U E	17.3451	Adder	20.41
274891	CAYUG;2U E	17.3451	Adder	20.41
275149	KELLYCK ;1E	20.3561	Adder	23.95
276167	Z1-106 E2	1.3342	Adder	1.57
276168	Z1-106 E1	1.3341	Adder	1.57
276169	Z1-107 E	2.7309	Adder	3.21
276170	Z1-108 E	2.6251	Adder	3.09
290021	O50 E	20.4530	Adder	24.06
290051	GSG-6; E	11.1236	Adder	13.09
290108	LEEDK;1U E	25.7295	Adder	30.27
293061	N-015 E	16.7861	Adder	19.75
293644	O22 E1	10.8153	Adder	12.72
293645	O22 E2	20.9944	Adder	24.7
294392	P-010 E	21.3184	Adder	25.08
910542	X3-005 E	0.7727	Adder	0.91
915011	Y3-013 1	3.9461	Adder	4.64
915021	Y3-013 2	3.9461	Adder	4.64
915031	Y3-013 3	3.9461	Adder	4.64
918052	AA1-018 E OP	17.3542	Adder	20.42
920272	AA2-123 E	2.5799	Adder	3.04
924471	AB2-096	44.7083	Adder	52.6
926311	AC1-109 1	2.0186	Adder	2.37
926321	AC1-109 2	2.0186	Adder	2.37
926331	AC1-110 1	2.0052	Adder	2.36
926341	AC1-110 2	2.0052	Adder	2.36
926351	AC1-111 1	0.8063	Adder	0.95
926361	AC1-111 2	0.8063	Adder	0.95
926371	AC1-111 3	0.8063	Adder	0.95
926381	AC1-111 4	0.8063	Adder	0.95
926391	AC1-111 5	0.8063	Adder	0.95
926401	AC1-111 6	0.8063	Adder	0.95
927451	AC1-142A 1	4.4186	Adder	5.2

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
927461	AC1-142A 2	4.4186	Adder	5.2
930501	AB1-091 O1	80.9897	Adder	95.28
930741	AB1-122 1O1	76.8999	Adder	90.47
930751	AB1-122 2O1	77.8579	Adder	91.6
933411	AC2-154 C	2.7626	Adder	3.25
933412	AC2-154 E	4.5074	Adder	5.3
933431	AC2-156 C O1	1.0103	Adder	1.19
933432	AC2-156 E O1	1.6485	Adder	1.94
933911	AD1-013 C	1.9642	Adder	2.31
933912	AD1-013 E	3.1375	Adder	3.69
933931	AD1-016 C	0.9804	Adder	1.15
933932	AD1-016 E	1.5996	Adder	1.88
934101	AD1-039 1	7.5362	Adder	8.87
934111	AD1-039 2	7.6301	Adder	8.98
934431	AD1-067 C	0.1397	Adder	0.16
934432	AD1-067 E	0.5873	Adder	0.69
934701	AD1-098 C O1	7.3184	Adder	8.61
934702	AD1-098 E O1	5.3432	Adder	6.29
934721	AD1-100 C	25.3457	Adder	29.82
934722	AD1-100 E	118.2800	Adder	139.15
934871	AD1-116 C	1.0107	Adder	1.19
934872	AD1-116 E	1.6490	Adder	1.94
934971	AD1-129 C	0.9544	Adder	1.12
934972	AD1-129 E	0.6363	Adder	0.75
935001	AD1-133 C O1	23.5023	Adder	27.65
935002	AD1-133 E O1	15.6682	Adder	18.43
936291	AD2-038 C O1	2.4826	Adder	2.92
936292	AD2-038 E O1	16.6143	Adder	19.55
936371	AD2-047 C O1	4.9436	Adder	5.82
936372	AD2-047 E O1	24.1366	Adder	28.4
936461	AD2-060	2.9080	Adder	3.42
936511	AD2-066 C O1	8.9497	Adder	10.53
936512	AD2-066 E O1	5.9665	Adder	7.02
937001	AD2-134 C	2.9079	Adder	3.42
937002	AD2-134 E	12.0124	Adder	14.13
937401	AD2-194 1	8.2426	Adder	9.7
937411	AD2-194 2	8.2421	Adder	9.7
938511	AE1-070 1	9.6851	Adder	11.39
938521	AE1-070 2	8.8603	Adder	10.42
938851	AE1-113 C	8.4369	Adder	9.93
938852	AE1-113 E	29.9126	Adder	35.19
939321	AE1-163 C O1	6.2383	Adder	7.34
939322	AE1-163 E O1	38.3212	Adder	45.08
939351	AE1-166 C O1	12.5095	Adder	14.72
939352	AE1-166 E O1	11.5472	Adder	13.58
939401	AE1-172 C O1	6.9294	Adder	8.15
939402	AE1-172 E O1	32.5126	Adder	38.25
940101	AE1-252 C O1	13.9207	Adder	16.38
940102	AE1-252 E O1	9.2805	Adder	10.92
940752	AE2-062 E	0.1379	Adder	0.16
941131	AE2-107 C	7.7372	Adder	9.1
941132	AE2-107 E	5.1581	Adder	6.07

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
941551	AE2-152 C O1	14.4340	Adder	16.98
941552	AE2-152 E O1	9.6227	Adder	11.32
941561	AE2-153 C O1	5.2303	Adder	6.15
941562	AE2-153 E O1	24.4874	Adder	28.81
941731	AE2-173 O1	3.3326	Adder	3.92
942111	AE2-223 C	2.4629	Adder	2.9
942112	AE2-223 E	16.4823	Adder	19.39
942421	AE2-255 C O1	3.1958	Adder	3.76
942422	AE2-255 E O1	9.5874	Adder	11.28
942651	AE2-281 C O1	0.8912	Adder	1.05
942652	AE2-281 E O1	5.4745	Adder	6.44
942991	AE2-321 C	8.6313	Adder	10.15
942992	AE2-321 E	4.2513	Adder	5.0
943121	AE2-341 C	13.4892	Adder	15.87
943122	AE2-341 E	6.6239	Adder	7.79
943381	AF1-009 C	0.6331	Adder	0.74
943382	AF1-009 E	2.5323	Adder	2.98
943591	AF1-030 C O1	8.9705	Adder	10.55
943592	AF1-030 E O1	4.4383	Adder	5.22
943801	AF1-048 C	4.0348	Adder	4.75
943802	AF1-048 E	2.6899	Adder	3.16
944041	AF1-072	2.2734	Adder	2.67
944911	AF1-156 C	13.3730	Adder	15.73
944912	AF1-156 E	8.9153	Adder	10.49
945351	AF1-200 FTIR	329.4462	Merchant Transmission	329.4462
946661	AF1-330 C	2.1155	Adder	2.49
946662	AF1-330 E	0.4644	Adder	0.55
946671	AF1-331	2.5508	Adder	3.0
957021	AF2-003 C O2	3.6517	Adder	8.11
957022	AF2-003 E O2	17.0965	Adder	37.95
957331	AF2-027 C	1.3943	Adder	3.1
957332	AF2-027 E	2.0914	Adder	4.64
958011	AF2-095 C O2	10.3469	Adder	22.97
958012	AF2-095 E O2	4.8691	Adder	10.81
958021	AF2-096 C O2	19.9092	Adder	44.19
958022	AF2-096 E O2	9.4150	Adder	20.9
958481	AF2-142 C	6.3433	Adder	14.08
958482	AF2-142 E	4.2288	Adder	9.39
958491	AF2-143 C	6.0728	Adder	13.48
958492	AF2-143 E	4.0486	Adder	8.99
959341	AF2-225 C	4.2172	Adder	9.36
959342	AF2-225 E	5.8238	Adder	12.93
959351	AF2-226 C	1.4049	Adder	3.12
959352	AF2-226 E	2.1074	Adder	4.68
960281	AF2-319 C	1.4049	Adder	3.12
960282	AF2-319 E	2.1074	Adder	4.68
960381	AF2-329	3.7097	Adder	8.23
960581	AF2-349 C	12.2138	Adder	27.11
960582	AF2-349 E	8.1425	Adder	18.07
960591	AF2-350 C O2	4.6238	Adder	10.26
960592	AF2-350 E O2	3.0825	Adder	6.84
960601	AF2-351 C O2	0.6165	Adder	1.37

Bus #	Bus	Gendeliv MW Impact	Type	Full MW Impact
960602	AF2-351 E O2	0.9248	Adder	2.05
960721	AF2-363 C O2	3.3122	Adder	7.35
960722	AF2-363 E O2	2.2082	Adder	4.9
960731	AF2-364 C O2	3.4357	Adder	7.63
960732	AF2-364 E O2	2.2905	Adder	5.08
960751	AF2-366 C O2	3.9047	Adder	8.67
960752	AF2-366 E O2	2.6031	Adder	5.78
961501	AF2-441 C O2	5.6774	Adder	12.6
961502	AF2-441 E O2	8.5161	Adder	18.9
WEC	WEC	4.6573	Confirmed LTF	4.6573
CALDERWOOD	CALDERWOOD	0.0656	Confirmed LTF	0.0656
CBM-W2	CBM-W2	25.6101	Confirmed LTF	25.6101
NY	NY	1.4616	Confirmed LTF	1.4616
CBM-W1	CBM-W1	79.8388	Confirmed LTF	79.8388
TVA	TVA	1.6492	Confirmed LTF	1.6492
O-066	O-066	17.3242	Confirmed LTF	17.3242
CHEOAH	CHEOAH	0.0801	Confirmed LTF	0.0801
CBM-S1	CBM-S1	6.1514	Confirmed LTF	6.1514
G-007	G-007	2.6780	Confirmed LTF	2.6780
MADISON	MADISON	24.8371	Confirmed LTF	24.8371
MEC	MEC	16.3540	Confirmed LTF	16.3540
BLUEG	BLUEG	2.3592	Confirmed LTF	2.3592
TRIMBLE	TRIMBLE	0.8147	Confirmed LTF	0.8147
CATAWBA	CATAWBA	0.3703	Confirmed LTF	0.3703

13.6 Contingency Descriptions - Secondary POI

Contingency Name	Contingency Definition
COMED_P1-2_695_B2	CONTINGENCY 'COMED_P1-2_695_B2' OPEN BRANCH FROM BUS 243206 TO BUS 270644 CKT 1 / 243206 05DUMONT 765 270644 WILTO; 765 1 END
COMED_P4_112-65-BT2-3__	CONTINGENCY 'COMED_P4_112-65-BT2-3__' TRIP BRANCH FROM BUS 270644 TO BUS 270607 CKT 1 / WILTO; 765 COLLI; 765 TRIP BRANCH FROM BUS 275232 TO BUS 270644 CKT 1 / WILTO;3M 345 WILTO; 765 TRIP BRANCH FROM BUS 275232 TO BUS 270926 CKT 1 / WILTO;3M 345 WILTO; B 345 TRIP BRANCH FROM BUS 275232 TO BUS 275332 CKT 1 / WILTO;3M 345 WILTO;3C 33 END

Contingency Name	Contingency Definition
COMED_P4_112-65-BT5-6__	CONTINGENCY 'COMED_P4_112-65-BT5-6__' TRIP BRANCH FROM BUS 270644 TO BUS 270607 CKT 1 / WILTO; 765 COLLI; 765 TRIP BRANCH FROM BUS 275233 TO BUS 270644 CKT 1 / WILTO;4M 345 WILTO; 765 TRIP BRANCH FROM BUS 275233 TO BUS 270927 CKT 1 / WILTO;4M 345 WILTO; R 345 TRIP BRANCH FROM BUS 275233 TO BUS 275333 CKT 1 / WILTO;4M 345 WILTO;4C 33 END

14 Affected Systems

14.1 MISO

MISO Impacts to be determined during later study phases (as applicable).