



**Generation Interconnection
Combined Feasibility / Impact Study Report
for
Queue Project AG1-558
BUCKNER 34.5 KV
13.3 MW Capacity / 20 MW Energy**

January 2021

Table of Contents

| | | |
|------|--|----|
| 1 | Introduction..... | 4 |
| 2 | Preface..... | 4 |
| 3 | General..... | 5 |
| 4 | Point of Interconnection..... | 6 |
| 5 | Cost Summary..... | 6 |
| 6 | Transmission Owner Scope of Work..... | 7 |
| 7 | Transmission Owner Analysis..... | 8 |
| 7.1 | Power Flow Analysis..... | 8 |
| 8 | Interconnection Customer Requirements..... | 8 |
| 8.1 | System Protection..... | 8 |
| 8.2 | Compliance Issues and Interconnection Customer Requirements..... | 9 |
| 8.3 | Power Factor Requirements..... | 9 |
| 9 | Revenue Metering and SCADA Requirements..... | 9 |
| 9.1 | PJM Requirements..... | 9 |
| 9.2 | Meteorological Data Reporting Requirements..... | 9 |
| 9.3 | Interconnected Transmission Owner Requirements..... | 10 |
| 10 | Summer Peak - Load Flow Analysis..... | 11 |
| 10.1 | Generation Deliverability..... | 11 |
| 10.2 | Multiple Facility Contingency..... | 11 |
| 10.3 | Contribution to Previously Identified Overloads..... | 11 |
| 10.4 | Potential Congestion due to Local Energy Deliverability..... | 11 |
| 10.5 | System Reinforcements - Summer Peak Load Flow - Primary POI..... | 12 |
| 10.6 | Flow Gate Details..... | 13 |
| 10.7 | Queue Dependencies..... | 14 |
| 10.8 | Contingency Descriptions..... | 15 |
| 11 | Short Circuit Analysis..... | 16 |
| 11.1 | System Reinforcements - Short Circuit..... | 16 |
| 12 | Affected Systems..... | 17 |
| 12.1 | TVA..... | 17 |
| 12.2 | Duke Energy Progress..... | 17 |
| 13 | Attachment 1: One Line Diagram..... | 18 |

1 Introduction

This Feasibility Study has been prepared in accordance with the PJM Open Access Transmission Tariff, 36.2, as well as the Feasibility Study Agreement between the Interconnection Customer (IC), and PJM Interconnection, LLC (PJM), Transmission Provider (TP). The Interconnected Transmission Owner (ITO) is Dominion.

2 Preface

The intent of the feasibility study is to determine a plan, with ballpark cost and construction time estimates, to connect the subject generation to the PJM network at a location specified by the Interconnection Customer. The Interconnection Customer may request the interconnection of generation as a capacity resource or as an energy-only resource. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: (1) Direct Connections, which are new facilities and/or facilities upgrades needed to connect the generator to the PJM network, and (2) Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system.

In some instances a generator interconnection may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection, may also contribute to the need for the same network reinforcement. Cost allocation rules for network upgrades can be found in PJM Manual 14A, Attachment B. The possibility of sharing the reinforcement costs with other projects may be identified in the feasibility study, but the actual allocation will be deferred until the impact study is performed.

The Interconnection Customer seeking to interconnect a wind or solar generation facility shall maintain meteorological data facilities as well as provide that meteorological data which is required per Schedule H to the Interconnection Service Agreement and Section 8 of Manual 14D.

The Feasibility Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer is responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

3 General

The Interconnection Customer (IC), has proposed a Solar; Storage generating facility located in Louisa County, Virginia. The installed facilities will have a total capability of 20 MW with 13.3 MW of this output being recognized by PJM as Capacity. The proposed in-service date for this project is October 21, 2022. This study does not imply a TO commitment to this in-service date.

| | |
|----------------------------|-----------------|
| Queue Number | AG1-558 |
| Project Name | BUCKNER 34.5 KV |
| State | Virginia |
| County | Louisa |
| Transmission Owner | Dominion |
| MFO | 20 |
| MWE | 20 |
| MWC | 13.3 |
| Fuel | Solar; Storage |
| Basecase Study Year | 2024 |

Any new service customers who can feasibly be commercially operable prior to June 1st of the basecase study year are required to request interim deliverability analysis.

4 Point of Interconnection

AG1-558 “Buckner 34.5 kV” will interconnect within the Old Dominion Electric Cooperative (ODEC) system which interconnects with the Dominion transmission system at the St. Johns DP 115 kV substation.

Attachment 1 shows a one-line diagram of the proposed interconnection facilities.

5 Cost Summary

The costs associated with interconnecting AG1-558 to the Old Dominion Electric Cooperative (ODEC) system will be documented in the two-party Interconnection Agreement between the IC and Old Dominion Electric Cooperative (ODEC).

The AG1-558 project will be responsible for the following costs:

| Description | Total Cost |
|---|-------------------------|
| Total Physical Interconnection Costs | \$ To be provided in IA |
| Total System Network Upgrade Costs | \$0 |
| Total Costs | \$ To be provided in IA |

This cost excludes a Federal Income Tax Gross Up charges. This tax may or may not be charged based on whether this project meets the eligibility requirements of IRS Notice 2016-36, 2016-25 I.R.B. (6/20/2016). If at a future date it is determined that the Federal Income Tax Gross charge is required, the Transmission Owner shall be reimbursed by the Interconnection Customer for such taxes.

Cost allocations for any System Upgrades will be provided in the System Impact Study Report.

6 Transmission Owner Scope of Work

Remote Terminal Work: During the Facilities Study, ITO's System Protection Engineering Department will review transmission line protection as well as anti-islanding required to accommodate the new generation and interconnection substation. System Protection Engineering will determine the minimal acceptable protection requirements to reliably interconnect the proposed generating facility with the transmission system. The review is based on maintaining system reliability by reviewing ITO's protection requirements with the known transmission system configuration which includes generating facilities in the area. This review may determine that transmission line protection and communication upgrades are required at remote substations.

7 Transmission Owner Analysis

Dominion assessed the impact of the proposed project for compliance with NERC Reliability Criteria on the Dominion Transmission System. The system was assessed using the summer 2024 AG1 case provided to Dominion by PJM.

When performing a generation analysis, Dominion’s main analysis includes load flow study results following a single contingency event for both normal and stressed system conditions. Dominion Criteria considers a transmission facility overloaded if it exceeds 94% of its emergency rating under normal and stressed system conditions. A full listing of Dominion’s Planning Criteria and interconnection requirements can be found in the Company’s Facility Connection Requirements which are publicly available at: <http://www.dominionenergy.com>.

The results of these studies evaluate the system under a limited set of operating conditions and do not guarantee the full delivery of the capacity and associated energy of this proposed generation facility under all operating conditions. NERC Planning and Operating Reliability Criteria allow for the re-dispatch of generating units to resolve projected and actual deficiencies in real time and planning studies. Specifically, in Planning Studies, NERC Planning Event 3 and 6 Contingency Conditions (Loss of generator, transmission circuit, transformer, shunt device, or Single Pole of a DC line followed by the loss of a generator, transmission circuit, transformer, shunt device or single pole of a DC line) allow for re-dispatch of generating units to resolve potential reliability deficiencies. For Dominion Planning Criteria the re-dispatch of generating units for these contingency conditions is allowed as long as the projected loading does not exceed 100% of a facility Load Dump Rating.

7.1 Power Flow Analysis

PJM performed a power flow analysis of the transmission system using a 2024 summer peak load flow model and the results were verified by Dominion. Additionally, Dominion performed an analysis of its transmission system and no further deficiencies were identified.

8 Interconnection Customer Requirements

8.1 System Protection

The IC must design its Customer Facilities in accordance with all applicable standards, including the standards in Dominion’s “Dominion Energy Electric Transmission Generator Interconnection Requirements” documented in Dominion’s Facility Interconnection Requirements “Exhibit C” located at: <https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>. Preliminary Protection requirements will be provided as part of the Facilities Study. Detailed Protection Requirements will be provided once the project enters the construction phase.

8.2 Compliance Issues and Interconnection Customer Requirements

The proposed Customer Facilities must be designed in accordance with Dominion’s “Dominion’s Facility Interconnection Requirements” document located at: <https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>. In particular, the IC is responsible for the following:

1. The purchase and installation of a fully rated protection device (circuit breaker, circuit switcher, fuse) to protect the IC’s GSU transformer(s).
2. The purchase and installation of the minimum required Dominion generation interconnection relaying and control facilities as described in the System Protection section noted above. This includes over/under voltage protection, over/under frequency protection, and zero sequence voltage protection relays.
3. The purchase and installation of supervisory control and data acquisition (“SCADA”) equipment to provide information in a compatible format to the Dominion Transmission System Control Center.
4. Compliance with the Dominion and PJM generator power factor and voltage control requirements.

The GSU(s) associated with the IC queue request shall meet the grounding requirements as noted in Dominion’s “Dominion’s Facility Interconnection Requirements” document located at: <https://www.dominionenergy.com/company/moving-energy/electric-transmission-access>.

The IC will also be required to meet all PJM, SERC, and NERC reliability criteria and operating procedures for standards compliance. For example, the IC will need to properly locate and report the over and under voltage and over and under frequency system protection elements for its units as well as the submission of the generator model and protection data required to satisfy the PJM and SERC audits. Failure to comply with these requirements may result in a disconnection of service if the violation is found to compromise the reliability of the Dominion system.

8.3 Power Factor Requirements

The IC shall design its non-synchronous Customer Facility with the ability to maintain a power factor of at least 0.95 leading (absorbing VARs) to 0.95 lagging (supplying VARs) measured at the high-side of the facility substation transformer(s) connected to the Dominion transmission system.

9 Revenue Metering and SCADA Requirements

9.1 PJM Requirements

The Interconnection Customer will be required to install equipment necessary to provide Revenue Metering (KWH, KVARH) and real time data (KW, KVAR) for IC's generating Resource. See PJM Manuals M-01 and M-14D, and PJM Tariff Section 8 of Attachment O.

9.2 Meteorological Data Reporting Requirements

The solar generation facility shall provide the Transmission Provider with site-specific meteorological data including:

- Back Panel temperature (Fahrenheit) - (Required for plants with Maximum Facility Output of 3 MW or higher)
- Irradiance (Watts/meter²) - (Required for plants with Maximum Facility Output of 3 MW or higher)
- Ambient air temperature (Fahrenheit) - (Accepted, not required)
- Wind speed (meters/second) - (Accepted, not required)
- Wind direction (decimal degrees from true north) - (Accepted, not required)

9.3 Interconnected Transmission Owner Requirements

The IC will be required to comply with all Interconnected Transmission Owner's revenue metering requirements for generation interconnection customers located at the following link:

<http://www.pjm.com/planning/design-engineering/to-tech-standards/>

10 Summer Peak - Load Flow Analysis

The Queue Project AG1-558 was evaluated as a 20.0 MW (Capacity 13.3 MW) injection at the Greenwood DP 115 kV substation in the Dominion area. Project AG1-558 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AG1-558 was studied with a commercial probability of 100.0 %. Potential network impacts were as follows:

10.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

10.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

None

10.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

10.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

| ID | FROM BUS# | FROM BUS | kV | FROM BUS AREA | TO BUS# | TO BUS | kV | TO BUS AREA | CK T ID | CONT NAME | Type | Rating MVA | PRE PROJE CT LOADIN G % | POST PROJE CT LOADIN G % | AC D C | MW IMPAC T |
|-----------|-----------|----------|-------|---------------|---------|----------|-------|-------------|---------|----------------|-----------|---------------|-------------------------|--------------------------|--------|------------|
| 168896093 | 314217 | 3ELMONT | 115.0 | DVP | 314237 | 3NRTHWST | 115.0 | DVP | 1 | DVP_P1-2: LN47 | operation | 220.899993896 | 120.1 | 123.55 | DC | 7.62 |

10.5 System Reinforcements - Summer Peak Load Flow - Primary POI

None.

10.6 Flow Gate Details

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

10.7 Queue Dependencies

The Queue Projects below are listed in one or more indices for the overloads identified in your report. These projects contribute to the loading of the overloaded facilities identified in your report. The percent overload of a facility and cost allocation you may have towards a particular reinforcement could vary depending on the action of these earlier projects. The status of each project at the time of the analysis is presented in the table. This list may change as earlier projects withdraw or modify their requests.

None

10.8 Contingency Descriptions

| Contingency Name | Contingency Definition |
|------------------------|--|
| DVP_P1-2: LN 47 | CONTINGENCY 'DVP_P1-2: LN 47' OPEN BRANCH FROM BUS 314136 TO BUS 314151 CKT 1 /* 3FREDBRG 115.00 - 3SLABTWN 115.00 OPEN BRANCH FROM BUS 314151 TO BUS 314153 CKT 1 /* 3SLABTWN 115.00 - 3WOODPCK 115.00 OPEN BRANCH FROM BUS 314152 TO BUS 314153 CKT 1 /* 3S JOHNS 115.00 - 3WOODPCK 115.00 OPEN BRANCH FROM BUS 314152 TO BUS 314216 CKT 1 /* 3S JOHNS 115.00 - 3PINWOOD 115.00 OPEN BUS 314151 /* ISLAND: 3SLABTWN 115.00 OPEN BUS 314152 /* ISLAND: 3S JOHNS 115.00 OPEN BUS 314153 /* ISLAND: 3WOODPCK 115.00 END |

11 Short Circuit Analysis

The following Breakers are overdutied:

None.

11.1 System Reinforcements - Short Circuit

None.

12 Light Load Analysis

Not Required.

13 Stability Analysis

Will be performed in the Facilities Study phase.

14 Affected Systems

14.1 TVA

TVA Impacts to be determined during later study phases (as applicable).

14.2 Duke Energy Progress

Duke Energy Progress Impacts to be determined during later study phases (as applicable).

15 Attachment 1: One Line Diagram

