



Generation Interconnections

Network Impacts

Potential network impacts for the injection of 168 MW into the Essex and NJT Meadows 230 kV system was evaluated for summer peak conditions in 2005.

Normal System

- No problems identified.

Multiple Facility Contingency (MAAC Criteria IIC)

- No problems identified.

Generator Deliverability

- No identified problems.

Short Circuit Analysis

- No identified problems.

System Reinforcements

- No identified reinforcements.