

Network Impacts

Potential network impacts for the injection of 12 MW into the existing Linden 230 kV system was evaluated for summer peak conditions in 2005.

Normal System

- No identified problems.

Multiple Facility Contingency (MAAC Criteria IIC)

- No identified problems.

Generator Deliverability

- No identified problems.

Short Circuit Analysis

- No identified problems.

System Reinforcements

- None