

**#P09 - Kerr Dam 115 kV (91 MW)**  
**Generation Interconnection**

**Network Impacts**

The #P09 project was studied as an injection of 91MW into Kerr Dam 115kV substation. Project #P09 was evaluated for compliance with reliability criteria for summer peak conditions in 2010. Potential network impacts were as follows:

**Generator Deliverability**

No problem identified.

**Multiple Facility Contingency**

No problem identified.

**Contribution to Previously Identified Overloads**

None

**New System Reinforcements**

None.

**Contribution to Previously Identified System Reinforcements**

None.

**Short Circuit**

No problem identified.