

#P62 – Gavin #2
Generation Interconnection

This analysis was completed to assess the reliability impact for a new generator interconnecting to the PJM system as a capacity resource.

Network Impacts

The #P62 project was studied as a 20 MW capacity increase to unit #1 at the Gavin generating station. Project #P62 was evaluated for compliance with reliability criteria for summer peak conditions in 2010. Potential network impacts were as follows:

Generator Deliverability

No problems were identified

Multiple Facility Contingency

No problems were identified

Short Circuit

Not required as there is no impedance change.

Contribution to Previously Identified Overloads

None

New System Reinforcements

None

Contribution to Previously Identified System Reinforcements

None