

**#R86 – Tanners Creek #2 138kV
Generation Interconnection**

This analysis was completed to assess the reliability impact for a new generator interconnecting to the PJM system as a capacity resource.

Network Impacts

The #R86 project was studied as a capacity increase of 5 MW at the Tanners Creek 138 kV substation. Project #R86 was evaluated for compliance with reliability criteria for summer peak conditions in 2007 to determine if Capacity Interconnection Rights can be granted. Potential network impacts were as follows:

Generator Deliverability

No problems identified

Multiple Facility Contingency

No problems identified

Contribution to Previously Identified Overloads

No problems were identified

Short Circuit

Not required, since there are no changes to the generating unit electrical characteristics.

New System Reinforcements

None

Contribution to Previously Identified System Reinforcements

None

.