

#S28– Blue Mound **Generation Interconnection**

This analysis was completed to assess the reliability impact for a new wind generator interconnecting to the PJM system as a capacity resource.

Network Impacts

The Queue S28 project was studied as a 198 MW (40 MW of capacity) injection into the Blue Mound 345kV Substation in ComEd territory. Project S27 was evaluated for compliance with reliability criteria for summer peak conditions in 2012. Potential network impacts were as follows:

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

No Problems were identified.

Multiple Facility Contingency

(Double Circuit Tower Line contingencies only for the full energy output. Stuck breaker and bus fault contingencies will be performed for the Impact Study)

No Problems were identified

Short Circuit

Will be conducted during System Impact Study.

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. “Network Impacts”, identified for earlier generation or transmission interconnection projects in the PJM Queue)

None identified

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. “Network Impacts”, initially caused by the addition of this project generation)

None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None

Potential Issues

Impacts on the MISO member transmission systems are not included in this analysis, but they will be included in the Impact Study, which may reveal upgrades needed in the MISO system not identified in this Feasibility Study.

Delivery of Energy Portion of Interconnection Request

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

No problems were identified.