

#S41 Eldred – Reed 10.5 MW
Generator Interconnection

This analysis was completed to assess the reliability impact for a new generator interconnecting to the PJM System as a Capacity Resource.

Network Impacts

The Queue S41 project was studied as a 10.5 MW injection into the Eldred to Reed 69 kV line. The project was evaluated for compliance with reliability criteria for summer peak conditions in 2012. Potential network impacts were as follows:

NETWORK IMPACTS

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

No Problems were identified

Multiple Facility Contingency

(Double Circuit Tower Line contingencies only for the full energy output. Stuck breaker and bus fault contingencies will be performed for the Impact Study)

No problems were identified.

Short Circuit Analysis

To be completed during the Queue S41 Impact Study.

Stability Analysis

Not required because of generator size.

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. “Network Impacts”, identified for earlier generation or transmission interconnection projects in the PJM Queue)

No problems were identified

NETWORK UPGRADE REQUIREMENTS

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. “Network Impacts”, initially caused by the addition of this project generation)

None identified.

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None identified.