

***PJM Generator Interconnection
T104 Gosport 115-kV
Feasibility Study***

January 2008
DMS # 466774 v1

Network Impacts

The project was studied as a 20 MW energy injection at the Gosport 115 kV facility. The project was evaluated for compliance with reliability criteria for summer peak conditions in 2012. Potential network impacts were as follows:

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

No problems were identified.

Multiple Facility Contingency

(Double Circuit Tower Line contingencies only for the full energy output. Stuck breaker and bus fault contingencies will be performed for the Impact Study)

No problems were identified.

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

No problems were identified.

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. "Network Impacts", initially caused by the addition of this project generation)

None.

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None.

Short Circuit

Not Required.

Stability

To be performed during the System Impact Study.