

U1-071 C. W. Bill Young Lock and Dam **Generation Interconnection**

General

The Interconnection Customer (IC), has proposed a 15 MW hydro power generating facility to be located at the C. W. Bill Young Lock and Dam in Oakmont, Allegheny County, Pennsylvania. U1-071 was studied as a 15 MW injection into the Allegheny Power (AP) 25kV system at Harwick. The project was evaluated for compliance with reliability criteria for summer peak conditions in 2012. The planned in-service date is June 1, 2015.

Point of Interconnection

U1-071 will interconnect with the Allegheny Power (AP) 25kV distribution system at the future All Dam 3 25kV switching station on the Harwick–Gulf Research line.

Direct Connection Requirements

Transmission Owner Scope of Direct Connection Work

The Transmission Owner's scope of work for the direct connection facilities includes constructing the new All Dam 3 25kV switching station. The Harwick-Gulf Research 25kV line shall be looped into this new switching station near Acme Junction.

Major equipment in the new All Dam 3 station will include: three (3) 25kV bay structures, three (3) 25kV circuit breakers, one (1) 25kV vertical break air switch, one (1) 25kV potential transformer and metering current transformers. The station will also include a control building, which will house all protective relaying, metering and SCADA RTU communications equipment required to accommodate the electrical facilities. Site preparation including grading and an access road is included in the estimate.

The estimated cost to perform this work is **\$1,530,000** in 2015 dollars. The estimated time to provide for the interconnection of this project is **24 months** after the receipt of a signed Interconnection Service Agreement and Construction Service Agreement.

Interconnection Customer Scope of Direct Connection Work

The Interconnection Customer (IC) has assumed full responsibility for the design and construction of all facilities associated with the U1-071 generating station and the 25kV direct connection line on the IC side of the POI. The IC will interconnect U1-071 with the AP system by constructing a customer-owned 25kV circuit (approximately 400' in length) from the generating station site to AP's All Dam 3 switching station. Route selection, line design, right-of-way acquisition and construction of such lines will be entirely the responsibility of the IC. Cost estimates do not include construction of that line. It is assumed that the ICs step up transformer will conform to the AP standard of delta on the low side and grounded wye on the high side. It is further assumed that a fiber optic interface will be used for the protection channel between the AP and developer's stations.

The IC will be required to install metering and telemetry equipment to provide revenue metering and real-time telemetry data to PJM. The requirements for this equipment are listed in Appendix 2, Section 8 of Attachment O to the PJM Tariff, as well as PJM Manuals 01 and 14D. Protective relaying and metering design and installation must comply with the Allegheny Power Applicable Standards.

Network Impacts

Generator Deliverability

*(Single or N-1 contingencies for the **Capacity** portion only of the interconnection)*

None

Multiple Facility Contingency

*(Double Circuit Tower Line contingencies only for the **Full energy** output. Stuck breaker and bus fault contingencies will be performed for the System Impact Study)*

None

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

Short Circuit

No breakers were identified as being over their maximum interrupting rating.

Listed below are the positive and zero sequence source equivalent impedance at the proposed All Dam 3 site with the GSU and generators OPEN.

Positive: (0.05502+j0.24421)

Zero: (0.06131+j0.52009)

While we can't mandate that our personnel install protective relaying and communications equipment at the generator site, Allegheny Power has responsibility for designing the protection scheme and providing specifications for all relays to be employed on the interconnection breaker terminal at the generation site to assure that the protective relaying equipment will be compatible with that installed on the interconnection breaker terminal at the new switching station. The relaying package will likely include both primary and backup protection. Allegheny Power is also responsible for testing and calibrating all relays and performing all tests to assure that relaying at the generator site is properly installed and functional.

The estimated total cost of this engineering and field test effort is **\$5,000 in 2010 dollars**.

Note: Purchase and installation of protective relaying and associated equipment at the generation site is not included in this scope of work. This phase of work is the responsibility of the customer.

The estimated cost for Allegheny Power Controls Engineering to complete a coordination review of the area, develop new relay settings, and implement the required changes is approximately **\$5,000 in 2010 dollars**.

Steady-State Voltage Requirements

Will be performed during the Queue U1-071 System Impact Study.

Stability and Reactive Power Requirements

Will be performed during the Queue U1-071 System Impact Study.

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. “Network Impacts”, initially caused by the addition of this project generation)

None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the System Impact Study)

None

Other Supporting Facility Charge

The Other Supporting Facilities Charges may include non-transmission facilities directly assigned and/or a general (rolled-in) facilities charge. The guidelines apply to all wholesale customers and all generators selling into or through the PJM Market, regardless of capacity, not connected directly to the AP Transmission System.

The Other Supporting Facilities Charge for the U1-071 generator interconnection project has been estimated to be **\$8,100/month in 2008 dollars**. The estimate is based on an average (or rolled-in) rate for West Penn’s sub-transmission system, which may or may not reflect the charge determined under a direct assignment methodology for radial facilities.