

This study was performed by MISO  
prior to ATSI integration with PJM.

MISO Project Number	J127	County	Wood
Point of Interconnection	ATSI Lemoyne substation	State	OH
Summer Net Output (MW)	40	Control Area	FE
RESULTS	DPP		

Summer Peak

Limiting Element	Contingency	DF (%)	Rating (MVA)	Overload (%)	FCITC (MW)
Lakeview - Ottawa 138kV ckt1	Beaver - Davis-Besse 345kV ckt1	6.4	339.0	106.7	-310.3
Greenfield - Lakeview 138kV ckt1	Beaver - Davis-Besse 345kV ckt1	6.4	243.0	105.2	-156.7

\*Constraints shown have a distribution factor above 5%. N/A indicates no constraints have been found based on the scope of the Feasibility Study.