

## W3-021 Jackson's Ferry-Peak Creek (Atlantic) 138kV

### Generation Interconnection

#### Network Impacts

Queue project W3-021 was studied as a(n) 70.0 MW (9.1 MW of which was Capacity) injection into AEP's system at the 50.0% tap between Jacksons Ferry and Peak Creek 138.0 kV line. Project W3-020 was evaluated for compliance with reliability criteria for summer peak conditions in 2014.

#### Generator Deliverability

*(Single or N-1 contingencies for the Capacity portion only of the interconnection)*

No problems identified

#### Multiple Facility Contingency

*(Double Circuit Tower Line, Line with Failed Breaker and Bus Fault contingencies for the full energy output)*

No problems identified

#### Short Circuit

*(Summary form of Cost allocation for breakers will be inserted here if any)*

No problems identified

#### System Reinforcements

None

#### Energy Portion of Interconnection Request

*(PJM also studied the delivery of the energy portion of the surrounding generation. Any potential problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Transmission Interconnection request.*

*Note: Only the most severely overloaded conditions are listed. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which analyzes all overload conditions associated with the overloaded element(s) identified. As a result of the aggregate energy resources in the area, the following violations were identified.)*

No problems identified.