

***PJM Generator Interconnection Request
Queue W3-041
Mt. Holly (Springfield Solar) 26kV
Feasibility/Impact Study Report***

**October 2012
#630458
Version 3**

W3-041 Mt. Holly (Springfield Solar) 26kV

Feasibility/Impact Study

General

Alethea CleanTech Advisors has proposed installing a 10 MW AC solar project on property located along Juliustown Road, Springfield Township, Burlington County, New Jersey. The project will consist of approximately 51,000, Ying Li, 235 KW Crystalline panels. The project will use 1MW Siemens inverters. The capacity evaluation is based upon 3.8 MW. The commercial operation date is December 31, 2011.

The intent of the Feasibility/Impact study is to determine system reinforcements and associated costs and construction time estimates required to facilitate the addition of the new generating plant to the transmission system. The reinforcements include the direct connection of the generator to the system and any network upgrades necessary to maintain the reliability of the transmission system.

Direct Connection

The interconnection will consist of a single 26-kV Line connection to M-195 which is currently an idle circuit from Mount Holly Substation. The line will be extended north on Route 206, then east on Juliustown Road to the project site. The total interconnection cost of \$1,457,442 is based on the most efficient possible route to the existing line, 26-kV infrastructure and is detailed as follows:

The developer will need to provide either a 26.4 kV solid bus or metal-clad switchgear station, with a circuit breaker, on the site for interconnection.

<u>Project Item</u>	<u>26-Kv Single Line</u>
Inside Plant	
Line Position/Feeder Row	\$0
Relay Protection	-
Manholes/Conduit	-
Other/Misc.	-
Sub Total	\$0
Outside Plant	
Overhead Line	\$ 1,382,143.00
Underground Line	-
Manholes/Conduit	-
Other/Misc.	-
Sub Total	\$ 1,382,143.00
Metering/Monitoring	
Revenue	
Metering/Telemetry/SCADA	\$75,300
Feeder Metering	\$0
Other/Misc.	-
Sub Total	\$75,300
Total Cost	\$1,457,443
Acceptable Generation level	Up To 10 MW

The cost is exclusive of work required to be performed by the developer as specified in PSE&G's Information & Requirements for Electric Service Handbook. This work includes, but may not be limited to, the following:

- Developer will adhere to specifications detailed in the PSE&G Information and Requirements for electric service handbook
- Developer is responsible for all trenching and the installation of conduits and manholes as normally required and specified by PSE&G
- Developer must obtain all permits and easements required to install the interconnection facilities
- Developer must provide access for the installation, maintenance and operation of all service equipment

It is anticipated that material procurement and construction will require 5-6 months from the date of project approval and authorization.

December 31, 2012

ISA is fully executed.

February 1, 2013

Developer submits preliminary site plan, 26-kV switchgear one-line diagram and equipment specifications for approval.

March 1, 2013

- PSE&G provides comments on project lay-out and design.
- CSA is fully executed and authorization is received to proceed with construction.
- Long lead time construction material is placed on order.
- First quarterly pre bill is due.

June 1, 2013

Second quarterly pre bill is due.

June 15, 2013

Developer submits final site plan, 26-kV switchgear one-line diagram and equipment specifications for approval.

July 1, 2013

PSE&G commences line construction.

July 15, 2013

- PSE&G provides final comments and approval of 26-kV switchgear lay-out and design.
- Developer begins construction based on approved design.

September 1, 2013

Third quarterly pre bill is due.

November 1, 2013

Final payment is due.

November 15, 2013

Switchgear inspection and approval by PSE&G.


December 3, 2013

Completion of interconnection work and service cut-in.

Notes:

- 1) Customer will abide by PSE&G Information and Requirements for electric service hand book
- 2) Customer is responsible to provide trench, conduit and manholes were applicable
- 3) Customer is responsible to provide access and easements
- 4) Customer is responsible to provide permits and associated costs.
- 5) Electric service route was based on most efficient route
- 6) Material procurement will be six months from project approval/authorization

Figure #1



Network Impacts

Queue project W3-041 was studied as a(n) 10.0 MW (3.8 MW of which was Capacity) injection into PSEG's system at the Lumberton 230kV substation. The project was studied on a combined feasibility-impact basis which utilizes an AC analysis, and incorporates all contingency types. Project W3-041 was evaluated for compliance with reliability criteria for summer peak conditions in 2015. Potential network impacts were as follows:

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

No problems identified

Multiple Facility Contingency

(Double Circuit Tower Line, Line with Failed Breaker and Bus Fault contingencies for the full energy output)

No problems identified.

Short Circuit

(Summary form of Cost allocation for breakers will be inserted here if any)

No problems identified

Stability

Not required because the project is less than 30 MW.

System Reinforcements

None

Energy Portion of Interconnection Request

(PJM also studied the delivery of the energy portion of the surrounding generation. Any potential problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which analyzes all overload conditions associated with the overloaded element(s) identified. As a result of the aggregate energy resources in the area, the following violations were identified.)

No problems identified.