

***Generation Interconnection
Combined
Feasibility/System Impact Study Report***

For

***PJM Generation Interconnection Request
Queue Position X3-070***

Reybold 138kV

February 2012

Preface

The intent of the Combined Feasibility/ System Impact Study is to determine a plan, with approximate cost and construction time estimates, to connect the subject generation interconnection project to the PJM network at a location specified by the Interconnection Customer. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system. All facilities required for interconnection of a generation interconnection project must be designed to meet the technical specifications (on PJM web site) for the appropriate transmission owner.

In some instances an Interconnection Customer may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection or merchant transmission upgrade, may also contribute to the need for the same network reinforcement. The possibility of sharing the reinforcement costs with other projects may be identified in the Feasibility Study, but the actual allocation will be deferred until the System Impact Study is performed.

Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer may be responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

General

PBF Power Marketing, LLC, the Interconnection Customer (IC), has proposed a 2 MWE (2 MWC) increase to Unit 3 at their existing facility located at the Delaware City Refining Company in Delaware City, Delaware. PJM studied X3-070 as a 2 MW injection into the Delmarva Power and Light system at the Reybold 138kV substation and evaluated the project for compliance with reliability criteria for summer peak conditions in 2015.

Point of Interconnection

X3-070 will interconnect with the Delmarva Power and Light (DPL) system through the existing Point of Interconnection (see Attachment 1).

Direct Connection Requirements

Transmission Owner (DPL) Scope of Direct Connection Work

The DPL scope of work and estimated costs for the direct connection facilities is as follows:

No direct connection work is required.

Interconnection Customer Scope of Direct Connection Work

The Interconnection Customer (IC) assumes full responsibility for the design and construction of all facilities associated with the X3-070 generating facility on the IC side of the Point of Interconnection.

The IC will be required to install metering and telemetry equipment to provide revenue metering and real-time telemetry data to PJM. The requirements for this equipment are listed in Appendix 2, Section 8 of Attachment O to the PJM Tariff, as well as PJM Manuals 01 and 14D.

Transmission Network Impacts

Potential transmission network impacts are as follows:

Generator Deliverability

*(Single or N-1 contingencies for the **Capacity** portion only of the interconnection)*

None

Multiple Facility Contingency

*(Double Circuit Tower Line, Line with Failed Breaker and, Bus Fault contingencies for the **Full** energy output.*

None

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

Short Circuit

None

Stability Analysis

Not required due to project size.

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. "Network Impacts," initially caused by the addition of this project's generation)

None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project.

None

Other Charges

DPL reserves the right to charge the Interconnection Customer operation and maintenance expenses to maintain the Inter Connection Customer attachment facilities, including metering and telecommunications facilities, owned by DPL.

Potential Congestion due to Local Energy Deliverability

(PJM also studied the delivery of the energy portion of the surrounding generation. Any potential problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with Network Upgrades to eliminate the operational restriction at their discretion by submitting a Transmission Interconnection Request. Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full deliverability for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which analyzes all overload conditions associated with the identified overloaded element(s). As a result of the aggregate energy resources in the area, the following violations were identified:

These are *not* required reliability upgrades.

None

Attachment 1

