

X4-016 Bayonne (Bayonne Cogen) 138kV

Generation Interconnection

Network Impacts

The Queue Project #X4-016 was studied as a(n) 10.0MW(Capacity10.0MW) injection at Co-Gen TE 138kV substation in the PSEG area. Project #X4-016 was evaluated for compliance with reliability criteria for summer peak conditions in 2015.

Potential network impacts were as follows:

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

- No problems identified

Multiple Facility Contingency

(Double Circuit Tower Line, Line with Failed Breaker and Bus Fault contingencies for the full energy output)

- No problems identified.

Short Circuit

- No problems identified.

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

- None

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. Network Impacts, initially caused by the addition of this project generation)

- None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

(Summary form of Cost allocation for transmission lines and transformers will be inserted here if any)

- None