

***PJM Generator Interconnection Request  
Queue #V3-009  
Desoto-Tanners Creek 345 kV  
Facilities Study***

**March 2016**

## **V3-009 Desoto – Tanners Creek 345 kV Facilities Study Report**

### **A. Facilities Study Summary**

#### **1. Project Description**

EDP Renewables north America LLC (EDPR) proposes to install PJM Project #V3-009, a 200 MW generating facility comprised of 111 – 1.8 MW wind turbine generators connecting to the American Electric Power (AEP) Desoto – Tanners Creek 345 kV circuit at the substation constructed for the U2-090 IPP (Losantville Station).

#### **2. Amendments/Changes to the Impact Study Report**

- The impact study was a combined report for V3-007, V3-008, and V3-009. The facilities studies have been requested as separate reports.
- Studies documented in the Impact Study Report pre-date implementation of a Light Load criteria in the RTEP process
- Studies have been re-tooled to reflect withdrawals or reductions of projects in earlier queues.

#### **3. Interconnection Customer Schedule**

EDPR has proposed the following schedule for their collector station:

- Receive back feed from AEP: May 17, 2019
- Commercial Operation Date: October 31, 2019

#### **4. Scope of Customer's Work**

- Complete generation collector station including step up transformers.
- 345 kV connection from generation station to switching station.
- Dual fiber optic tie between stations.
- Station communications lines.

## **5. Description of Transmission Owner Facilities Included in the Facilities Study**

### **Direct Connection Work**

- Install one 345 kV breaker to Losantville station to accommodate the connection for V3-009. (Network Upgrade n4780)
- Install 345 kV metering to the new line exit for the V3-009 connection. (Network Upgrade n4781)

### **Network Upgrade Work**

- None required.

## **6. Total Cost of Transmission Owner Facilities Included in the Facilities Study:**

Direct Connection facilities	\$1,183,400
Network Upgrade facilities	<u>\$0</u>
Total Cost	\$1,183,400

## **7. Summary of Schedule Milestones for Completion of Transmission Owner Work Included in Facilities Study:**

May 17, 2019      Interconnection Station ready for service

## **B. Transmission Owner Facilities Study Results**

### **1. Transmission Lines – New**

None.

### **2. Transmission Lines – Upgrades**

None.

### **3. Substation Facilities – New**

#### **Losantville 345 kV Station**

Add one 345 kV breaker to create a new line connection for the V3-009 IPP project. Add 345 kV metering for the new line exit within the Losantville station footprint.

### **4. Substation Facilities – Upgrades**

None

## 5. Metering & Communications

### Physical Requirements

- Install (1) - Steel -3PH Metering steel structure per CT/PT/SA application.
- Install (1) - Foundation -Metering steel structure foundation.
- Install Control Cable- run thru new installed trench.

### Metering Equipment

Use standards SS-497001, DM 51.01 to add PT and CT & primary and backup SEL734

- Install (3) - Free standing CTs and PTs between wavetrap and the bus.
- Install (3) - 84kV MCOV Station Class Arrester.

The metering requirements are published in: “AEP Metering and Telemetry Requirements for AEP Transmission Customers” (document SS-490011).

Communication requirements are published in the “AEP SCADA RTU Requirements at Transmission Interconnection Facilities” (document SS-500000).

## 6. Environmental, Real Estate and Permitting Issues

Since the interconnection location is proposed at an existing station, no additional permitting issues are expected.

## 7. Summary of Results of Study

### Cost Estimates for AEP

	<b>Network Upgrade Number</b>	<b>Engineering</b>	<b>Material</b>	<b>Construction</b>	<b>Misc.</b>	<b>Total</b>
Losantville	n4779	\$27,400	\$414,900	\$123,100	\$276,300	\$841,700
Metering	n4780	\$21,800	\$135,300	\$63,200	\$121,400	\$341,700
<b>Total</b>		<b>\$49,200</b>	<b>\$550,200</b>	<b>\$186,300</b>	<b>\$397,700</b>	<b>\$1,183,400</b>

### Schedule

January 9, 2018	Station design begins
March 6, 2018	Material ordered
August 7, 2018	Station construction begins
April 9, 2019	Outage begins
May 17, 2019	Outage ends

### Assumptions

System conditions allow scheduled outages to occur.  
ISA executed by March 1, 2016.

## **8. Information Required for Interconnection Service Agreement**

### Direct Interconnection Cost Breakdown

Direct Material -	\$550,200
Direct Labor -	\$235,500
Indirect Material -	\$45,500
Indirect Labor -	<u>\$352,200</u>
Total	\$1,183,400

### Network Upgrade Cost Breakdown

None.





Figure 1

# Losantville Station Desoto-Tanners Creek 345 kV



**Figure 2**