



Generation Interconnection

Queue Project AE1-147

Bellefonte 46 KV

Feasibility Study Report

Capacity : 12 MW / Energy : 20 MW

January, 2019

General

Interconnection Customer has proposed a new solar generating facility located in Centre County, Pennsylvania. The installed facilities will have a total capability of 20 MW with 12 MW of this output being recognized by PJM as Capacity. The proposed in-service date for this project is December 31, 2021. **This study does not imply a West Penn Power Company (Transmission Owner or WPP) commitment to this in-service date.**

Point of Interconnection

The AE1-147 solar facility will interconnect with the WPP subtransmission system by tapping the 46 kV radial line between Bush Junction substation and the National Gypsum metered load.

Network Impacts

The Queue Project AE1-147 was evaluated as a 20 MW (Capacity 12 MW) injection at Bush Junction 46 KV substation in the APS zone (FirstEnergy, West Penn Power area). Project AE1-147 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AE1-138 was studied with a commercial probability of 53%. Potential network impacts were as follows:

Primary POI: Summer Peak Analysis – 2022

Generator Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

None

Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

Short Circuit

None. (No overdutied circuit breakers identified)

Delivery of Energy Portion of Interconnection Request

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Only the most severely overloaded conditions are listed. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed, which will study all overload conditions associated with the overloaded element(s) identified.

None

Primary POI: System Reinforcements:

Short Circuit

None.

Stability and Reactive Power Requirement

Will be determined at a later study stages.

Summer Peak Load Flow Analysis Reinforcements

New System Reinforcements

(Upgrades required to mitigate reliability criteria violations, i.e. Network Impacts, initially caused by the addition of this project generation)

None

Contribution to Previously Identified System Reinforcements

(Overloads initially caused by prior Queue positions with additional contribution to overloading by this project. This project may have a % allocation cost responsibility which will be calculated and reported for the Impact Study)

None