



**Generation Interconnection
Feasibility Study Report
for
Queue Project AF2-398
NECESSITY-DINNERBELL 12.47 KV
1.9 MW Capacity / 3 MW Energy**

July 2020

Table of Contents

1	Introduction.....	4
2	Preface.....	4
3	General	5
4	Point of Interconnection.....	6
4.1	Primary POI:.....	6
4.2	Secondary POI:	6
5	Cost Summary	6
6	Transmission Owner Scope of Work.....	8
7	Schedule.....	9
8	Transmission Owner Analysis.....	9
8.1	Power Flow Analysis	9
8.2	Stability Analysis	9
8.3	Voltage Control	9
8.4	Short Circuit and Dynamics Analysis.....	10
9	Interconnection Customer Requirements.....	10
9.1	Compliance Issues	10
10	Revenue Metering and SCADA Requirements	11
10.1	PJM Requirements	11
10.2	Meteorological Data Reporting Requirements	11
10.3	Interconnected Transmission Owner Requirements.....	11
11	Summer Peak - Load Flow Analysis	12
11.1	Generation Deliverability	13
11.2	Multiple Facility Contingency	13
11.3	Contribution to Previously Identified Overloads.....	13
11.4	Potential Congestion due to Local Energy Deliverability.....	13
11.5	System Reinforcements.....	14
11.6	Flow Gate Details.....	14
11.7	Queue Dependencies	14
11.8	Contingency Descriptions.....	15
12	Short Circuit Analysis.....	15
13	Affected Systems	15

13.1	NYISO	15
------	-------------	----

1 Introduction

This Feasibility Study has been prepared in accordance with the PJM Open Access Transmission Tariff, 36.2, as well as the Feasibility Study Agreement between the Interconnection Customer (IC), and PJM Interconnection, LLC (PJM), Transmission Provider (TP). The Interconnected Transmission Owner (ITO) is West Penn Power Company (WPP) (APS).

2 Preface

The intent of the feasibility study is to determine a plan, with ballpark cost and construction time estimates, to connect the subject generation to the PJM network at a location specified by the Interconnection Customer. The Interconnection Customer may request the interconnection of generation as a capacity resource or as an energy-only resource. As a requirement for interconnection, the Interconnection Customer may be responsible for the cost of constructing: (1) Direct Connections, which are new facilities and/or facilities upgrades needed to connect the generator to the PJM network, and (2) Network Upgrades, which are facility additions, or upgrades to existing facilities, that are needed to maintain the reliability of the PJM system.

In some instances a generator interconnection may not be responsible for 100% of the identified network upgrade cost because other transmission network uses, e.g. another generation interconnection, may also contribute to the need for the same network reinforcement. Cost allocation rules for network upgrades can be found in PJM Manual 14A, Attachment B. The possibility of sharing the reinforcement costs with other projects may be identified in the feasibility study, but the actual allocation will be deferred until the impact study is performed.

The Interconnection Customer seeking to interconnect a wind or solar generation facility shall maintain meteorological data facilities as well as provide that meteorological data which is required per Schedule H to the Interconnection Service Agreement and Section 8 of Manual 14D.

The Feasibility Study estimates do not include the feasibility, cost, or time required to obtain property rights and permits for construction of the required facilities. The project developer is responsible for the right of way, real estate, and construction permit issues. For properties currently owned by Transmission Owners, the costs may be included in the study.

3 General

The Interconnection Customer (IC), has proposed a Solar generating facility located in Fayette County, Pennsylvania. The installed facilities will have a total capability of 3 MW with 1.9 MW of this output being recognized by PJM as Capacity. The proposed in-service date for this project is December 31, 2021. This study does not imply a TO commitment to this in-service date.

Queue Number	AF2-398
Project Name	NECESSITY-DINNERBELL 12.47 KV
State	Pennsylvania
County	Fayette
Transmission Owner	APS (West Penn Power)
MFO	3
MWE	3
MWC	1.9
Fuel	Solar
Basecase Study Year	2023

Any new service customers who can feasibly be commercially operable prior to June 1st of the basecase study year are required to request interim deliverability analysis.

4 Point of Interconnection

The POI for the Project will be accomplished by installing phase additions to an existing single phase line and reconductoring that line to either POI on the Dinnerbell 12 kV circuit out of Necessity substation. The interconnection of the project at either Primary POI or Secondary POI will be accomplished by tapping the Dinnerbell 12 kV line and constructing a one span tap to a 12.47kV metering package.

4.1 Primary POI:

Near pole 430813-WP14. The distribution line tap will be located approximately 2.1 miles from Necessity substation. This will require phase additions and reconductoring of approximately 7400' of existing single phase.

4.2 Secondary POI:

Near pole 324569-WP14. The distribution line tap will be located approximately 0.98 miles from Necessity substation. This will require phase additions and reconductoring of approximately 3500' of existing single phase. No physical interconnection costs are provided for the secondary POI, only analysis results are provided. If the customer chooses the secondary POI for the System Impact phase, then the costs will be provided at that time.

The analysis results for the primary and secondary POI are the same as the project was studied at the same electrical point in the model for each location.

The IC will be responsible for acquiring all easements, properties and permits that may be required to construct both the new 12kV line and the associated attachment facilities. A summary of the Project direct connection facilities that will be required for the POI and their estimated costs are shown in this document.

5 Cost Summary

The AF2-398 project will be responsible for the following costs for the Primary POI connection:

Description	Total Cost
Total Physical Interconnection Costs	\$458,969
Total System Network Upgrade Costs	\$0
Total Costs	\$458,969

This cost excludes a Federal Income Tax Gross Up charges. This tax may or may not be charged based on whether this project meets the eligibility requirements of IRS Notice 88-129. If at a future date it is determined that the Federal Income Tax Gross charge is required, the Transmission Owner shall be reimbursed by the Interconnection Customer for such taxes.

Note that all cost estimates contained in this document were produced with an engineering design based on current information. The IC will be responsible for the actual cost of the direct connection that is implemented.

West Penn Power herein reserves the right to return to any issues in this document and, upon appropriate justification, request additional monies to complete any reinforcements to the distribution system.

Cost allocations for any System Upgrades will be provided in the System Impact Study Report.

6 Transmission Owner Scope of Work

Tap near pole 430813-WP14. The distribution line tap will be located approximately 2.1 miles from Necessity substation. This will require phase additions and reconductoring of approximately 7400' of existing single phase.

The total physical interconnection costs is given in the table below:

Description	Total Cost
Convert approximately 7400' of existing single phase line to three-phase using 3/0 AAAC conductor to a 12.47 kV metering package. Upgrade fuse size at pole 202561.	\$456,969
Change the LTC setting at and update settings on 560WE recloser at Necessity SS	\$2,000
Total Physical Interconnection Costs	\$458,969

7 Schedule

Based on the scope of work for interconnection facilities, it is expected to take a minimum of **12 months** after the signing of an Interconnection Agreement and construction kickoff call to complete the installation. This assumes that there will be no environmental issues with any of the new properties associated with this project, that there will be no delays in acquiring the necessary permits for implementing the defined direct connection and network upgrades, and that all distribution system outages will be allowed when requested.

8 Transmission Owner Analysis

8.1 Power Flow Analysis

A Power Flow study was conducted to determine the reliability impact of the proposed Project on the West Penn Power distribution line and substation. This included the performance of a contingency analysis to identify any facility overload or voltage condition that violates the FE Planning Criteria. Any such violation that is either directly attributable to this project or for which it will have a shared responsibility is included in this report with a least cost plan identified to mitigate them.

The CYME Power Flow Analysis was performed using expected 2023 summer/winter peak load base case. The analysis performed by West Penn Power used a detailed representation of the West Penn Power 138kV and 12kV systems. A simulation of all possible contingencies in the area of the Project were analyzed to test for criteria compliance. After review, the solar system posed overload and voltage problems to the circuit under either a maximum or minimum output generation. However, these conditions can be mitigated with appropriate action. There was also no expected flow onto the 138kV source due to the normal loading on the transformer.

Results of the West Penn Power Flow Analysis shows one location where there is a FE Planning Criteria thermal violation directly attributable to the Project. The criteria violation occurs at a fuse pole that would be providing service to the solar site. These are currently 100T fuses and would be changed to 140T fuses.

8.2 Stability Analysis

A dynamic stability analysis was completed by FE. There were no stability concerns identified for the system.

8.3 Voltage Control

Since this installation will have the ability to change load instantly based on the operation of the PV system the voltage fluctuation was studied during the normal operation of the system. The voltage fluctuation was studied using several combinations of the solar generation and load level. The maximum instantaneous change expected on the system at both the substation bus and POI is acceptable and the voltage regulator will correct the load changes within 1 minute to insure required steady state voltage.

8.4 Short Circuit and Dynamics Analysis

A short circuit analysis has been performed by West Penn Power. The findings show that no equipment is over-dutied with the addition of the Project. Since the inverter limits the fault current to 1 time the rating, all protective devices are acceptable.

9 Interconnection Customer Requirements

The IC will be responsible for meeting all criteria as specified in the applicable sections of the Customer Interconnection Guide 3 Phase document.

9.1 Compliance Issues

The IC will be responsible for meeting all FE criteria as defined in the FE Requirements for Distribution Connected Facilities¹.

The IC must meet all PJM and NERC reliability criteria and operating procedures required for standards compliance.

West Penn Power requests a copy of relay settings to insure they meet the requirements of Section 6.0 of the Customer Interconnection Guide.

West Penn Power Regional Engineering requires a transformer configuration of wye grounded – wye grounded connection unless determined otherwise by West Penn Power Regional Engineering.

Section 7.1 of the Customer Interconnection Guide requires access via SCADA and will be required as spelled out as described in Section 7.1 of the Customer Interconnection Guide.

Section 9.0 of the Customer Interconnection Guide requires either pre-certification or acceptance testing to ensure compliance with IEEE 1547.1 Standard Conformance Test Procedure for Equipment Interconnecting Distributed Resources with Electric Power Systems. When Acceptance Testing is required, it must be performed by a third-party testing organization. West Penn Power must be notified of when the testing is to occur and have the option to attend.

In addition to the IC requirements identified in this report, the customer's interconnection must conform with all the requirements identified in IEEE Std. 1547-2018, unless a requirement has been specifically waived or altered, in writing, by The Company. The IC is advised to review all of the interconnection guidance provided in the document titled, Customer Guide for Retail Interconnection of Electric Power Producing and Storage Facilities, Commercial/Industrial located on the FirstEnergy/Company website for any additional requirements beyond those provided in IEEE-1547-2018. This guide is applicable to wholesale or retail interconnections.

10 Revenue Metering and SCADA Requirements

10.1 PJM Requirements

The Interconnection Customer will be required to install equipment necessary to provide Revenue Metering (KWH, KVARH) and real time data (KW, KVAR) for IC's generating Resource. See PJM Manuals M-01 and M-14D, and PJM Tariff Section 8 of Attachment O.

10.2 Meteorological Data Reporting Requirements

The solar generation facility shall provide the Transmission Provider with site-specific meteorological data including:

- Back Panel temperature (Fahrenheit)
- Irradiance (Watts/meter²)
- Ambient air temperature (Fahrenheit) – (Accepted, not required)
- Wind speed (meters/second) – (Accepted, not required)

10.3 Interconnected Transmission Owner Requirements

The IC will be required to comply with all Interconnected Transmission Owner's revenue metering requirements for generation interconnection customers located at the following link:

<http://www.pjm.com/planning/design-engineering/to-tech-standards/>

11 Summer Peak - Load Flow Analysis

The Queue Project AF2-398 was evaluated as a 3.0 MW (Capacity 1.9 MW) injection at the Necessity 138 kV substation in the APS area. Project AF2-398 was evaluated for compliance with applicable reliability planning criteria (PJM, NERC, NERC Regional Reliability Councils, and Transmission Owners). Project AF2-398 was studied with a commercial probability of 53.0 %. Potential network impacts were as follows:

Note: The Primary and Secondary POI were studied at same electrical point in the model so they both have the same analysis results.

11.1 Generation Deliverability

(Single or N-1 contingencies for the Capacity portion only of the interconnection)

None

11.2 Multiple Facility Contingency

(Double Circuit Tower Line, Fault with a Stuck Breaker, and Bus Fault contingencies for the full energy output)

None

11.3 Contribution to Previously Identified Overloads

(This project contributes to the following contingency overloads, i.e. "Network Impacts", identified for earlier generation or transmission interconnection projects in the PJM Queue)

None

11.4 Potential Congestion due to Local Energy Deliverability

PJM also studied the delivery of the energy portion of this interconnection request. Any problems identified below are likely to result in operational restrictions to the project under study. The developer can proceed with network upgrades to eliminate the operational restriction at their discretion by submitting a Merchant Transmission Interconnection request.

Note: Only the most severely overloaded conditions are listed below. There is no guarantee of full delivery of energy for this project by fixing only the conditions listed in this section. With a Transmission Interconnection Request, a subsequent analysis will be performed which shall study all overload conditions associated with the overloaded element(s) identified.

None

11.5 System Reinforcements

None

11.6 Flow Gate Details

The following indices contain additional information about each facility presented in the body of the report. For each index, a description of the flowgate and its contingency was included for convenience. The intent of the indices is to provide more details on which projects/generators have contributions to the flowgate in question. All New Service Queue Requests, through the end of the Queue under study, that are contributors to a flowgate will be listed in the indices. Please note that there may be contributors that are subsequently queued after the queue under study that are not listed in the indices. Although this information is not used "as is" for cost allocation purposes, it can be used to gage the impact of other projects/generators. It should be noted the project/generator MW contributions presented in the body of the report are Full MW Impact contributions which are also noted in the indices column named "Full MW Impact", whereas the loading percentages reported in the body of the report, take into consideration the PJM Generator Deliverability Test rules such as commercial probability of each project as well as the ramping impact of "Adder" contributions. The MW Impact found and used in the analysis is shown in the indices column named "Gendeliv MW Impact".

None

—

11.7 Queue Dependencies

The Queue Projects below are listed in one or more indices for the overloads identified in your report. These projects contribute to the loading of the overloaded facilities identified in your report. The percent overload of a facility and cost allocation you may have towards a particular reinforcement could vary depending on the action of these earlier projects. The status of each project at the time of the analysis is presented in the table. This list may change as earlier projects withdraw or modify their requests.

None

11.8 Contingency Descriptions

None

12 Short Circuit Analysis

Short Circuit analysis to be performed in the System Impact phase.

13 Affected Systems

13.1 NYISO

NYISO Impacts to be determined during later study phases (as applicable).